

Appendix E

Fluvial Geomorphology

Fluvial Geomorphology Study Fruitland-Winona Block 1 Servicing Strategy City of Hamilton, Ontario



Prepared for: Urbantech Consulting 2030 Bristol Circle, Suite 105 Oakville, Ontario L6H 0H2

March 8, 2024 PN21043



Report Prepared by: GEO Morphix Ltd.

36 Main Street North

PO Box 205

Campbellville, ON LOP 1B0

Report Title: Fluvial Geomorphology Study - Fruitland-Winona Block 1

Servicing Strategy

Project Number: PN21043

Status: Final Version: 1.2

Prepared by: Lindsay Davis, M.Sc., P.Geo, CAN-CISEC,

Approved by: Paul Villard, Ph.D., P.Geo., CAN-CISEC, EP, CERP

Approval Date: March 8, 2024

Table of Contents

1	Intro	oduction1				
2	Back	ground Review	1			
	2.1	Background Review	1			
	2.2	Proposed Site Conditions	2			
	2.3	Surficial Geology	2			
3	Wate	Watercourse Characteristics				
	3.1	Reach Delineation	2			
	3.2	Field Observations	3			
4	Erosion Threshold Analysis5					
	4.1	Methods	6			
	4.2	Results	6			
5	Post-	and Pre-Development Erosion Exceedance Analysis	7			
	5.1	Methods	8			
	5.2	Results	9			
6	Conc	eptual Channel Design	11			
	6.1	Channel Planform	12			
	6.2	Bankfull Channel	13			
	6.3	Fish Passage	15			
	6.4	Channel Corridor	15			
		6.4.1 Corridor Sizing	15			
	6.5	Habitat Restoration	16			
	6.6	Wetland Replication	17			
	6.7	Stormwater Management Outlet Design	17			
7	Reco	mmendations for Detailed Design	18			
8	Post-	Construction Monitoring Recommendations	18			
9	Sumr	mary and Recommendations	18			
10	Refer	ences	20			
List	of T	ables				
Table	1. Re	ach characteristics summary	3			
Table	2: Re	ach classifications summary	5			

Fable 3: Bankfull conditions and erosion threshold calculation parameters for the Watercours Reach WC5	
Table 4: Results from the pre- to post-development erosion exceedance analysis for Reach W	
Table 5: Bankfull parameters for the proposed channel	. 15
Fable 6: Meander belt width estimate for design Reach WC5	. 16
Appendices	
Appendix A Reach Mapping	А
Appendix B Photo Record	В
Appendix C Field Observations	C
Appendix D Detailed Assessment Summary	D
Appendix E Erosion Modelling Hydrographs	E

1 Introduction

GEO Morphix Ltd. was retained by Urbantech Consulting to complete a fluvial geomorphological assessment for the receiving watercourse associated with the proposed Stormwater Management (SWM) facilities within the Block 1 area. Two watercourse features traverse through the Block 1 property and are identified as **Watercourse 5** (**WC5**) and **Watercourse 6** (**WC6**). To support future development plans, it is understood that **WC5** is proposed to be realigned and engineered, while **WC6** is proposed to remain in its natural state. Further, **WC5** is proposed to receive outflows from a SWM pond (Pond 1). An erosion assessment was assessment was complete for **WC5** to to determine if exacerbated rates of erosion could be anticipated within the watercourse as a consequence of development.

The following activities were completed as part of the fluvial geomorphological assessment:

- Review of pertinent background information, including conceptual development plans and previous reporting on the subject watercourse
- Desktop analysis to determine the potential zone of impact, which is the extent of the channel to be addressed
- Delineation and confirmation of stream reaches in the study area
- Rapid geomorphological field assessment to determine the stability of the receiving watercourse
- Completion of a detailed geomorphic assessment downstream of the proposed outlet locations, the primary objective of which is to support the critical flow or erosion threshold
- Determine erosion thresholds for the receiving watercourse
- Complete an erosion exceedance exercise comparing pre- and post-development hydrology provided by Urbantech Consulting (2021)

The following activities were completed in support of the proposed conceptual corridor realignments:

- Calculate bankfull channel dimensions for the proposed corridor alignments
- Channel planform, profile, and detail drawings
- Determine meander belt width for the low flow channel to ensure it can be accommodated within designed corridors
- Provide recommendations for wetland recreation within designed corridors

2 Background Review

2.1 Background Review

The Block 1 property is located in the western end of Stoney Creek, Ontario. The property is bound by Barton Road to the north, Fruitland Road to the west, Highway 8 to the south, and an agricultural property to the east. Existing land use throughout the property includes agricultural, rural residential, and commercial. Agricultural land-use is dominant throughout the interior of the subject property. However, these fields are no longer actively cultivated. Residential and commercial lands are present along the margins of the property.

Two watercourses, **Watercourse 5 (WC5)** and **Watercourse 6 (WC6)**, traverse the property, flowing in a south-to-north direction towards Lake Ontario. **WC5** enters the subject lands through

a culvert beneath Fruitland Road and runs parallel to the road on the western edge of the property. **WC5** passes through a short culvert crossing, associated with the existing commercial building in the northwest corner of the property, before exiting the subject property though a culvert under Barton Road. **WC6** flows into the property through a culvert passing under Highway 8. Flows travel north, parallel to Jones Road, and exits the property through a culvert passing beneath Barton Road.

A map of the study area is provided in **Appendix A.**

2.2 Proposed Site Conditions

The proposed development for Block 1 consists mainly of low- and medium-density residential units, with a community park, an elementary school, and some commercial lands. A 40 m wide channel block is proposed for **WC5**, with a portion of the channel set to be realigned within it. Three stormwater management (SWM) ponds are proposed within the property, with outlets discharging into either **WC5** or **WC6**. Of these, Pond 1 will discharge into **WC5** approximately 180 upstream of the Barton Street Culvert. Consequently, the channel section spanning from the Pond 1 outlet to the Barton Street culvert defines the zone of impact for the erosion assessment. The section spanning from Fruitland Road to the approximate outlet location is what is proposed to be realigned.

2.3 Surficial Geology

Channel morphodynamics are largely governed by the flow regime and the availability and type of sediments (i.e., surficial geology) within the stream corridor. These factors are explored as they not only offer insight into existing conditions, but also potential changes that could be expected in the future as they relate to a proposed activity. Understanding local surficial geology is important for determining appropriate erosion thresholds, as the stability of the channel banks and bed is dependent on the composition of soils, sediment, and underlying parent materials (MNR, 2002).

The Block 1 property resides within Iroquois Plain physiographic region (Chapman and Putnam, 1984). This region extends from the shores of Lake Ontario up to the base of the Niagara escarpment, and is characterized by heavy-textured, low-permeability soil derived from the shales of the underlying Queenston Formation. Broad gravel ridge formations exist from Stoney Creek to Hamilton, in which loams have developed with improved drainage. The surficial geology throughout the site is characterized entirely by the Paleozoic bedrock shales of the Queenston Formation (OGS, 2010).

3 Watercourse Characteristics

3.1 Reach Delineation

Reaches are homogeneous segments of channel used in geomorphological investigations. Reaches are divided as such because they are expected to have similar inputs and outputs in terms of sediments and discharge. They are also expected to react similarly throughout to flow events and other stressors. They are studied semi-independently as each is expected to function in a manner that is at least slightly different from adjoining reaches. This allows for a meaningful

characterization of a watercourse as the aggregate of reaches, or an understanding of a particular reach, for example, as it relates to a proposed activity.

Reaches are delineated based on changes in the following:

- Channel planform
- Channel gradient
- Physiography
- Land cover (land use or vegetation)
- Flow, due to tributary inputs
- Soil type and surficial geology
- Certain types of channel modifications by humans

This follows scientifically defensible methodology proposed by Montgomery and Buffington (1997), Richards et al. (1997), and the Toronto and Region Conservation Authority (2004).

Reaches are first delineated as a desktop exercise using available data and information such as aerial photography, topographic maps, geology information and physiography maps. The results are then verified in the field.

The existing reach delineation was adopted for this assessment, where a single reach (**WC5**) was delineated along **Watercourse 5** within the bounds of the property. This delineation was confirmed during the site visits described Section 3.2, and no additional reach breaks were identified. **Watercourse 6** was not assessed in this report, as it resides outside the zone of impact identified for scope of this assessment.

3.2 Field Observations

Rapid and detailed field assessments were completed as part of this study on August 19^{th} , 2021 and January 31^{st} , 2024. Photographs from the field assessments are provided in **Appendix B**, rapid field observations are provided in **Appendix C**, and the detailed assessment summary is provided in **Appendix D** for reference. A summary of the general observations characterizing the delineated reaches is presented in **Table 1**.

Table 1. Reach characteristics summary

Reach Name	Date Visited	Avg. Bankfull Width (m)	Avg. Bankfull Depth (m)	Riffle Substrate	Pool Substrate	Dominant Riparian Condition	Notes
WC5	2021-08-19	3.64	0.34	Clay	Clay	Established trees, shrubs	Straight channel with uniform trapezoidal cross- section, minimal geomorphic activity noted

Reach **WC5** is a straight, trapezoidal channel with little to no observable geomorphic activity or geomorphic unit development. The channel was likely straightened as part of the prior agricultural activities within the block. Pooled water was present in the reach during the assessment, but flows were imperceptible due to the low channel gradient. The bed and banks are comprised of a dense,

cohesive silty-clay. Banks are well-rooted from the established trees and shrubs that inhabit the riparian corridor.

Rapid Assessments

Rapid field assessments were completed for each of the identified reaches of the receiving watercourse. The rapid assessments were completed to identify the dominant local geomorphic processes, document stream health, and to identify any areas of concern regarding erosion or instability. This included the following observations for each reach:

- Characterization of stream form, process, and evolution using the Rapid Geomorphological Assessment (RGA) (MOE, 2003; VANR, 2007), which evaluates degradation, aggradation, widening, and planimetric form adjustment at the reach scale
- Assessment of the ecological function of the watercourse using the Rapid Stream Assessment Technique (RSAT) (Galli, 1996), which evaluates stream health based on a number of biological indicators
- Stream classification following a modified Downs (1995) and a modified Brierley and Fryirs (2005) River Styles Classification approach which evaluate the magnitude and potential for channel instability and indicate dominant sediment loads, respectively
- Instream estimates of bankfull channel geometry
- Bed and bank material composition and structure
- Georeferenced photographs to document the location of all observed erosion and infrastructure

Channel instability was objectively quantified through the application of the Ontario Ministry of the Environment's (MOE, 2003) Rapid Geomorphic Assessment (RGA). Observations were quantified using an index that identifies channel sensitivity based on evidence of aggradation, degradation, channel widening, and planimetric adjustment. The index produces values that indicate whether the channel is *stable/in regime* (score <0.20), *stressed/transitional* (score 0.21-0.40) or *adjusting* (score >0.41).

The Rapid Stream Assessment Technique (RSAT) was also employed to provide a broader view of the system and consider the ecological functioning of the watercourse (Galli, 1996). Observations were made of channel stability, channel scouring or sediment deposition, instream and riparian habitats, and water quality. The RSAT score ranks the channel as maintaining a poor (<13), fair (13-24), good (25-34) or excellent (35-42) degree of stream health.

The tributary was classified according to a modified Downs (1995) Channel Evolution Model, which describes successional stages of a channel as a result of a perturbation, namely hydromodification. Understanding the current stage of the system is beneficial as this allows one to predict how the channel will continue to evolve, or respond to an alteration to the system.

The River Styles Framework (Brierley and Fryirs, 2005) provides a geomorphic approach to examining river character, behaviour, condition, and recovery potential through the identification of the Geomorphic Process Zone. Geomorphic attributes are assessed, larger scale interactions between zones are analyzed, and historical data are studies in order to understand the historical evolution and future trajectories of those reaches. This ultimately provides a physical template for river management. A modified classification approach was applied to the study reaches.

A summary of the reach classifications and rapid assessment scores is provided in Table 2.

Table 2: Reach classifications summary

Reach	Date	RGA	Dominant	RSAT	Downs Model	River Styles
Name	Visited	Score	Process	Score	Classification	Framework
WC5	2021-08-19	0.14	Widening	28	`m' – Lateral migration (initiating)	

Reach **WC5** displayed minimal evidence of instability or erosion. This was reflected by the RGA score of 0.14, indicating a relatively stable channel. The dominant geomorphic process identified was widening, as it scored highest of the four indices in the RGA. **WC5** scored 28 on the RSAT, indicating an acceptable level of stream health. The reach was classified as a suspended load dominated, straight channel under the River Styles Framework (Brierley and Fryirs, 2005). Under the Downs (1995) model, the initiation of lateral migration was identified as the dominant channel forming mechanism.

Detailed Geomorphological Assessments

The detailed assessment, used to inform the erosion threshold analysis, was completed on reach **WC5** on August 19th, 2021. The downstream portion of reach **WC5** was selected for the detailed assessment, as it is situated downstream of the proposed outlet for Pond 1 and will receive discharges originating from the site. Activities completed for the detailed assessment included the following:

- Long-profile survey of the channel centre line
- Eight detailed cross-sectional surveys of the watercourse
- Detailed instream measurements at each cross-section location including bankfull channel geometry, riparian conditions, bank material, bank height/angle, and bank root density
- Bed material sampling at each cross-section following a modified Wolman's (1954) Pebble Count Technique or substrate sample
- Velocity and discharge measurements at select representative cross-sections

The resulting measured channel parameters are outlining **Table 3**, and a summary of the detailed assessment results is provided in **Appendix D**.

4 Erosion Threshold Analysis

Erosion thresholds are used to determine the magnitude of flow required to potentially entrain and transport bed and/or bank material. As such, they are used to inform erosion mitigation strategies in channels influenced by conceptual flow and stormwater management plans.

Erosion thresholds were determined from detailed field observations of reach **WC5**. The erosion threshold is the theoretical point, typically expressed as a critical discharge or shear stress, at which entrainment of sediment would occur based on bed and bank materials. Due to variability between bed and bank composition and structure, erosion thresholds are determined for both bed and bank materials. The lower of the bed and bank erosion thresholds is adopted, as it provides the more conservative and limiting estimate.

Threshold targets are determined using different methods that are dependent on channel and sediment characteristics. For example, thresholds for non-cohesive sediments are commonly estimated using a shear stress approach, similar to that of Miller et al. (1977), which is based on a modified Shield's curve. A velocity approach could also be applied, such as that described by Komar (1987). For cohesive materials, empirically derived values such as those compiled by Fischenich (2001), Chow (1959) or Julien (1998), could be applied.

4.1 Methods

An erosion threshold is quantified based on the bed and bank materials and local channel geometry, in the form of a critical discharge. Theoretically, above this discharge, entrainment and transport of sediment can occur. To determine this discharge, the velocity, U is calculated at various depths for a representative cross section until the average velocity in the cross section slightly exceeds the critical velocity of the bed material. The velocity is determined using a Manning's approach, where the Manning's n value is visually estimated through a method described by Acrement and Schneider (1989) or calculated using Limerino's (1970) approach. The velocity is mathematically represented as:

$$U = \frac{1}{n}d^{2}/_{3}S^{1}/_{2}$$
 [Eq. 1]

where, d is depth of water, S is channel slope, and n is the Manning's roughness coefficient. The visual approach (Acrement and Schneider, 1989) was adopted for determining the Manning's roughness coefficient.

For the bank materials, following Chow (1959) in a simplified cross section, 75% of the bed shear stress acts on the channel banks. In a similar approach, the depth of flow is increased until the shear stress acting on the banks exceeds the resisting shear strength of the bank materials.

4.2 Results

Summarized results of the erosion threshold analysis are provided in **Table 3**. Reach **WC5** contains similar bed and bank materials, differentiated mainly by their level of compactness and water content. Bank material was identified as a non-colloidal silty loam with a corresponding critical velocity of 0.53 m/s. This critical velocity was adopted for the bed materials as well. As the bed material was more compact than the bank material, adopting the bank material critical velocity is a conservative approach with regards to erosion risk. Considering the material's level of cohesiveness, 0.53 m/s is a conservative estimate of the critical velocity itself.

Table 3: Bankfull conditions and erosion threshold calculation parameters for the Watercourse 5 Reach WC5

Channel mayamakay	Results by Reach				
Channel parameter	WC5				
Bankfull Conditions					
Average bankfull width (m)	3.64				
Average bankfull depth (m)	0.56				
Bankfull channel gradient (%)	0.76				
D ₅₀ (mm)	<2				
D ₈₄ (mm)	<2				
Manning's n roughness coefficient	0.038				
Bankfull discharge (m³/s)	1.31				
Bankfull velocity (m/s)	1.06				
Channel Bed Erosion Threshold					
Bed Material	Silty-clay loam, fairly compact				
Apparent shear stress acting on bed (N/m²)	7.30				
Critical velocity at the bed (m/s)*	0.53				
Critical discharge (m³/s)	0.116				
Channel Banks Erosion Threshold					
Bank Material	Silty-clay loam, compact				
Apparent shear stress acting on banks (N/m²)	10.59				
Critical velocity at the banks (m/s)*	0.53				
Critical discharge (m³/s)	0.290				
Limiting Critical discharge (m³/s)	0.116				

^{*} Criteria of Fischenich (2001) for non-colloidal silty loam

5 Post- and Pre-Development Erosion Exceedance Analysis

Using the results of the erosion threshold analysis and the provided hydrological modelling for post- and pre-development conditions, additional analyses regarding the impacts of SWM controls on potential erosion within the watercourses were completed with our own in-house model, based on four indices:

- 1) Cumulative time of exceedance
- 2) Number of exceedance events

- 3) Cumulative effective discharge
- 4) Cumulative effective work index (i.e. cumulative effective stream power)

These indices have been applied elsewhere in CH, TRCA, CVC, and other jurisdictions. They, as a product, provide an evaluation of the number of events, period of transport, and magnitude. We note that the most relevant indicator is the cumulative effective stream power.

Time of exceedance and number of exceedances can be simply calculated from the discharge record. For more relevant indicators, hydraulic information is required Our model applies the discharge to a characteristic cross-section. Using a Manning's approach, the discharge at each time step in the continuous hydrological model is converted into a velocity, depth of flow, shear stress, and/or stream power. These parameters are calculated based on field measurements of slope, cross section and channel roughness. This provides analysis that is site appropriate and specific.

The post- and pre-development hydrological modelling reflects changes to the hydrological regime resulting from SWM measures being implemented within the catchment. Continuous flow data was provided by Urbantech Consulting (2021) in 5-minute increments for synthetic 25 mm, 2-year, 5-year, 10-year, 25-year, 50-year, and 100-year Chicago storm events. The hydrological modeling was analyzed to calculate the aforementioned erosion indices to identify changes in the erosive potential within **WC5** following development.

5.1 Methods

To calculate work terms, both velocity and shear stress were calculated at each time step. Through an iterative process, water depth and velocity were calculated for each discharge passing through a representative cross-section. The cross-section is divided into floodplain and bankfull sections. The cross-section is further broken into panels. Velocity, U, is calculated for each panel using the Manning's approach. This is a conservative approach as it allows dissipation of flood energy in the floodplain.

The total discharge, Q_T at each time step is based on the summation of the discharge of all panels, Q_i , such that:

$$Q_{T} = \sum Q_i$$
 [Eq. 2]

 Q_i is discharge through a panel (which is set at 10 percent of the cross-section). Q_i is defined as:

$$Q_i = U_i w_i d_i ag{[Eq. 3]}$$

where, w_i and d_i are width and depth for each panel. The discharge for each panel was then summed to give a total discharge. This is more accurate than using average cross-sectional dimensions of a simple trapezoidal channel, as the bed is usually irregular, and a panel approach more accurately represents the true cross-sectional area.

For each event, the discharge is converted into a maximum depth and average velocity. The maximum depth is used to calculate a maximum bed shear stress, $\tau_{o_{\max}}$ based on:

$$au_{
m max} = d_{
m max}
ho g S_{
m bed}$$
 [Eq. 4]

where, d_{max} is the maximum water depth, ρ is water density, g is acceleration due to gravity, and S_{bed} is the channel bed slope.

Cumulative total work, ω_{tot} is defined as:

$$\omega_{\mathsf{tot}} = \sum \tau_{\mathsf{0}_{\mathsf{max}}} \,.\, U_{\mathsf{avg}} \,.\, \Delta t$$
 [Eq. 5]

where, U_{avg} is average velocity (Q_{tot}/A_{tot} , where A_{tot} is wetted area), while cumulative effective work index (ω_{eff}) is defined by:

$$\omega_{\text{eff}} = \sum \tau - \tau_{cr} \cdot U \cdot \Delta t, \omega < 0 = 0$$
 [Eq. 6]

where, τ_{cr} is the critical shear stress.

Time of exceedance t_{ex} defined as:

$$t_{\rm ex} = \sum \Delta t \ \text{for} (Q_T > Q_{\rm threshold})$$
 [Eq. 7]

where, $Q_{\text{threshold}}$ is the discharge at the erosion threshold.

5.2 Results

The full series of post- to pre-development hydrographs are included in **Appendix E**, and include the erosion threshold based on discharge, for reference. **Table 4** provides the results of the assessment based on the hydrographs provided by Urbantech Consulting (2021).

Table 4: Results from the post- and pre-development erosion exceedance analysis for Reach WC5

Simulation		CED (m³/s)	ი _{eff} (N/m²)	t _{ex} (hrs)
	(PRE)	0.95	16.49	3.25
25 mm	(POST)	0.98	15.04	3.92
	Change (%)	3.10%	-8.79%	20.51%
	(PRE)	6.45	135.52	15.00
2-year	(POST)	7.83	168.78	17.08
	Change (%)	21.29%	24.55%	13.89%
	(PRE)	12.18	280.67	18.42
5-year	(POST)	14.46	340.20	20.42
	Change (%)	18.73%	21.21%	10.86%
	(PRE)	16.45	376.81	20.25
10-year	(POST)	19.29	454.25	22.17
	Change (%)	17.28%	20.55%	9.47%
	(PRE)	22.44	497.47	22.33
25-year	(POST)	25.98	584.02	24.17
	Change (%)	15.77%	17.40%	8.21%
	(PRE)	26.77	574.64	23.58
50-year	(POST)	30.75	659.04	25.25
	Change (%)	14.89%	14.69%	7.07%
	(PRE)	31.27	648.04	24.67
100-year	(POST)	35.71	724.56	26.33
	Change (%)	14.19%	11.81%	6.76%

It is noted that the cumulative effective discharge (CED) and cumulative effective work index (ω_{eff}) are considered the most relevant erosion indices, as they reflect both the severity and duration of an exceedance event. Further, storms of moderate magnitudes and of relatively frequent recurrence typically exert the most influence on a given channel's geomorphic regime. Results from the 25 mm event and, to a lesser extent, the 2-year event are therefore the most relevant storm simulations in the context of evaluating erosion potential following hydrological regime changes.

For the 25 mm storm, the CED saw a minor increase of 3.10% from pre- to post-development hydrological conditions. The ω_{eff} decreased by 8.79% and the cumulative exceedance duration (tex) increased by 20.51%. For the 2-year event, the CED, ω_{eff} , and tex increased by 21.29%, 24.55%, and 13.89%, respectively. Increases in all indices were predicted for the larger storm events. The magnitude of these predicted increases consistently tapers off as storm magnitudes increase, reaching 14.19%, 11.81%, and 3.76% for the 100-year event CED, ω_{eff} , and tex, respectively.

The notable decrease in erosion potential predicted for the 25 mm event is expected to offset the moderate increases predicted for the larger, less frequent storms. Thus, the modelling results indicate that exacerbated rates of erosion resulting from development will not occur within reach **WC5**.

6 Conceptual Channel Design

As part of the Stoney Creek Urban Boundary Expansion (SCUBE) Phase 3, **WC5** was identified to be restored and realigned, which provides opportunity to replace the existing morphologically-limited channel with a naturalized riffle and pool typology, with cross sectional dimensions closer to that of a naturalized watercourse conveying similar flows. One goal of the natural channel design is to replace the existing degraded channel that has been impacted by past agricultural and development activities. A naturalized watercourse will offer significant improvements to channel form and function, per unit length.

The realignment and naturalization provide opportunities for improved riparian conditions and a well-developed bankfull channel with morphological variability. Improvement in morphology and function will provide additional benefits to sediment balance, floodplain storage, vegetation communities and terrestrial habitat features, aquatic habitat, edge impacts, water balance, fish passage and water quality.

The primary objectives of the design are to:

- Restore the physical form of the channel including planform and in-channel characteristics
- Ensure channel stability and function during low flow periods
- Create low-flow channel that accommodates the bankfull discharge to improve the function of the channel corridor and increase interactions with the floodplain
- Create a floodplain that includes interconnected wet meadow and linear wetland features of variable depth, shape, and hydroperiod
- Provide a mix of coarse and fine sediment sources throughout the low-flow channel and floodplain

- Enhance aquatic habitat for warmwater fish through the provision of a morphologically diverse channel with spatially varied flows
- Improve riparian habitat by installing woody plantings and dynamic floodplain features
- Mitigate potential hazards to the development as well as lands surrounding the development

Technical details are provided in subsequent sections to outline the approach used for channel sizing and habitat restoration.

6.1 Channel Planform

The initial channel planform layout will be created using the modelled radius of curvature value (Rc) as a guide. The radius of curvature (Rc) of meanders can be used to evaluate channel stability. For example, stable meanders typically exhibit larger Rc values as opposed to lower values that indicate increased channel bank erosion and avulsion. Bankfull width is often an appropriate indicator for this instability. Hickin and Nanson (1983) note that channel avulsions are common when meander Rc is approximately 1-2 times the channel bankfull width. For larger Rc (e.g., >5), the upstream limb of the meander will migrate more rapidly than the downstream limb (Hooke, 1975). Williams (1986) was used to derive values for the channel radius of curvature, using the following equation (Eq. 8):

$$Rc = 2.43 \times w$$
 [Eq. 8]

where *Rc* is the radius of curvature and *w* is the average bankfull width.

Empirical models derived by Hey and Thorne (1986) were followed to determine riffle spacing. Hey and Thorne's (1986) modelled values are often applied in larger watercourses. As such, multiple methods (Eq. 9-11) were considered in order to provide a range of riffle spacing values. These are:

$$Z = 6.31 \times w$$
 [Eq. 9]

$$Z = 9.1186 \times w^{0.8846}$$
 [Eq. 10]

$$Z = 7.36 \times w^{0.896} \times S^{-0.03}$$
 [Eq. 11]

where Z represents riffle spacing.

Stream power and unit stream power were calculated as a function of bankfull discharge and channel gradient (Eq. 12-13). Stream power values are important to determine the need for mitigating channel bank and bed erosion. Stream power is given by:

$$\Omega = \rho \times g \times d \times S$$
 [Eq. 12]

where ρ is the density of water (kg/m³), g is the acceleration due to gravity (m/s²), and Q and S are discharge (m³/s) and channel gradient, respectively.

Stream power per unit width (Eq. 13), is given by:

$$\omega = \frac{\Omega}{w}$$
 [Eq. 13]

where as before, Ω and w are stream power and bankfull width, respectively.

The final channel planform will be established through an iterative process. First, a cross section with defined bankfull geometry was developed to calculate parameters for the planform (i.e., radius of curvature). The cross section will then be further refined, and riffle and pool lengths will be determined based on channel gradient.

6.2 Bankfull Channel

The recommended restoration design focuses on a riffle and pool sequences. The riffle and pool sequences will provide significant improvements to not only the channel, as it essentially mimics a natural system, but also to aquatic habitat. In summary, the riffle-pool system offers numerous benefits, namely:

- · Channel bed relief for flow variability
- Water aeration in riffle sections
- Relatively quiescent flows in pool sections to provide refuge for fish during high flows
- Increased depths in pools to provide relatively cool water
- In-channel energy dissipation

Channel design dimensions are determined by bankfull discharge, as this represents what is generally referred to as the "channel-forming discharge" or the "dominant discharge". Several methods can be applied to select an appropriate bankfull discharge. Back calculation of discharge from a reference reach along with support from hydrological modelling is usually the most appropriate. Due to changes in hydrology likely to occur because of the proposed development on site, a discharge based on hydrological modelling was determined for **WC5** and then subsequently used to define channel bankfull geometry. The discharge used to size the bankfull channel was assumed to be equivalent to the modelled 2-year flow. As such, the bankfull discharge was defined as 1.40 m³/s, based on hydrological modelling provided by Urbantech Consulting Engineers (2021). Bankfull capacity for channels generally have a range from the 1- to 2-year return events. The bankfull channel geometries are provided for guidance for the design concept and can be further refined based on subsequent studies.

A simple Manning's approach was used to iteratively back-calculate bankfull dimensions for the proposed channel. Since pools are designed to contain ineffective space, this model over-predicts the amount of discharge that they convey. As such, the modelled values for the riffles give a better prediction of the channel's capacity. Average channel geometries, as well as anticipated bankfull conditions for the proposed channel, are provided in **Table 5**.

Table 5: Average bankfull parameters for the proposed channel

	Reach 1		
Channel parameter	Riffle	Pool	
Average bankfull width (m)	2.50	3.65	
Average bankfull depth (m)	0.32	0.39	
Maximum bankfull depth (m)	0.45	0.70	
Bankfull width-to-depth ratio	7.89	9.25	
Riffle gradient (%)	2.40	0.68	
Bankfull gradient (%)	0.68	0.68	
Average radius of curvature (m)	22		
Riffle-pool spacing (m)	8		
Manning's roughness coefficient, n	0.035	0.04	
Mean bankfull velocity (m/s)	1.77	0.97	
Bankfull discharge (m³/s) *	1.40 1.40		
Discharge to accommodate (m³/s)	1.40	1.40	
Tractive force at bankfull (N/m²)	106	47	
Stream power (W/m)	330	93	
Unit stream power (W/m²)	132	43	
Froude Number (unitless)	1.0	0.50	
Maximum grain size entrained (m) **	0.11	0.05	
Mean grain size entrained (m)**	0.08	0.03	

^{*} Based on Manning's equation; using riffle gradient as pools contain ineffective space, the velocity and discharge conveyed in them are not representative

The sizing of proposed substrate materials was guided by a review of hydraulic conditions (i.e., tractive force, flow competency) in the typical cross sections. The channel bed substrate is derived by balancing the average shear stress acting on the bed with the critical shear stress for the material. When the critical shear stress slightly exceeds the average shear stress acting on the bed, sediment transport is initiated.

To provide for a stable bed and level of sorting, 40% 50 mm – 100 mm diameter riverstone, 30% granular 'b' and 30% native material is proposed for the riffles. Granular 'b' consists of a mix of stone where approximately 20% - 50% of the stone is greater than 0.005 m in diameter, but nothing larger than 0.15 m in diameter. These materials will always have a core of sediment that is not entrained under bankfull flow conditions. This material maintains the character of the native material, while providing slightly higher stability and opportunity for sediment sorting. A mix of granular 'B' and native material is proposed for the pools given they experience lower velocities. Hydraulic sizing should be confirmed during detailed design once the channel geometries and flows have been finalized.

^{**} Based on a modified Shields equation (Miller et al. 1977), assuming Shields parameter equals 0.06 for gravel

6.3 Fish Passage

The near-bed velocity within the channel was modelled to determine whether fish passage is possible under the range of conditions expected for the low-flow channel. The velocity increases logarithmically with height above the bed surface in turbulent flows, through a relationship known as the von Karmen equation, or the Law of the Wall. Based on a knowledge of the bed materials, a theoretical height above the bed where velocity equals zero can be determined. The von Karmen equation is typically used to estimate the shear stress at the bed surface. However, a near-bed velocity can be back calculated using the average shear stress predicted for the low flow channel. The modelled velocities at a 0.01 m depth from the channel bed for the realigned channel was approximately 0.37 m/s in the riffles at the 2-yr return flow.

These values are within the range of velocities tolerated by various species found within the watershed (i.e., brook stickleback, creek chub, etc.; Katopodis and Gervais, 2016). Additionally, channels with gradients less than 5.0% are possible for fish passage, and the realigned channel has gradients that are less than 5.0% (Newbury, 2013). As a result, the gradients and velocities within the realigned channel are not detrimental to fish passage for local species.

6.4 Channel Corridor

6.4.1 Corridor Sizing

Meander belt width delineation was completed in support of defining erosion requirements for the realigned watercourse within the proposed development. With regards to delineating the hazard associated with channel migration, the Ontario Ministry of Natural Resources treats confined and unconfined systems differently. Unconfined systems are those with poorly defined valleys or slopes well outside where the channel could realistically migrate. In unconfined systems, the hazard is assumed to be from channel migration. Unconfined systems require a meander belt width. Given the size of the existing channel compared to the floodplain, this channel can be considered unconfined.

As part of the design, a meander belt width was calculated based on design bankfull dimensions of the channel to ensure that the planform has a meander belt width that falls within the proposed corridor requirements. Given the scale of the watercourse and limited migration potential for the system, the hazard limits calculated can be considered conservative. The meander belt widths provided are based on a modelled relation from Williams (1986) which were modified to include channel width and a factor of safety, and applied using the bankfull channel dimensions such that:

$$B_w = (4.3W_b^{1.12} + W_b) \times 1.2$$
 [Eq. 16]

where *Bw* is meander belt width (m), and *Wb* is bankfull channel width (m). An additional 20% buffer, or factor of safety, was applied to the computed belt width values. This addresses issues of under prediction and provides a factor of safety.

The bankfull channel dimensions of the proposed channel have an average width of 3.10 m. The resulting meander belt width estimates are provided in **Table 6**.

Table 6: Meander belt width estimate for design WC5

Omagh Tributary	Meander Belt Width (m)*	Corridor Bottom Width (m)
Design Reach 1	23	23

^{*} Includes 20% factor of safety

The predicted meander belt width for realigned **WC5** is 23 m based on the proposed flows and corridor gradient. All meander belt width calculations are based on channels where instream energy is greater than potential resistance of the bank materials. As such, they over predict the potential extent of meandering of vegetation-controlled channels and the erosion hazard. The proposed valley bottom width for **WC5** of 23 m adequately addresses the erosion hazard.

6.5 Habitat Restoration

The design incorporates several habitat elements within the channel corridor to improve riparian habitat and promote wildlife biodiversity. To maximize potential for wildlife passage, forage and residency, the habitat design incorporates varying topographies and woody debris. The habitat elements proposed include tortuous meanders, brush mattresses, basking logs, pallet type wood piles, raptor poles, rock piles, and terrestrial mounds.

Potential overwintering deep sections are proposed to provide critical habitat for resident fish. The overwintering deep sections are provided within the tortuous meander pattern, which will increase scour and depth. Overwintering deep sections will be 0.35 m deeper than the typical proposed pools. This habitat feature will provide fish with potential refuge from freezing conditions in the winter, but also provide ideal habitat during low flow periods, and increase habitat heterogeneity within the channel. Due to the size of the proposed channel the pools could freeze completely during the winter.

Brush mattress is proposed along the outside meander bend of the tortuous meanders and at the connection with the conveyance swale at the upstream extent. This treatment consists of live brush cuttings installed parallel to the banks and tied in with coir twine and stakes. The brush mattress will provide bank stability and improve aquatic habitat through shading.

Basking logs consist of a mixture of hardwood and softwood species, place in shallow areas of wetlands and anchored with a mix of stone or limestone blocks. These logs are angled in a way to promote turtle basking.

Pallet type wood piles consist of logs, snags and other wood debris, placed in a way that forms a stable interconnected mound, in the shape of a pallet. Additionally, the wood piles are planted with native fruit bearing vines, which provide forage opportunities for wildlife. Wood piles are placed at various locations along the length of the floodplain.

Raptor poles are constructed from large conifer tree trunks, embedded into the ground and serve to provide perches for larger raptors.

Rock piles consist of a mix of stone of varying sizes, piled up to create small mounds. These features provide hibernation habitat for various terrestrial species. The base of the piles is partially buried to prevent rock falls. Rock piles are installed at various locations along the length of the floodplain.

Terrestrial mounds consist of native material, piled up to create small mounds with a small dimple on the top. The bottom of the mound is seeded with the specified seed mix, while the top has limited soil and seed on it to provide foraging opportunities.

The full channel corridor will be restored using native plant species. This includes appropriate species for the various seed mixes as well as woody vegetation. The plantings are intended to enhance the terrestrial habitat through the provision of species and habitat diversity, increase floodplain soil stability and floodplain roughness, and increase sedimentation. The landscaping plan will be prepared at detailed design.

6.6 Wetland Replication

Offline wetland features will be constructed in addition to the channel. These features enhance terrestrial habitat by increasing diversity and providing a more natural floodplain form. They also provide functional benefits such as short-term water retention and sediment banking. They will be irregularly shaped to maximize the perimeter for a given area, which increases the potential for edge effects. Submerged and dry mounds are proposed within the offline wetlands to provide a topographically complex bottom to increase habitat heterogeneity. The short-term water retention function of these wetland types helps to polish water and moderate the discharge of water into the channel. These features will address the proposed wetland replication due to the removal of the existing wetland feature.

Wetland replication is proposed as part of the development to compensate for the removal of existing wetlands. Within the **WC5** corridor 0.46 ha of wetland is provided, which accounts for approximately 30% of the floodplain. The proposed wetlands have an average depth of 0.60 m. The wetlands were designed with mounds of variable heights to allow for a range of wetland vegetation to establish. We have provided variability to assure that from year-to-year a range of water depths and hydroperiods are provided. The proposed restoration planting plan will be completed at detailed design.

6.7 Stormwater Management Outlet Design

Stormwater management Pond 1 is proposed to outlet to the **WC5** corridor. We recommend a stone core wetland be installed at the proposed outfall. The stone core refers to hydraulically sized rounded stone, which is the subsurface material used to ensure wetland stability. The stone should be hydraulically sized to withstand the pipe capacity or maximum outflow velocity from the SWMP outlet and should include a 20% factor of safety. The wetland should be constructed as an overexcavated depression which is lined with a mix of soil and granular materials, to provide both depressional and subsurface storage (within the interstitial space of the sediment and soil). A layer of topsoil will be installed on top of the stone core to improve vegetation establishment within the feature. Filtration is provided as a result of flow through the soil medium between the pocket wetland a proposed channel.

7 Recommendations for Detailed Design

To support detailed design and ensure proper implementation of the channel corridors, the following activities are recommended at the detailed design stages:

- Confirm valley and channel gradients
- Develop planform and profile for the proposed corridors
- Develop a native planting plan for the proposed corridors
- Confirm hydraulic stone sizing to ensure the channel is stable
- Determine potential locations for additional terrestrial habitat features within each corridor
- Develop recommendations for implementation during construction, including an erosion and sediment control plan
- Develop and finalize a post-construction monitoring plan for the realigned channels

8 Post-Construction Monitoring Recommendations

A post-construction monitoring program is recommended to assess the performance of the implemented channel design. Monitoring observations can also be used to determine the need for remedial works, if required. Monitoring is recommended for three full calendar years after construction and includes annual visual inspections and surveys. The following monitoring and reporting activities are suggested for the realigned channel:

- General observations of the channel works should be documented after construction and after the first large flooding event to identify any potential areas of erosion concern
- Collection of a photographic record of site conditions
- Total station survey of the longitudinal profile and monumented cross sections following construction. This would serve as the as-built reference condition for use in comparing surveys completed in subsequent years
- Re-survey of the longitudinal profile and cross sections in subsequent years after construction
- Installation of erosion pins at monumented cross sections after construction and monitoring of the erosion pins during subsequent years
- Bed material characterization based on Wolman (1954) pebble counts
- General vegetation surveys completed annually after construction, for the duration of the monitoring period to determine survivorship of the plant materials (any dead, diseased or damaged plant materials will be replaced within the warranty period)
- Annual reporting to summarize construction activities (i.e., design implementation), and subsequent year-end reports for the duration of the monitoring period

9 Summary and Recommendations

The purpose of this study was to investigate the potential for excess erosion to occur in the receiving watercourse associated with the SWM outflows from the proposed development within the Block 1 property, Hamilton. Reconnaissance-level field assessments of the receiving watercourse (**WC5**) were completed to characterize the system and identify erosion-sensitive locations within the zone of impact. A detailed geomorphic assessment was completed within the

zone of impact along reach **WC5**, from which an erosion threshold was computed and provided as a critical discharge. For reach **WC5**, a critical discharge of 0.116 m³/s was determined based on a critical velocity of 0.53 m/s acting on the silty-clay bed materials (Fischenich, 2001).

Erosion exceedance modelling results indicate that the proposed stormwater management plan adequately addresses the concerns regarding potential excess erosion within WC5 following development. A reduction in erosion potential was predicted for the 25 mm, and a moderate increase in erosion potential was predicted for the larger, less-frequent storms. Considering the reduction in erosion potential predicted for the highly relevant 25 mm event, we do not foresee the requirement for any changes to the proposed stormwater management plan, or for the requirement of any additionally systemic erosion protection measures, as the assimilative capacity of the receiving watercourse is sufficient for the proposed changes to the hydrological regime.

We trust this report meets your requirements. Should you have any questions please contact the undersigned.

Respectfully submitted,

Paul Villard Ph.D., P.Geo., CAN-CISEC, EP, CERP Director, Principal Geomorphologist

Lindsay Davis, M.Sc., P.Geo., CAN-CISEC Geomorphologist

Lindsay Dew

10 References

Brierley, G. J. and Fryirs, K. A. 2005. Geomorphology and River Management: Applications of the River Styles Framework. Blackwell Publishing, Oxford, UK, 398pp.

Downs, P.W. 1995. Estimating the probability of river channel adjustment. Earth Surface Processes and Landforms, 20: 687-705.

Chapman, L.J. and Putnam, D.F. 1984. The Physiography of Southern Ontario. Ontario Geological Survey, Special Volume 2, Map 226.

Chow, V.T. 1959. Open channel hydraulics. McGraw Hill, New York.

Fischenich, C. 2001. Stability Thresholds for Stream Restoration Materials. EMRRP Technical Notes Collection (ERDC TN-EMRRP-SR-29), U.S. Army Engineer Research and Development Center, Vicksburg, MS.

Galli, J. 1996. Rapid Stream Assessment Technique, Field Methods. Metropolitan Washington Council of Governments.

Hey, R. D. and Thorne, C. R. 1986. Stable channels with mobile gravel beds. Journal of Hydraulic Engineering, American Society of Civil Engineers 112: 671-689.

Hickin, E.J. and Nanson, G.C. 1984. Lateral migration rates of river bends. Journal of Hydraulic Engineering, 110: 1557-1567.

Hooke, J.M. 1975. Distribution of sediment transport and shear stress in a meander bend. Journal of Geology, 83: 543-566.

Julien, P. Y. 1998. Erosion and Sedimentation (1st ed.). Cambridge University Press.

Katopodis, C. and Gervais, R. 2016. Fish swimming performance database and analyses. DFO Can. Sci. Advis. Sec. Res. Doc. 2016/002. vi + 550 p

Komar, P.D. 1987. Selective gravel entrainment and the empirical evaluation of flow competence. Sedimentology, 34: 1165-1176

Limerinos, J.T. 1970: Determination of the Manning coefficient from measured bed roughness in natural channels. United States Geological Survey Water-Supply Paper 1898B.

Miller, M.C., McCave, I.N. and Komar, P.D. 1977. Threshold of sediment erosion under unidirectional currents. Sedimentology, 24: 507-527.

Ministry of Environment (MOE). 2003. Ontario Ministry of Environment. Stormwater Management Guidelines.

Montgomery, D.R. and J.M. Buffington. 1997. Channel-reach morphology in mountain drainage basins. Geological Society of America Bulletin, 109 (5): 596-611.

Neill, C.R. 1967. Mean-velocity criterion for scour of coarse uniform bed material. Proceedings of the 12th Congress, International Association of Hydraulic Research, 3, 46-54.

Newbury, R.W. 2013. Designing fish-passable riffles as gradient controls in Canadian streams. Canadian Water Resources Journal, 38: 232-250.

Ontario Geological Survey (OGS). 2010. Surficial geology of Southern Ontario. Ontario Geological Survey. Miscellaneous Release – Data 128-REV.


Richards, C., Haro, R.J., Johnson, L.B. and Host, G.E. 1997. Catchment and reach-scale properties as indicators of macroinvertebrate species traits. Freshwater Biology, 37: 219-230.

Toronto and Region Conservation Authority. 2004. Belt Width Delineation Procedures.

Vermont Agency of Natural Resources (VANR). 2007. Step 7: Rapid Geomorphic Assessment (RGA). Phase 2 Stream Geomorphic Assessment.

Williams, G.P. 1986. River meanders and channel size. Journal of Hydrology, 88 (1-2): 147-164.

Appendix A Reach Mapping





Detailed Assessment Subject Property

Fruitland-Winona Block 1 Servicing Strategy

Hamilton, Ontario



Imagery: Google Earth Pro: 2018 Subject Property: Parish Aquatic Services, 2019. Watercourse and 1 m Contour: City of Hamilton, 2020. Detailed Assessment: GEO Morphix Ltd., 2021. Printed: March 2022. PN21043. Drawn by: J.T., M.O.

Appendix B Photo Record

Flows enter reach **WC5** through a concrete box culvert passing under Fruitland Road. No erosion concerns were noted. Yellow arrow denotes flow direction.



No bed scour was noted downstream of the Fruitland Road culvert.

Project #: PN21043

Photo 1 Reach **WC5**

Photo 2 Reach **WC5**



Reach **WC5** has a predominantly trapezoidal channel shape throughout the study area. Minimal flow velocities were observed during the assessment.



Bank materials across the entire reach are characterized by silty clay. Occasional tree roots were observed, but the bottom third of the bank is typically exposed.

Photo 4 Reach **WC5**

Photo 3 Reach **WC5**





Photo 6 Reach **WC5**

Exposed material is common at toe of bank. Riparian vegetation provides some level of stabilization, but roots are typically small and immature.

Several sections of shallow flow, abundant debris, and loose bed material are present.

Debris is largely associated with past agricultural infrastructure.



A small footbridge is present in **WC5**. A thick debris jam exists immediately upstream and retains a level of flow.

Project #: PN21043

Photo 7 Reach **WC5**

Photo 8 Reach **WC5**





Bank armouring and a footbridge were observed further downstream. This infrastructure is significantly degraded and has evidently not been maintained for many years.

Project #: PN21043

Photo 10 Reach **WC5**

Photo 11 Reach **WC5** Flows near the downstream extent of the reach are slightly deeper. The channel width expands in this section. The leaning trees indicate a level of channel widening.



Evidence of erosion largely subsides near the downstream extent, as the channel exhibits more depositional tendencies, indicated by siltation on the bed.

Photo 12 Reach **WC5**

Appendix C Field Observations

Rapid Geomorphic Assessment

Date:	2021-08-19	Stream/Reach:	watercourse 5
Weather:		Location:	Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

Field Staff:		Watershed/Subwatershed:		-	b					
Process		Geomorphic Indicator	Pres	sent?	Factor					
	No.	Description	Yes	No	Value					
	1	Lobate bar		X						
	2	Coarse materials in riffles embedded	Named							
Evidence of	3	Siltation in pools	X							
Aggradation	4	Medial bars		×	1/					
(AI)	5	Accretion on point bars		X	16					
	6	Poor longitudinal sorting of bed materials		×						
	7	Deposition in the overbank zone		×						
		Sum of indices =	1	5	0.167					
	1	Exposed bridge footing(s)	Manager	_						
	2	Exposed sanitary / storm sewer / pipeline / etc.	-	and promise						
	3	Elevated storm sewer outfall(s)	***	erichtenge,	1					
	4	Undermined gabion baskets / concrete aprons / etc.			1					
Evidence of	5	Scour pools downstream of culverts / storm sewer outlets		× ·	0					
Degradation (DI)	6	Cut face on bar forms		×	1					
(51)	7	Head cutting due to knick point migration		× ·	16					
	8	Terrace cut through older bar material		× .						
	9	Suspended armour layer visible in bank		×						
	10	Channel worn into undisturbed overburden / bedrock		× .	1					
		Sum of indices =	U	6	0					
	1	Fallen / leaning trees / fence posts / etc.	×							
	2	Occurrence of large organic debris		大.	1					
•	3	Exposed tree roots	×							
	4	Basal scour on inside meander bends		*.						
Evidence of Widening	5	Basal scour on both sides of channel through riffle	X	-	3,					
(WI)	6	Outflanked gabion baskets / concrete walls / etc.		×	3/8					
. ,	7	Length of basal scour >50% through subject reach		X						
	8	Exposed length of previously buried pipe / cable / etc.	waster.	Michael Market	7-					
	9	Fracture lines along top of bank		X .	1					
	10	Exposed building foundation	Names	- Dysonia -	1					
		Sum of indices =	3	5	0.37					
	1	Formation of chute(s)		×						
Evidonae of	2	Single thread channel to multiple channel		×						
Evidence of Planimetric	3	Evolution of pool-riffle form to low bed relief form		×	1					
Form	4	Cut-off channel(s)		×	1					
Adjustment	5	Formation of island(s)		×						
(PI)	6	Thalweg alignment out of phase with meander form		X						
	7	Bar forms poorly formed / reworked / removed		叉	1					
		Sum of indices =			()					

Additional notes: - Min observable	Stability Index (SI) = (AI+DI+WI+PI)/4 = 0 .\4								
asomorphic activity	Condition	In Regime	In Transition/Stress	In Adjustment					
	SI score =	₯ 0.00 - 0.20	□ 0.21 - 0.40	□ 0.41					

Completed	by:	Check	ked	by	:	

Rapid Stream Assessment Technique

 \square 0 \square 1 \square 2

unstable with high

Point range

amount of fresh sand

Project Code: 24043

Date:	2021-08-19	Stream/Reach:		Water cour	se 5			
Weather:		Location:		Hamilton				
Field Staff:	21 DW	Watershed/Subwate	rshed:		a a			
Evaluation Category	Poor	Fair	Good	Excellent				
	 < 50% of bank network stable Recent bank sloughing, slumping or failure frequently observed 	50-70% of bank network stable Recent signs of bank sloughing, slumping or failure fairly common	stable • Infreque	o of bank network ent signs of bank ng, slumping or	 > 80% of bank network stable No evidence of bank sloughing, slumping or failure Stream bend areas very stable Height < 0.6 m above stream (< 1.2 m above stream bank for large mainstem areas) Bank overhang < 0.6 m 			
Channel	Stream bend areas highly unstable Outer bank height 1.2 m above stream bank (2.1 m above stream bank for large mainstem areas) Bank overhang > 0.8-1.0 m	Stream bend areas unstable Outer bank height 0.9-1.2 m above stream bank (1.5-2.1 m above stream bank for large mainstem areas) Bank overhang 0.8-0.9m	Outer b m abov 1.5 m a for large	bend areas stable ank height 0.6-0.9 e stream bank (1.2- bove stream bank e mainstem areas) verhang 0.6-0.8 m				
Stability	Young exposed tree roots abundant > 6 recent large tree falls per stream mile	Exposed tree roots old, large and woody Generally 0-1 recent large tree falls per stream mile						
	Bottom 1/3 of bank is highly erodible material Plant/soil matrix severely compromised	ple material generally highly erodible generally highly retrix severely material generally highly re			Bottom 1/3 of bank is generally highly resistant plant/soil matrix or material			
	Channel cross-section is generally trapezoidally- shaped	Channel cross-section is generally trapezoidally- shaped		l cross-section is ly V- or U-shaped	Channel cross-section is generally V- or U-shaped			
Point range	- □ 0 □ 1 □ 2	□ 3 □ 4 □ 5	□ 6	反7 □ 8	□ 9 □ 10 □ 11			
Ma	> 75% embedded (> 85% embedded for large mainstem areas)	• 50-75% embedded (60- 85% embedded for large mainstem areas)	59% en	embedded (35- nbedded for large m areas)	Riffle embeddedness < 25% sand-silt (< 35% embedded for large mainstem areas)			
	Few, if any, deep pools Pool substrate composition >81% sand- silt	Low to moderate number of deep pools Pool substrate composition 60-80% sand-silt	pools • Pool sub	e number of deep ostrate composition o sand-silt	High number of deep pools (> 61 cm deep) (> 122 cm deep for large mainstem areas) Pool substrate composition <30% sand-silt Streambed streak marks and/or "banana"-shaped sediment deposits absent			
Channel Scouring/ Sediment Deposition	Streambed streak marks and/or "banana"-shaped sediment deposits common	Streambed streak marks and/or "banana"-shaped sediment deposits common	and/or `	bed streak marks banana"-shaped of deposits				
2.5.5.5.	 Fresh, large sand deposits very common in channel Moderate to heavy sand deposition along major portion of overbank area 	Fresh, large sand deposits common in channel Small localized areas of fresh sand deposits along top of low banks	uncomn • Small lo	arge sand deposits non in channel calized areas of nd deposits along ow banks	Fresh, large sand deposits rare or absent from channel No evidence of fresh sediment deposition on overbank			
	Point bars present at most stream bends, moderate to large and unstable with high	Point bars common, moderate to large and unstable with high amount of fresh sand	well-veg	ors small and stable, getated and/or ed with little or no and	Point bars few, small and stable, well-vegetated and/or armoured with little or no fresh sand			

amount of fresh sand

·□ 3 □ 4

□ 5 🕱 6

or no fresh sand

□ 7 □ 8

fresh sand

Date:	2021-08-19	Reach: Woterco	wse 5 Project Code:	21043			
Evaluation Category	Poor	Fair	Good	Excellent			
	Wetted perimeter < 40% of bottom channel width (< 45% for large mainstem areas)	Wetted perimeter 40- 60% of bottom channel width (45-65% for large mainstem areas)	Wetted perimeter 61-85% of bottom channel width (66-90% for large mainstem areas)	Wetted perimeter > 85% of bottom channel width (> 90% for large mainstem areas)			
	Dominated by one habitat type (usually runs) and by one velocity and depth condition (slow and shallow) (for large mainstem areas, few riffles present, runs and pools dominant, velocity and depth diversity low)	Few pools present, riffles and runs dominant. Velocity and depth generally slow and shallow (for large mainstem areas, runs and pools dominant, velocity and depth diversity intermediate)	Good mix between riffles, runs and pools Relatively diverse velocity and depth of flow	 Riffles, runs and pool habitat present Diverse velocity and depth of flow present (i.e., slow, fast, shallow and deep water) 			
Physical Instream	 Riffle substrate composition: predominantly gravel with high amount of sand 5% cobble 	 Riffle substrate composition: predominantly small cobble, gravel and sand 5-24% cobble 	Riffle substrate composition: good mix of gravel, cobble, and rubble material 25-49% cobble	Riffle substrate composition: cobble, gravel, rubble, boulder mix with little sand > 50% cobble			
Habitat	 Riffle depth < 10 cm for large mainstem areas 	Riffle depth 10-15 cm for large mainstem areas	Riffle depth 15-20 cm for large mainstem areas	Riffle depth > 20 cm for large mainstem areas			
, ,	 Large pools generally < 30 cm deep (< 61 cm for large mainstem areas) and devoid of overhead cover/structure 	Large pools generally 30- 46 cm deep (61-91 cm for large mainstem areas) with little or no overhead cover/structure	Large pools generally 46-61 cm deep (91-122 cm for large mainstem areas) with some overhead cover/structure	Large pools generally > 61 cm deep (> 122 cm for large mainstem areas) with good overhead cover/structure			
	Extensive channel alteration and/or point bar formation/enlargement	Moderate amount of channel alteration and/or moderate increase in point bar formation/enlargement	Slight amount of channel alteration and/or slight increase in point bar formation/enlargement	No channel alteration or significant point bar formation/enlargement			
	• Riffle/Pool ratio 0.49:1; ≥1.51:1	• Riffle/Pool ratio 0.5- 0.69:1 ; 1.31-1.5:1	• Riffle/Pool ratio 0.7-0.89:1 ; 1.11-1.3:1	• Riffle/Pool ratio 0.9-1.1:1			
	• Summer afternoon water temperature > 27°C	Summer afternoon water temperature 24-27°C	Summer afternoon water temperature 20-24°C	Summer afternoon water temperature < 20°C			
Point range	□ 0 □ 1 □ 2	□ 3 🍃 4	□ 5 □ 6	□ 7 □ 8			
No	 Substrate fouling level: High (> 50%) 	Substrate fouling level: Moderate (21-50%)	Substrate fouling level: Very light (11-20%)	Substrate fouling level: Rock underside (0-10%)			
Water Quality	Brown colourTDS: > 150 mg/L	• Grey colour • TDS: 101-150 mg/L	Slightly grey colour TDS: 50-100 mg/L	Clear flowTDS: < 50 mg/L			
Water Quality	 Objects visible to depth 0.15m below surface 	Objects visible to depth 0.15-0.5m below surface	Objects visible to depth 0.5-1.0m below surface	Objects visible to depth 1.0m below surface			
	 Moderate to strong organic odour 	Slight to moderate organic odour	Slight organic odour	• No odour			
Point range	□ 0 □ 1 □ 2	□ 3 □ 4	☞ 5 □ 6	□ 7 □ 8			
Riparian Habitat	Narrow riparian area of mostly non-woody vegetation	Riparian area predominantly wooded but with major localized gaps	Forested buffer generally 31 m wide along major portion of both banks	Wide (> 60 m) mature forested buffer along both banks			
Conditions	Canopy coverage: <50% shading (30% for large mainstem areas)	Canopy coverage: 50- 60% shading (30-44% for large mainstem areas)	Canopy coverage: 60-79% shading (45-59% for large mainstem areas)	Canopy coverage: >80% shading (> 60% for large mainstem areas)			
Point range	□ 0 □ 1	□ 2 □ 3	□ 4 □ 5	1 6 □ 7			
Total overall s	core $(0-42) = 28$	Poor (<13) F	air (13-24) Good (25-	Excellent (>35)			

V:
h

	eral Site Cha						Pro	, ₎ e	CL	<u> </u>	<i>a</i>	e:										
Date:		120	21-08-19	Str	eam/	Rea	ich:						V	raf	51	C	ou.	(5	C	100	5	
Neath	ner:			Loc	cation	:											tor					
Field S	Staff:	J	T DM	Watershed/Subwatershed:																		
eatur	es			Site	e Sket	ch:				7	4	1										
	Reach break								×	-		v	A									
	Cross-section											-	,	~	1		1					
	Flow direction										/											
∼	Riffle																				1	A
	Pool							J		1												
⋘	Medial bar									1	7	2										
	Eroded bank		40																			
	Undercut bank									1												
	Rip rap/stabilization	n/gabi	on				-				X	3				ļ						
->>>	Leaning tree						-	,	<u>e</u>		ļ					ļ						
····×	Fence										/	1					/					
	Culvert/outfall									\						/						
	Swamp/wetland		т —				-			\		1	2									
AAA	Grasses)	ļ	1		中						ļ		
	Tree					-			(_					4					
	Instream log/tree					-	-			7	\		1			ļ	1					
< * *	Woody debris					ļ						\	L-Y				101	-				
只	Station location		4			<u> </u>	-					1				50	191	1		ļ		
low T	Vegetated island					-				Ę	10	<u>H</u>		92		-	17	, 0				
H1	Standing water					ļ					\ \	-		X	5	1		1		0/		
H2	0-3	a flow									1	90	4			40	20	1/	λe	0/	-	
H3	Scarcely perceptible Smooth surface flow			-				,			丛	1×	1			1	1	1-	ļ., .	1	()	
пз Н4	Upwelling	/V	*	-		ļ	V) a	, K						<		p l	<u> </u>	C	(,	dg	٣	
H5	Rippled			-		0	(10)	1	100		7	- (B									
н 5	Unbroken standing	Wave		-							8			26		<u> </u>				ļ		
H7	Broken standing wa			-		1				Įλ	1		5			ļ				ļ		
H8	Chute	110		-		ļ	-				-1		\ \	7		ļ	ļ					
H9	Free fall			-		ļ	-						1	/\					ļ			
Substr						ļ	1					1	1			ļ						
S1	Silt	S6	Small boulder	1		ļ	-					-	- \	\	×		01	d				
S2	Sand	57	Large boulder								.7	2			`	1	6	. 0	· .	Q		
S3	Gravel	58	Bimodal			ļ				W					7-1				or or	. &		
54	Small cobble	S9	Bedrock/till										X	8	0			1. 1.		2		
S5	Large cobble			1		ļ	1					0.	1	~ ~		3)	ļ		, i),	
Other						-						0.	1	\forall	7/5)	£	- V	, 1,	OV
вм	Benchmark	EP	Erosion pin			-	H						A	1		7		~ \ \			<i>†</i> ^ ·	€ €
BS	Backsight	RB	Rebar	-		 	1						7									
os	Downstream	US	Upstream			1					/		1			-						
NDJ	Woody debris jam	TR	Terrace			-				1		- /	/						a page of the second of the	ACTUAL STATE		ment to be selected to
/WC	Valley wall contact	FC	Flood chute							24	7	4	9	96	KIN	4)	Sc	ale:	i	J	L	L
BOS	Bottom of slope	FP	Flood plain	Ad	ditior	al N	Vote	5:/	-	1		5		-	1		-		1.			
ros	Top of slope	KP	Knick point			iui I	1010	٥. (10	14		7	V [*	1	_	6.	0	W	5 h	din	IT	

Completed by: _____ Checked by: _____

Detailed Assessment (Total Station)

Project Code: 21043

Date:	2021-08-19	Reach:	"Watercourse 5"
Weather:		Location:	"Watercourse 5" Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	
Point No.	Code	Notes	Survey Direction
100 106	,	1,960 Rod height	☑ Upstream to Downstream
		should bp 1,600	☐ Downstream to Upstream
107			
			Cross-sections
	0.50		No. of Cross-sections:
1.54	PBED		Monitoring Cross-sections:
			□ None
			9□ Yes
X53	REVERSED		If yes, which ones: & /
•			
			Rain in last 24 hours
			™None
		•	☐ Yes: Amount mm
		6	Valley Type:
			Confined Partially Unconfined
			Channel Zone:
			Headwater Transfer Deposition
			Land Use: Residential /to
	8		Aquatic Vegetation: 41000
			Portion of Aquatic Vegetation: 10%
			Riparian Vegetation:
	•		Extent of Riparian Cover:
			Fragment None Continuous
			Riparian Cover (channel widths):
			1-4 4-10 >10
		. /	Age Class of Riparian Vegetation:
			Immature Established Mature
	•		(<5 yrs) (5-30 yrs) (>30 yrs)
	-		Extent of Encroachment:
			None Minimal Moderate
			Heavy Extreme
			Density of Woody Debris:
	65		Tow Moderate High

Completed by:		Checked	By:	
---------------	--	---------	-----	--

Infrastructure

LWD

Overall Photographs Taken

Blockage(s) in Channel:



Date:	2021-08-19	Reach/Cross-section:	X51 - M
Weather:		Location:	Mamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

	VV				Notes	Cross-secti	onal Morph	ology	
6.30	1622					□ Riffle		⊠ Run	□ Other
6.70	1611					L			
7.00	1563					Substrate			
7.30	1526					Sample:			
7.60	1498					■ Bed ■ Ba	ınk 🗆 Subpa	vement 🗆	Water □ None
7.90	1538		•			Pebble Cou			
8.10	1555		***************************************			1. Clay	11	21	31
8.30	1601					2+	12	22	
8,60	1692					3. 5:1+	13	23	33
8.90	1783					4.	14	24	34
9.20	1838					5	15	25	35
19 ,50	1981	BF				6	16	26	36,
9,60	2095	1 /				7	17	27	37
9.80	2302					8	18	28	38
9.90	2340	WC				9	19	29	39
10.10	2412					10	20	30	40
10.30	2448			-		Particle Sha	ape:		
10.50	2432					☐ Platy	☐ Sub-a	angular 🗆	Well Rounded
10,70	2441					☐ Very Angu	ılar □ Angu	lar	Sub-Rounded
11.00	2441					☐ Rounded			
11.30	2400				-	Embedednes	is:		%
11.60	2346			•		Subpavemer	ıt		
11.80	2321						Well □ Mo	derate 🗆	Poor □ Very po
11.95	2295								
12.00	2035					Sediment T			
12.15	2015						bserved	Not Ob	served
12.30	1873					If Observed			
12,45	1790								g □ Saltation
12.65	1701					Percentage of	of Bed Active		
12.90	1638		2						
13,20			8			Velocity an	d Discharge		
13,60						Velocity:		Meth	
14.00						☑ Estimated			
14.40	1625					☐ Measured			
14.60	1602					Discharge:		□ AD	
14:85	1600								rsh McBirney
		***************************************				☐ Measured	m	$^3/s \square Oth$	ner

Completed	by:	 Checked	by:	
		Pag	je _	of

Page _____ of ____

Bank Characteristics

Project Code: 2 1 0 43

Date:	R	leach/XS:	XS
Sketch (Viewed D	ownstream) Include: vegetation type and lo	cation, soll horizons, woody debri	s roots atr
Lef	t Bank		Right Bank
			7 9 00
		5	
	46	y - 3; 1c	
Left Bank Materials	S	Right Bank Materials	
□ Bedrock	□ Gravel	☐ Bedrock	☐ Gravel
□ Till □ Clay	☐ Small Cobble	□ Till	☐ Small Cobble
□ Silt	☐ Large Cobble ☐ Small Boulder	☐ Clay ☐ Silt	☐ Large Cobble
☐ Sand	☐ Large Boulder	□ Sand	☐ Small Boulder ☐ Large Boulder
Bank Height:	0.76 m 75 °	Bank Height:	0 7 / m
Bank Angle: Root Depth:	0,15 m	Bank Angle:	95 0,30 m
Root Density:	50 %	Root Depth: Root Density:	20 m
Undercut:	m	Undercut:	m
Erosion Pin:	m	Erosion Pin:	0.20 m
	1		\$ · · · · · · · · · · · · · · · · · · ·
Penetrometer:	ka/cm²	Panotromotore	
			wot Used: □ Yes □ No
F	- Kg/Cili	Fc	oot Used:
	- Kg/Cili	Fc	Kg/ Cili
F	- Kg/Cili	Fc	oot Used:
Additional Notes	- Kg/Cili	Fc	oot Used:
F	- Kg/Cili	Fc	oot Used:
Additional Notes	- Kg/Cili	Fc	oot Used:



Project Code:

21043

Date:		2021-	04-19	Reach	/Cross-secti	on:	x52		·
Weather		4.0.2.1	-0.5	Locatio			Hami	1 to 0	
Field Sta	ff:	JT I	DM C		hed/Subwa	itershed:	+ (q Mi	1 10.7	
2	100	1000			Notes	Cross-section	onal Morph	ology	
6.30	1564					□ Riffle	Pool	□Run	□ Other
6.60	1575		· pl						
6,90	1585					Substrate		10.00	
7,10	1642					Sample:			
7,30	1690					₽ Bed ₽ Ba	ınk 🗆 Subpa	vement 🗆 \	Water □ None
7,60	1740		í			Pebble Cou	nt (cm):		
7.90	1769					1	11	21.	31
8,20	1796		a the s			2.Clay		22	32
8.40	1892	BF	× ,			3	13	23	33
8,60	2045					4. 5.1+	14	24	34
8.80	2262	* 113				5	15	25	35
8.95	2326					6	16	26	36
9.10	2345					7	17.	27	37
9.30	23 56	2300	→WL			8	18	28	38
9,60	2392					9	19	29	39
9.80	2400					10	20	30	40
10.00	2402					Particle Sha	ape:		
10.20	2388					☐ Platy	☐ Sub-a	ingular 🗆 \	Well Rounded
10,40	2335					☐ Very Angu	ılar 🗆 Angul	ar 🗍 S	Sub-Rounded
10,60	2264					☐ Rounded	/		
10.80	2116					Embedednes	s:		
11.00	1855					Subpavemer	ıt:		
11,20	1705					Sorting:	Well 🗆 Mo	derate 🗆 P	oor 🗆 Very poor
11.40	1615								
11.70	1516					Sediment T	ransport		
12.00	1437					□ 0	bserved	⊠ Not Obse	erved
12.30	1432		7			If Observed	1:		
	-					☐ Suspende	d 🗆 Sliding	☐ Rolling	□ Saltation
						Percentage of	of Bed Active		%
						Velocity an	d Discharge		100
						Velocity:		Metho	d a
						🖄 Estimated	m/	s 🗆 Wiffle	e ball
						☐ Measured	m	/s □ Curr	ent Meter
						Discharge:		□ ADV	
						☐ Estimated	m ³	/s □ Mars	h McBirney

Completed	by:	Checked	by:	

 \square Measured _____m³/s \square Other

Bank Characteristics

Project Code: 21043

	Ownstream) Include: vegetati	Reach/XS:	1 0		200
Lef	t Bank			Right Bank	
		V			
t Bank Materia	☐ Gravel		Bank Materials Bedrock	□ Gravel	
□ Till ☑ Clay ☑ Silt □ Sand	☐ Small Boulder ☐ Large Boulder	-Q	Till Clay Silt Sand	☐ Small Boulde ☐ Large Boulde	r
	75 0.30 20	n	Root Depth: Root Density:	6.30 20	m m %
Erosion Pin Penetrometer	n k	n n .g/cm² P J No	Erosion Pin:	t Used: □ Yes	m m kg/cm² □ No
ditional Notes					Ind 110
oto Order:					

Project Code: 21043

Date:	2021-0	8-19	Reach,	Cross-sect	ion: XS3
Weather:			Locatio	on:	yan il ton
Field Staff:	TT	DM	Waters	shed/Subw	
200				Notes	Cross-sectional Morphology
					□ Riffle □ Pool
					Substrate
			***************************************		Sample:
	+-				☐ Bed ☐ Bank ☐ Subpavement ☐ Water ☐ None
<u> </u>	2 191				Pebble Count (cm):
- 5	tation				1 11 21 31
					2 12 22 32
					3. <u>Clay</u> 13 23 33
			****		4 14 24 34
					5. 5. 15. 25. 35.
					6 16 26 36
					7 17 27 37
					8 18 28 38
					9 19 29 39
					10 20 30 40
					Particle Shape:
					☐ Platy ☐ Sub-angular ☐ Well Rounded
		Land Maria			☐ Very Angular ☐ Angular ☐ Sub-Rounded
			1.00		□ Rounded
					Embededness: %
		-			Subpavement:
			***********		Sorting: ☐ Well ☐ Moderate ☐ Poor ☐ Very poor
:		. 1971			Sediment Transport
					☐ Observed ☐ Not Observed
					If Observed:
1					☐ Suspended ☐ Sliding ☐ Rolling ☐ Saltation
			CAT.		Percentage of Bed Active: %
			el Yg		Velocity and Discharge
3					Velocity: Method:
				1 = v	☑ Estimated m/s ☐ Wiffle ball
					☐ Measuredm/s ☐ Current Meter
					Discharge: □ ADV
	2 1				☐ Estimated m³/s ☐ Marsh McBirney
					☐ Measuredm³/s ☐ Other

Completed by: _____ Checked by: _____

Bank Characteristics

Project Code: 21043

Date:	2021-	-08-19	1	Reach/XS:	X53	
Sketch (Vie	wed Downstre	am) Include: vegeta	tion type and I	ocation, soil horizons, woo	dy debris, roots, etc.	
					- war	
	Left Bank				Right Banl	(
		45				
		06				
		2				
7	14	11/				
						9 7
					Z Z	P NP -
						Y Y Y
				17		
				V		
47						
Left Bank M		25 20 30 30 4 37 5		Right Bank Ma	iterials	en e
☐ Bedr	rock	☐ Gravel		☐ Bedrock		
		☐ Small Cobble			☐ Small C	
☐ Clay		☐ Large Cobble	, (1)	Clay	☐ Large C	
☑ Silt	, 210	☐ Small Boulder		⊠ Silt	☐ Small B	
☐ Sand		☐ Large Boulder	1	☐ Sand	Large B	
	Height:(Angle:		m •	Bank He	sigile.	m
	Depth:	0.18	m	Bank A	1 4	
	Density:	Cons	m %	Root Da		m
	idercut:	0.03		Root Der	ercut:	%
	ion Pin:		m m	Erosion		m
L1 03	ЮП РПП.		111.	Elosioi	I FIII.	m
Penetro	ometer:		kg/cm²	Penetrom	neter:	kg/cm²
	Foot Us		□ No		Foot Used: ☐ Y	
Addistr						
Additional N	votes					
Maria de la companya		1 1				
Photo Ord	er:	LK				

Page ____ of ____

Completed by: _____ Checked by: _____

Date:		021-0	o - i a	Poach	/Cross-sect		090		.11 92
Weather:	2	000	<u> </u>	Locatio		ion:	X5 T	1.1	
Field Staff:		7 - F	Sun		shed/Subw	atorchod	Mem.	176 h	
)/ \	Waters	sileu/ Subw	atersiieu:	****		
X	8		2/3		Notes	Cross-section	nal Morph	ology	-
6.30 11	666					☐ Riffle	☐ Pool	Run	☐ Other
6.60 1	684							,	
6.901	643					Substrate			
7.20	625					Sample:			
7,50	1614					□ Bed □ Bar	nk 🗆 Subpa	vement 🗆 \	Water □ None
7.80 1	632					Pebble Coun			
8.901	620	BF					11	21.	31
8.10	679				79	2+_	12		
8.30 1	841					3. 5: H	13		
8.502	1062					i .	14		
8.60 2	2156	WL				1	15		
18.702	1.195	BED		ES E 4			16		
8.80 2	231						17		
9.10 2	251						18		
9.30 2	269					4	19		
9.50 2	353					10			
9.75 2	1278	14				Particle Sha		(9	
10.00 2	196					☐ Platy	☐ Sub-a	ngular 🗆 \	Vell Rounded
10.30 2	159			9 ¥355 Ž		☐ Very Angul		and the same of th	Sub-Rounded
10.45 2	125					☐ Rounded			
10.552	020					Embededness	:		%
10.75 1	915					Subpavement			
11.00 1	825			77 67 5					oor 🗆 Very poor
11.30 1	795			<i>i</i>		-			
11,601	780	17.4		-		Sediment Tra	ansport		11.00
11.901	712					□ Ob	served	Not Obse	rved
12.20 10	040					If Observed:		1 (811)	
12.501	544					☐ Suspended	□ Sliding	☐ Rolling	☐ Saltation
12.701	518					Percentage of	Bed Active:		%
				1 a 8		is agr			
	1	1.0 - 2 m				Velocity and	Discharge	14.192	
						Velocity:		Method	
						☐ Estimated _	m/s	s 🗆 Wiffle	ball
						☐ Measured _	m/	s 🗆 Curre	ent Meter
						Discharge:		☐ ADV	
						☐ Estimated _	m³/	's □ Marsh	n McBirney
						☐ Measured _	m³/	/s □ Other	

Completed by:	Checked by:
	Page of

Bank Characteristics

Project Code:

21043

ate: 20'	21-08-19	Re		254	
ketch (Viewed Do	ownstream) Include: ve	egetation type and loca	tion, soil horizons, woody debris,	roots, etc.	
Left	Bank			Right Bank	
☐ Bedrock ☐ Till	☐ Gravel ☐ Small Cob		Right Bank Materials □ Bedrock □ Till □ Clay	☐ Gravel☐ Small Cobble☐ Large Cobble	
☐ Bedrock	☐ Gravel	oble ilder	☐ Bedrock		
☐ Till ☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density: ☐ Undercut: ☐ Erosion Pin: ☐ Penetrometer:	☐ Gravel ☐ Small Cob ☐ Large Cob ☐ Small Bou ☐ Large Bou ☐ . 구	oble older o	☐ Bedrock ☐ Till ☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density: ☐ Undercut: ☐ Erosion Pin: ☐ Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ . 6 7 □ . 0	m ° m %

Completed by: _____ Checked by: _____



Page ____ of ____

Cross-Section Characteristics

Project Code:

21043

Date:		08-19	Reach	Cross-sect	ion:	×55		
Weather:	26.00	Sun	Locatio	on:		Hamil	ton	
ield Staff:	JT	PM	Waters	shed/Subw	atershed:			
				Notes	Cross-section	onal Morphol	oav	
					□ Riffle	<u> </u>		Other
-						<u> </u>	a run	Other
					Substrate			
	T (): 1			,	Sample:			
	COTO				☐ Bed ☐ Ba	nk □ Subpave	ement 🗆 Wa	iter 🗆 None
		1			Pebble Cour	nt (cm):		
	5 19	IVON			1	11	21,	31
					2. Clan			
					3	13		
					4. 5:1+			
					5	15		
					6			
						17		
						18		
					1	19		
					1	20		
					Particle Sha			
						☐ Sub-an	gular 🗆 We	ell Rounded
					1	lar 🗆 Angular		b-Rounded
					☐ Rounded			
						5:		%
						:		,,
					1	Well □ Mode		r 🗆 Verv no
								тегу ре
					Sediment Tr	ansport		
							Not Observ	red
					If Observed			
					The second of th	l □ Sliding	□ Rolling	Saltation
						Bed Active: _	_	
					T ON CONTROL OF			
					Velocity and	Discharge		
					Velocity:		Method:	
				8	_	m/s		all
					1	m/s		
					Discharge:		□ ADV	
						m³/s		McBirnev
					□ Measured _			



Bank Characteristics

Project Code:

1				
1	1	13	4	
dan	Ł	U		30

Date:		Reach/XS:	*	
ketch (Viewed Dow	nstream) Include: vegetation type	and location, soil horizons, woody debris	, roots, etc.	
Left B	ank		Right Bank	
			Right Bank	
WWW.				
THE WAY				VVV
			XIIIII	
eft Bank Materials		Right Bank Materials	5	
□ Bedrock	☐ Gravel	□ Bedrock	□ Gravel	
□ Till	☐ Small Cobble	□ Till	☐ Small Cobbl	e
☐ Clay	☐ Large Cobble	□ Clay	☐ Large Cobbl	e ,
Silt	☐ Small Boulder	∠ Silt	☐ Small Bould	er
☐ Sand	☐ Large Boulder	☐ Sand	☐ Large Bould	er
Bank Height:	<u>0,10</u> m	Bank Height:	30	m °
Bank Angle:	2 12	Bank Angle:	000	
Root Depth:	0.10 m	Root Depth:	10	m 04
Root Density:	- 70	Root Density: Undercut:	-	% m
	m	Frosion Pin		m m
LIOSION I III.	111	210310111111.		
Penetrometer:	kg/cm	Penetrometer:	* * * * * * * * * * * * * * * * * * *	kg/cm²
Fo	ot Used: ☐ Yes ☐ No		Foot Used: ☐ Yes	□ No
Additional Notes				
Photo Order:				

Completed by: _____ Checked by: _____



Date:

Project Code:

Reach/Cross-section:

1043

Completed by: _____ Checked by: _____

Notes	Weather:	26°C 5un	Location: Hamilton
Riffle	Field Staff:		
Riffle			
Substrate Sample:			Notes Cross-sectional Morphology
Sample:	0		□ Riffle □ Pool ☒ Run □ Other
Sample:			
Bed Bank Subpavement Water Nor	7		Substrate
Pebble Count (cm): 1.	(0	, 100	Sample:
1.		1	☐ Bed ☐ Bank ☐ Subpavement ☐ Water ☐ None
2		, to JiDA	Pebble Count (cm):
3.			1 11 21 31
4.			2 12 22 32
4.			3. <u>Clay</u> 13 23 33
6.			4 14 24 34
7			5. 5. 15 25 35
8			6 16 26 36
9			7 17 27 37
10	D		8 18 28 38
Particle Shape: Platy			9 19 29 39
□ Platy □ Sub-angular □ Well Rounder □ Very Angular □ Angular □ Sub-Rounder □ Rounded □ Rounded □ Embededness:			10 20 30 40
□ Very Angular □ Angular □ Sub-Rounded □ Rounded Embededness:			Particle Shape:
□ Rounded Embededness:			☐ Platy ☐ Sub-angular ☐ Well Rounded
Embededness:% Subpavement:			☐ Very Angular ☐ Angular ☐ Sub-Rounded
Subpavement:			☐ Rounded
Sorting:			Embededness: %
Sorting:			Subpavement:
			Sorting: □ Well □ Moderate □ Poor □ Very poor
Sediment Transport			Sediment Transport
☐ Observed ☐ Not Observed	1		
If Observed:			If Observed:
☐ Suspended ☐ Sliding ☐ Rolling ☐ Saltatio		-	☐ Suspended ☐ Sliding ☐ Rolling ☐ Saltation
Percentage of Bed Active:			
Velocity and Discharge	3		Velocity and Discharge
Velocity: Method:			
☐ Estimated ☐ m/s ☐ Wiffle ball	4		
☐ Measuredm/s ☐ Current Meter			
Discharge: □ ADV			
☐ Estimated m³/s ☐ Marsh McBirney			
□ Measuredm³/s □ Other			

Bank Characteristics

etch (Viewad Dawn	etream) I-dud-	dia basa 11			
etcii (viewed Dowi	istream) Include: vegeta	ation type and loca	tion, soil horizons, woody debris	, roots, etc.	
Left Ba	ank			Right Bank	
					+
TXXXXX					
1					
			V		
				De joble ing	
				achour	
ft Bank Materials			Right Bank Materials		
□ Bedrock	□ Gravel		□ Bedrock	□ Gravel	
□ Till □ Clay	☐ Small Cobble☐ Large Cobble		□ Till □ Clay	☐ Small Cobble ☐ Large Cobble	
□ Silt	☐ Small Boulde		Silt	☐ Small Boulde	
□ Sand	☐ Large Boulde		☐ Sand	☐ Large Boulde	
Bank Height: _	0.56	m	Bank Height:	0.78	m
Bank Angle: _	70	0	Bank Angle:	75	0
Root Depth: _	0,40	m	Root Depth:	0,40	m
Root Density: Undercut: _	/	% m	Root Density: Undercut:		% m
		m m	Erosion Pin:		m m
		And to			2 2 2 2 2
Penetrometer: _	·	kg/cm²	Penetrometer:	-	kg/cm ²
Foo	ot Used: □ Yes	□ No	F	Foot Used: ☐ Yes	□ No
dditional Notes					
	- 1 P				
noto Order:	ADLK				

Project Code: 21043

Date:	2021-08-10	Reach/Cross-sect	tion: XC7
Weather:	200 540	Location:	Hamilton
Field Staff:	JI	Watershed/Subw	atershed:
		Notes	Cross-sectional Morphology
			□ Riffle □ Pool □ Run □ Other
T	211		Substrate
l l			Sample:
			□ Bed □ Bank □ Subpavement □ Water □ None
			Pebble Count (cm):
			1 11 21 31
			2 12 22 32
			3 13 23 33 4/ 14 24 34
			1
			5 15 25 35
			6. 5. 16 26 36
			7 17 27 37
N. J.			8 18 28 38
			9 19 29 39
			10 20 30 40
			Particle Shape:
115			☐ Platy ☐ Sub-angular ☐ Well Rounded
			☐ Very Angular ☐ Angular ☐ Sub-Rounded
			□ Rounded
			Embededness: %
	1 0 2 =0	4,	Subpavement:
	s 1		Sorting: ☐ Well ☐ Moderate ☐ Poor ☐ Very poor
		* * * * *	Sediment Transport
			☐ Observed ☐ Not Observed
			If Observed:
4 :			\square Suspended \square Sliding \square Rolling \square Saltation
		S	Percentage of Bed Active: %
			Velocity and Discharge
			Velocity: Method:
			☐ Estimated m/s ☐ Wiffle ball
			☐ Measuredm/s ☐ Current Meter
			Discharge: □ ADV
			☐ Estimated m³/s ☐ Marsh McBirney
			☐ Measuredm³/s ☐ Other

Completed by: _____ Checked by: _____



Page ____ of ____

Bank Characteristics

te:		Reach/XS:		
etch (Viewed Down	stream) Include: vegetation type	and location, soil horizons, woody debr	is roots etc	. 400.7
	And the second of the second o	and received, son herizons, modely debi	15, 10015, etc.	
Left Ba	ank		Right Bank	
15/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/1/			6.600	60
			DENTA	1
		Clay + 5:1+		
t Bank Materials		Right Bank Materia	ls	
□ Bedrock	☐ Gravel	□ Bedrock	☐ Gravel	
		1 1		
□ Till	☐ Small Cobble	□ Till	☐ Small Cobble	
Clay	☐ Large Cobble	Clay Clay	☐ Large Cobble	
☐ Clay ☑ Silt	☐ Large Cobble☐ Small Boulder	□ Clay -□ Silt	□ Large Cobble □ Small Boulder	
☐ Clay ☑ Silt ☐ Sand	☐ Large Cobble ☐ Small Boulder ☐ Large Boulder	□ Clay -□ Silt □ Sand	☐ Large Cobble☐ Small Boulder☐ Large Boulder☐	
□ Clay ☑ Silt □ Sand Bank Height: _	☐ Large Cobble☐ Small Boulder	□ Clay -□ Silt □ Sand Bank Height:	☐ Large Cobble ☐ Small Boulder ☐ Large Boulder ☐ m	
□ Clay ☑ Silt □ Sand Bank Height: _ Bank Angle: _	□ Large Cobble □ Small Boulder □ Large Boulder ○ G 및 m	□ Clay -□ Silt □ Sand Bank Height: Bank Angle:	□ Large Cobble □ Small Boulder □ Large Boulder □ .6 4 m	
☐ Clay ☐ Silt ☐ Sand Bank Height: _ Bank Angle: _ Root Depth: _	□ Large Cobble □ Small Boulder □ Large Boulder □	□ Clay □ Silt □ Sand Bank Height: Bank Angle: Root Depth:	□ Large Cobble □ Small Boulder □ Large Boulder □ .6 4	
☐ Clay ☐ Silt ☐ Sand Bank Height: _ Bank Angle: _ Root Depth: _ Root Density: _	□ Large Cobble □ Small Boulder □ Large Boulder □ 40 m %	□ Clay □ Silt □ Sand Bank Height: Bank Angle: Root Depth: Root Density:	□ Large Cobble □ Small Boulder □ Large Boulder □ .6 4 m □ .0 .4 m m □ .0 .4 m m □ .0 .4 m	
☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density: ☐ Undercut:	□ Large Cobble □ Small Boulder □ Large Boulder □ 0.62	□ Clay □ Silt □ Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut:	□ Large Cobble □ Small Boulder □ Large Boulder □ .6 4 m □ .0 .40 m	
☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: _ ☐ Bank Angle: _ ☐ Root Depth: _ ☐ Root Density: _ ☐ Undercut: _	□ Large Cobble □ Small Boulder □ Large Boulder □ 40 m %	□ Clay □ Silt □ Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut:	□ Large Cobble □ Small Boulder □ Large Boulder □ .6 4 m □ .0 .4 m m □ .0 .4 m m □ .0 .4 m	
☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: _ ☐ Bank Angle: _ ☐ Root Depth: _ ☐ Root Density: _ ☐ Undercut: _ ☐ Erosion Pin: _	□ Large Cobble □ Small Boulder □ Large Boulder □ 0.63	Clay Silt Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin:	Large Cobble Small Boulder Large Boulder 0.64 m 10 m 15 % m m 15 m m	m^2
☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density: ☐ Undercut: ☐ Erosion Pin: ☐ Penetrometer: ☐	□ Large Cobble □ Small Boulder □ Large Boulder □ 0.62	Clay Silt Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin:	□ Large Cobble □ Small Boulder □ Large Boulder □ .6 4 m □ .0 .40 m	
☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density: ☐ Undercut: ☐ Erosion Pin: ☐ Penetrometer: ☐	□ Large Cobble □ Small Boulder □ Large Boulder □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m	Clay Silt Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin:	Large Cobble Small Boulder Large Boulder O, 64 m AO	
Clay Silt Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin: Penetrometer:	□ Large Cobble □ Small Boulder □ Large Boulder □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m	Clay Silt Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin:	Large Cobble Small Boulder Large Boulder O, 64 m AO	
☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: _ ☐ Bank Angle: _ ☐ Root Depth: _ ☐ Root Density: _ ☐ Undercut: _ ☐ Erosion Pin: _ ☐ Penetrometer: _ ☐	□ Large Cobble □ Small Boulder □ Large Boulder □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m	Clay Silt Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin:	Large Cobble Small Boulder Large Boulder O, 64 m AO	
☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density: ☐ Undercut: ☐ Erosion Pin: ☐ Penetrometer: ☐	□ Large Cobble □ Small Boulder □ Large Boulder □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m	Clay Silt Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin:	Large Cobble Small Boulder Large Boulder O, 64 m AO	
☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: _ ☐ Bank Angle: _ ☐ Root Depth: _ ☐ Root Density: _ ☐ Undercut: _ ☐ Erosion Pin: _ ☐ Penetrometer: _ ☐	□ Large Cobble □ Small Boulder □ Large Boulder □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m □ m	Clay Silt Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin:	Large Cobble Small Boulder Large Boulder O, 64 m AO	



Date:	2021-08-19	Reach/Cross-section:	X5 g
Weather:	26° 500	Location:	Hamilton
Field Staff:	JT DM	Watershed/Subwatershed:	

X	8				Notes	Cross-sectional Morph	ology
6.30	1698		-			☐ Riffle ☐ Pool	Run 🗆 Other
6.60	17/6						
6,95	1771				-	Substrate	
7.20	1816					Sample:	
7.50	1883					☐ Bed ☐ Bank ☐ Subpa	vement 🗆 Water 🗆 None
7,70	1967					Pebble Count (cm):	
7,90	2095					1 11	21 31
8.15	2135			-	-	2	22 32 23 33 24. 34.
8,40	2151	WL				3 13	23 33
8,40	2173						
8,50	2183					5. <u>5\</u> \15	25 35
8,70	2232				-	6 16	26 36
9.00	3198					7 17	27 37
9,20	2152	0 1					28 38
9.50	2133	Rock ed				9 19	29 39
9.70	1650	Rock on				ACCUPATION AND AND AND AND AND AND AND AND AND AN	30 40
(0.00	1677	Rock	0			Particle Shape:	
10,10	1744	Rade	edge				angular Well Rounded
10.30	1686					☐ Very Angular ☐ Angul	ar ☐ Sub-Rounded
10,50	1605					☐ Rounded	er e
10.80	157	***************************************				Embededness:	
11,30	1464		***************************************			Subpavement:	
	4					Sorting:	derate 🗆 Poor 🗆 Very poo
-				1			
						Sediment Transport	
							Not Observed
		al awareness				If Observed:	
							☐ Rolling ☐ Saltation
						Percentage of Bed Active	:
						Velocity and Discharge	
						Velocity:	Method:
						☑ Estimated _ ○ _ m/	
	***************************************					☐ Measuredm,	
						Discharge:	□ ADV
		**		- entire - e		☐ Estimated m³	
						☐ Measuredm ³	/s □ Other

Completed by:	Checked by:
	Page of

Page ____ of ____

Bank Characteristics

	1-08-19		XS:		110
etch (Viewed Dow	/nstream) Include: vegeta	ation type and location, se	oil horizons, woody debris,	roots, etc.	
	M/M				
Left B	Bank			Right Bank	
1					
1	/				
	Cock	100	n	10	
	mony		lubris Di		
			of ×5		
	-1/4	- V,			
		TINALIO		\$	
	75	X 7		XF cobble	
				armourino	
)
		Clay	15:17		
ft Rank Materials		Pio	ht Bank Materials		
ft Bank Materials	□ Gravel	Rig	ht Bank Materials □ Bedrock	□ Gravel	
	☐ Gravel		□ Bedrock	□ Gravel	
☐ Bedrock ☐ Till	☐ Small Cobble		□ Bedrock □ Till	☐ Small Cobble	
☐ Bedrock			□ Bedrock	☐ Small Cobble ☐ Large Cobble	
□ Bedrock □ Till ☑ Clay	☐ Small Cobble☐ Large Cobble	r	□ Bedrock □ Till ▷ Clay	☐ Small Cobble☐ Large Cobble☐ Small Boulder	
□ Bedrock □ Till 図 Clay 風 Silt	☐ Small Cobble ☐ Large Cobble ☐ Small Boulde	r	□ Bedrock □ Till □ Clay ☑ Silt	☐ Small Cobble ☐ Large Cobble ☐ Small Boulder ☐ Large Boulder	
□ Bedrock □ Till □ Clay □ Silt □ Sand	☐ Small Cobble ☐ Large Cobble ☐ Small Boulde	r	□ Bedrock □ Till □ Clay ☑ Silt □ Sand	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ . 5)	-
□ Bedrock □ Till □ Clay □ Silt □ Sand Bank Height:	Small Cobble Large Cobble Small Boulde Large Boulde	r r m	□ Bedrock □ Till □ Clay ☑ Silt □ Sand Bank Height:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ . 5] 3 0	m
□ Bedrock □ Till □ Clay □ Silt □ Sand Bank Height: Bank Angle:	□ Small Cobble □ Large Cobble □ Small Boulde □ Large Boulde	r r m	□ Bedrock □ Till □ Clay ☑ Silt □ Sand Bank Height: Bank Angle:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0	m °
☐ Bedrock ☐ Till ☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth:	Small Cobble Large Cobble Small Boulde Large Boulde	r r m °	□ Bedrock □ Till □ Clay □ Silt □ Sand □ Bank Height: □ Bank Angle: □ Root Depth: □ Root Density: □ Undercut:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0	m °
☐ Bedrock ☐ Till ☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density:	□ Small Cobble □ Large Cobble □ Small Boulde □ Large Boulde □ 5 0 □ 3 0	r r m ° m	□ Bedrock □ Till □ Clay □ Silt □ Sand □ Bank Height: □ Bank Angle: □ Root Depth: □ Root Density: □ Undercut:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0	m ° m %
☐ Bedrock ☐ Till ☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density: ☐ Undercut: ☐ Erosion Pin:	□ Small Cobble □ Large Cobble □ Small Boulde □ Large Boulde □ 5 □	r m ° m % m	□ Bedrock □ Till □ Clay □ Silt □ Sand □ Bank Height: □ Bank Angle: □ Root Depth: □ Root Density: □ Undercut: □ Erosion Pin:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0	m ° m % m
☐ Bedrock ☐ Till ☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density: ☐ Undercut: ☐ Erosion Pin: ☐ Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulde □ Large Boulde □ 5 □	r r m ° m % m m	□ Bedrock □ Till □ Clay □ Silt □ Sand □ Bank Height: □ Bank Angle: □ Root Depth: □ Root Density: □ Undercut: □ Erosion Pin: □ Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0 2 0	m ° m % m m kg/cm²
☐ Bedrock ☐ Till ☐ Clay ☐ Silt ☐ Sand ☐ Bank Height: ☐ Bank Angle: ☐ Root Depth: ☐ Root Density: ☐ Undercut: ☐ Erosion Pin: ☐ Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulde □ Large Boulde □ 5 □	r m ° m % m	□ Bedrock □ Till □ Clay □ Silt □ Sand □ Bank Height: □ Bank Angle: □ Root Depth: □ Root Density: □ Undercut: □ Erosion Pin: □ Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0	m ° m % m
□ Bedrock □ Till □ Clay □ Silt □ Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin: Penetrometer: Fo	□ Small Cobble □ Large Cobble □ Small Boulde □ Large Boulde □ 5 □	r r m ° m % m m	□ Bedrock □ Till □ Clay □ Silt □ Sand □ Bank Height: □ Bank Angle: □ Root Depth: □ Root Density: □ Undercut: □ Erosion Pin: □ Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0 2 0	m ° m % m m kg/cm²
☐ Bedrock ☐ Till ☐ Clay ☐ Silt ☐ Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin: Penetrometer: Fo	□ Small Cobble □ Large Cobble □ Small Boulde □ Large Boulde □ 5 □	r r m ° m % m m	□ Bedrock □ Till □ Clay □ Silt □ Sand □ Bank Height: □ Bank Angle: □ Root Depth: □ Root Density: □ Undercut: □ Erosion Pin: □ Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0 2 0	m ° m % m m kg/cm²
☐ Till ☐ Clay ☐ Silt ☐ Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin: Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulde □ Large Boulde □ 5 □	r r m ° m % m m	□ Bedrock □ Till □ Clay □ Silt □ Sand □ Bank Height: □ Bank Angle: □ Root Depth: □ Root Density: □ Undercut: □ Erosion Pin: □ Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0 2 0	m ° m % m m kg/cm²
☐ Bedrock ☐ Till ☐ Clay ☐ Silt ☐ Sand Bank Height: Bank Angle: Root Depth: Root Density: Undercut: Erosion Pin: Penetrometer: Fo	□ Small Cobble □ Large Cobble □ Small Boulde □ Large Boulde □ 5 □	r r m ° m % m m	□ Bedrock □ Till □ Clay □ Silt □ Sand □ Bank Height: □ Bank Angle: □ Root Depth: □ Root Density: □ Undercut: □ Erosion Pin: □ Penetrometer:	□ Small Cobble □ Large Cobble □ Small Boulder □ Large Boulder □ 3 0 2 0	m ° m % m m kg/cm²

Page ____ of ____

Bank Characteristics

□ Bedrock □ Gravel □ Till □ Small Cobble □ Clay □ Large Cobble □ Silt □ Small Boulder □ Sand □ Large Boulder □ Bank Height: □ Sand □ Large Boulder □ Bank Angle: □ Sand □ Large Boulder □ Bank Height: □ Sand □ Large Boulder □ Bank Angle: □ Sand □ Large Boulder □ Bank Angle: □ Sand □ Large Boulder □ Bank Height: □ Sand □ Large Boulder □ Bank Height: □ Sand □ Large Boulder □ Bank Angle: □ Sand □ Large Boulder □ Bank Height: □ Sand □ Sand	te: 202	1-08-19	R	Reach/XS:	58	
Bank Materials Gravel Till Small Cobble Till Small Cobble Till Small Cobble Till Small Cobble Till Small Soulder Sand Large Soulder Sand Bank Height: One of the state o	etch (Viewed Down	nstream) Include: vege	tation type and lo	ocation, soil horizons, woody debris,	roots, etc.	
Redrock Gravel Till Small Cobble Till Small Soulder Sand Sa						
Right Bank Materials	Left Ba	ank			Right Bank	
Right Bank Materials						
Right Bank Materials	4	7				
Right Bank Materials						
Right Bank Materials						
Right Bank Materials						
Right Bank Materials						
Right Bank Materials		Cock	ino	n n	/<	
Right Bank Materials		Jarmon	11.	lubris 1		
Right Bank Materials Bedrock Gravel Till Small Cobble Clay Large Cobble Silt Small Boulder Sand Large Boulder Sand Large Boulder Bank Height: So				/ of ×5		
Right Bank Materials Bedrock Gravel Till Small Cobble Clay Large Cobble Silt Small Boulder Sand Large Boulder Sand Large Boulder Bank Height: So	1.	-1/6				
Right Bank Materials Bedrock Gravel Till Small Cobble Clay Large Cobble Silt Small Boulder Sand Large Boulder Bank Height: Sand Large Boulder Bank Angle: So			1 1 1 1 1 1 1		8	
Right Bank Materials Bedrock Gravel Till Small Cobble Clay Large Cobble Silt Small Boulder Sand Large Boulder Bank Height: Sand Large Boulder Bank Angle: So		7		7 20 -6	YF cobble	
Right Bank Materials Bedrock Gravel Till Small Cobble Clay Large Cobble Silt Small Boulder Sand Large Boulder Bank Height: Sand Large Boulder Bank Angle: So					armonfine	
Right Bank Materials Bedrock Gravel Till Small Cobble Clay Large Cobble Silt Small Boulder Sand Large Boulder Bank Height:						
Right Bank Materials Bedrock Gravel Till Small Cobble Clay Large Cobble Silt Small Boulder Sand Large Boulder Bank Height:			Clay	+5:17		
□ Bedrock □ Gravel □ Till □ Small Cobble □ Clay □ Large Cobble □ Silt □ Small Boulder □ Sand □ Large Boulder □ Bank Height: □ Sand □ Large Boulder □ Bank Angle: □ Sand □ Sand						
Bedrock						
□ Bedrock □ Gravel □ Till □ Small Cobble □ Clay □ Large Cobble □ Silt □ Small Boulder □ Sand □ Large Boulder □ Bank Height: □ Sand □ Large Boulder □ Bank Angle: □ Sand □ Sand	ft Bank Materials			Right Bank Materials		
Clay Large Cobble Silt Small Boulder Sand Large Boulder Sand Large Boulder Sand Large Boulder Bank Height:	☐ Bedrock	☐ Gravel			☐ Gravel	
Silt Small Boulder Sand Large Boulder	□ Till	☐ Small Cobble	e	□ Till	☐ Small Cobble	
Sand	© Clay	☐ Large Cobble	e	□ Clay	☐ Large Cobble	
Bank Height:	☑ Silt	☐ Small Boulde	er	⊠ Silt	☐ Small Boulder	r
Bank Angle: 50 ° Root Depth: 0.30 m Root Density: 20 % Root Density: 20 % Undercut: m Undercut: m Erosion Pin: m Erosion Pin: m Erosion Pin: m Penetrometer: kg/cm² Penetrometer: kg/cm² Foot Used: □ Yes □ No Foot Used: □ Yes □ No	☐ Sand	☐ Large Boulde	er	☐ Sand		г
Root Depth:	Bank Height: _		m	Bank Height:		m
Root Density:	Bank Angle: _	50	0	Bank Angle:		۰
Undercut: m	Root Depth: _	0.00	m	Root Depth:	030	m
Erosion Pin: m	Root Density: _	20	%	Root Density:	20	%
Penetrometer: kg/cm² Penetrometer: kg/cm² Foot Used: □ Yes □ No	Undercut: _		m	Undercut:		m
Foot Used:				1		
Foot Used:	Erosion Pin: _		m	Erosion Pin:		m
dditional Notes UDIR			NO. 20 .	entero per de contentido de magantas		
u DIR	Penetrometer: _		kg/cm²	Penetrometer:		kg/cm²
noto Order:	Penetrometer: _		kg/cm²	Penetrometer:		kg/cm²
hoto Order:	Penetrometer: _ Foo		kg/cm²	Penetrometer:		kg/cm²
hoto Order:	Penetrometer: _		kg/cm²	Penetrometer:		kg/cm²
hoto Order:	Penetrometer: _ Foo	ot Used: □ Yes	kg/cm²	Penetrometer:		kg/cm²
	Penetrometer: Foo dditional Notes	ot Used: □ Yes	kg/cm²	Penetrometer:		kg/cm²
	Penetrometer:Foo	ot Used: □ Yes	kg/cm²	Penetrometer:		kg/cm²

Appendix D Detailed Assessment Summary



Detailed Geomorphological Assessment Summary

Reach: Watercourse 5


Project Number:	PN21043	Date:	2021-08-19
Client:	Urbantech Consulting	Length Surveyed (m):	86.1
Location:	Hamilton	# of Cross-Sections:	8

Reach Characteristics 167.1 ha Drainage Area: **Dominant Riparian Vegetation Type:** Trees Geology/Soils: Paleozoic Bedrock **Extent of Riparian Cover:** Continuous 4-10 Channel Widths Surrounding Land Use: Residential/Agricultural Width of Riparian Cover: Valley Type: Unconfined Established (5-30 Years) Age Class of Riparian Vegetation: Minimal **Dominant Instream Vegetation Type:** Algae **Extent of Encroachment into Channel:** 10% Portion of Reach with Vegetation: **Density of Woody Debris:** Low

Hydrology			
Measured Discharge (m ³ /s):	Not measured	Calculated Bankfull Discharge (m ³ /s):	1.31
Modelled 2-year Discharge (m ³ /s):	Not modelled	Calculated Bankfull Velocity (m/s):	1.06
Modelled 2-year Velocity (m/s):	Not modelled		

Profile Characteristics	
Bankfull Gradient (%):	0.76
Channel Bed Gradient (%):	0.42
Riffle Gradient (%):	n/a
Riffle Length (m):	n/a
Riffle-Pool Spacing (m):	n/a

Planform Characteristics	
Sinuosity:	1.29
Meander Belt Width (m):	Not measured
Radius of Curvature (m):	Not measured
Meander Amplitude (m):	Not measured
Meander wavelength (m):	Not measured



Bank Characteristics										
	Minimum	Maximum	Average		Minimum	Maximum	Average			
Bank Height (m):	0.40	0.78	0.62							
Bank Angle (deg):	30	85	64	Torvane Value (kg/cm²):		Not measured				
Root Depth (m):	0.10	0.40	0.27	Penetrometer Value (kg/cm ³):		Not measured				
Root Density (%):	10	60	28	Bank Material (range):	Silty	-clay loam (unif	orm)			
Bank Undercut (m):	0.00	0.03	0.00							


GEO Morphix Ltd. Page 1 of 3

Cross-Sectional Characteristics									
	Minimum	Maximum	Average						
Bankfull Width (m):	2.60	5.00	3.64						
Average Bankfull Depth (m):	0.13	0.42	0.34						
Bankfull Width/Depth (m/m):	7	38	13						
Wetted Width (m):	0.10	1.80	1.22						
Average Water Depth (m):	0.01	0.11	0.05						
Wetted Width/Depth (m/m):	4	60	28						
Entrenchment (m):		Not measured							
Entrenchment Ratio (m/m):		Not measured							
Maximum Water Depth (m):	0.04	0.20	0.11						
Manning's <i>n</i> :		0.040							



Photograph at cross section 6 (looking downstream)

Representative Cross-Section #6



article Size (mm)				Subpa	veme	nt:			Shale	e			
D ₁₀ :	<2			Partic	le sha	pe:			N/A				
D ₅₀ :	<2			Embe	ddedn	ess (%):		N/A				
D ₈₄ :	<2			Partic	le ran	ge (r	iffle)):	Silt t	o clay			
				Partic	le Ran	ige (pool)):	Silt t	o clay			
100													
			- 1 1										1 1
90						+							
80													
80 - 70 -													
80 - 70 -													
80 - 70 -													
80 70 60 50 40 30													
80 70 60 50 40													

GEO Morphix Ltd. Page 2 of 3

Channel Thresholds			
Flow Competency (m/s):		Tractive Force at Bankfull (N/m²):	25.33
for D ₅₀ :	n/a	Tractive Force at 2-year flow (N/m^2) :	Not modelled
for D ₈₄ :	n/a	Critical Shear Stress (D ₅₀) (N/m ²):	n/a
Unit Stream Power at Bankfull (W/m²):	26.86		

General Field Observations

Channel Description


Watercourse 5 flows through an unconfined valley surrounded by a mix of residential and agricultural areas. The continuous extent of riparian vegetation consists of grasses, herbaceous vegetation, shrubs, and trees. This vegetation is established on the landscape and only minimally encroaches upon the channel. The average bankfull width and depth are 3.64 m and 0.34 m, respectively. Both the bed and bank material is comprised primarily of a compact silty clay loam, with trace amounts of shale pebbles observed. No riffle-pool sequeces are present within the reach. The channel generally exhibits a trapezoidal cross-section shape, with bank angles ranging from 30 to 85. Undercutting and active erosion of the banks was not prevelant. Flow velocities were imperceptible during the assessment.


Photo of typical channel conditions, facing upstream



GEO Morphix Ltd. Page 3 of 3


Appendix E Erosion Modelling Hydrographs






Project #: PN21043


ii




Project #: PN21043




Project #: PN21043



PLANFORM



PROFILE H = 1:500; V=1:50



- 1. THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN
- CONJUNCTION WITH THIS DRAWING SET. 2. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING
- CONSTRUCTION FOR REFERENCE.

 3. THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES. 5. LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED
- ENGINEER, AND THE CONTRACT ADMINISTRATOR.
- CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
- 7. ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G., GEOTECHNICAL, HYDROGEOLOGICAL, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.

PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

8. BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL,

TIMING OF WORKS

- 1. WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRF/DFO. TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO
- COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE
- OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF 3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN
- ONLY DURING FAVOURABLE WEATHER CONDITIONS. 4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

SITE AND MATERIAL MANAGEMENT

- 1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m
- AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED
- IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN. 3. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
- 4. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW. 5. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR
- MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
- 6. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
- 7. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED,
- UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.

 8. AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ONSITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

EROSION AND SEDIMENT CONTROL

- 1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS. 2. FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITÉ VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES, DEWATERING, AND IN- OR NEAR-WATER WORKS. SHOULD CONCERNS ARISE; THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND
- ANY OTHER APPROPRIATE PARTIES. 3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE
- 4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER
- 5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
- 6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
 7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE
- 8. THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING
- SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION. 9. IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT 1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY

- OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAVINE OR STORM SEWER SYSTEM. 2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS,
- EXCESS OIL, AND GREASE.

 3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
- A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE. 5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS
- SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

WORK AREA ISOLATION

- 1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
 2. CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT
- PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM
- EITHER SIDES OF THE WATERCOURSE OR WETLAND. 3. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 M FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER.
- 4. FISH MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTRY

1.	24/03/15	LD	FIRST	CONCE	PTUAL DESIGN SUBMISSION	
	DATE	BY			REVISIONS	
DESIG	SNED BY: LD				CHECKED BY: PV	
DRAW	/N BY: AS / SG	ì			DATE: APRIL 2024	

NOT FOR CONSTRUCTION **SCALED FOR PLOT** ON 'ARCH D'

M O R P H I X™ 36 Main St N., P.O. Box 205 Campbellville, Ontario L0P 1B0

T: 416.920.0926


www.geomorphix.com


24/03/15 BLOCK 1 BSS FRUITLAND-WINONA BLOCK 1 OWNERS

WATERCOURSE 5 CONCEPTUAL CHANNEL DESIGN PLANFORM AND PROFILE


GROUP, HAMILTON

PROJECT No.: 21043 DRAWING No.: GEO-1 SHEET 1 OF 5 SCALE: AS NOTED





PROFILE H = 1:500; V=1:50



GENERAL NOTES

- 1. THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN
- CONJUNCTION WITH THIS DRAWING SET.

 2. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR DEFERENCE.
- CONSTRUCTION FOR REFERENCE.

 3. THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
- THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
 LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED
- ENGINEER, AND THE CONTRACT ADMINISTRATOR.

 CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR
- CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
 ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G., GEOTECHNICAL, HYDROGEOLOGICAL, AND/OR WATER
- RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
- 8. BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

TIMING OF WORKS

- WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRF/DFO.
 TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUT.
- COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF
- NESTING BIRDS.

 3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
- 4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

SITE AND MATERIAL MANAGEMENT

- 1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m
- AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED STAGING/STORAGE AREA.

 2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
- AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.

 3. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
- STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW.
 MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR
- MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
- 6. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
- 7. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.
- UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.

 8. AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ONSITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

EROSION AND SEDIMENT CONTROL

- ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS.
 FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES, DEWATERING, AND IN- OR NEAR-WATER WORKS. SHOULD CONCERNS ARISE; THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND
- ANY OTHER APPROPRIATE PARTIES.

 3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE
- MONITORING.
 4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER
- 5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
- 6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.
 7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE
- 8. THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION.
- 9. IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT 1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY

- OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAVINE OR STORM SEWER SYSTEM.

 2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL AND GREASE
- 3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR SURFACE WATER DRAINAGE.
- A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A
 DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE.
 THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETE.
- THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

WORK AREA ISOLATION

- ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
 CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT
- PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND.
- 3. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 M FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER.
- 4. FISH MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTRY

1.	24/03/15	LD	FIRST CONCEPTUAL DESIGN SUBMISSION
	DATE	BY	REVISIONS

DESIGNED BY: LD CHECKED BY: PV

DRAWN BY: AS / SG DATE: APRIL 2024

24/03/15

NOT FOR CONSTRUCTION SCALED FOR PLOT ON 'ARCH D' MORPHIX™
36 Main St N., P.O. Box 205
Campbellville, Ontario L0P 1B0

T: 416.920.0926 www.geomorphix.com


BLOCK 1 BSS

FRUITLAND-WINONA BLOCK 1 OWNERS GROUP, HAMILTON


WATERCOURSE 5
CONCEPTUAL CHANNEL DESIGN
PLANFORM AND PROFILE

PROJECT No.: 21043 DRAWING No.: GEO-2


SCALE: AS NOTED SHEET 2 OF 5



PLANFORM 1:500



PROFILE H = 1:500; V=1:50



- 1. THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN CONJUNCTION WITH THIS DRAWING SET.
- 2. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING
- CONSTRUCTION FOR REFERENCE.

 3. THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES. 5. LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED
- ENGINEER, AND THE CONTRACT ADMINISTRATOR.
- 6. CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
- 7. ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G., GEOTECHNICAL, HYDROGEOLOGICAL, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
- 8. BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

- 1. WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRF/DFO. TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE
- OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF
- 3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS. 4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

- SITE AND MATERIAL MANAGEMENT 1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m
- AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED
- 2. IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN. 3. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS.
- STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW. 5. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR
- MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
- 6. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS. 7. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED,
- UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.

 8. AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ONSITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

EROSION AND SEDIMENT CONTROL

1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS. 2. FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES, A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITÉ VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES, DEWATERING, AND IN- OR NEAR-WATER WORKS. SHOULD CONCERNS

ARISE; THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND

- ANY OTHER APPROPRIATE PARTIES. 3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE
- 4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER
- 5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
- 6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED.

 7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE
- 8. THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION.
- 9. IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT

- 1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY, RAVINE OR STORM SEWER SYSTEM. 2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL, AND GREASE. 3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR
- SURFACE WATER DRAINAGE. 4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE.
- 5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

WORK AREA ISOLATION

- 1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
 2. CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT
- PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND.
- 3. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 M FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER.
- 4. FISH MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTRY

1.	24/03/15	LD	FIRST CONCEPTUAL DESIGN SUBMISSION			
	DATE	BY			REVISIONS	
DESIG	DESIGNED BY: LD				CHECKED BY: PV	
DRAW	DRAWN BY: AS / SG				DATE: APRIL 2024	
			·			

NOT FOR CONSTRUCTION **SCALED FOR PLOT** ON 'ARCH D'

24/03/15

M O R P H I X™ 36 Main St N., P.O. Box 205 Campbellville, Ontario L0P 1B0


T: 416.920.0926


www.geomorphix.com


BLOCK 1 BSS FRUITLAND-WINONA BLOCK 1 OWNERS GROUP, HAMILTON

WATERCOURSE 5 CONCEPTUAL CHANNEL DESIGN PLANFORM AND PROFILE

PROJECT No.: 21043 DRAWING No.: GEO-3 SHEET 3 OF 5 SCALE: AS NOTED








- 5. BRANCHES TO BE PLACED ON SLOPE WITH BUTT END TOWARDS VALLEY FLOOR AND PUSHED INTO SOIL. 6. BRANCHES MUST BE FLEXIBLE ENOUGH TO CONFORM TO THE SLOPE SURFACE IRREGULARITIES.
- 7. POUND DEAD STAKES TO HALF THEIR LENGTH INTO SOIL BETWEEN BRANCHES. TIE COIR TWINE AROUND DEAD STAKES AND TIGHTLY
- OVER BRANCHES. USE A CLOVE HITCH TO SECURE STAKES. POUND STAKES INTO SLOPE TO COMPRESS BRANCHES AGAINST GROUND.
- 8. TAMP LIVE STAKES BETWEEN DEAD STAKES.

9. FILL VOIDS BETWEEN BRANCHES OF THE BRUSH MATTRESS WITH SOIL TO PROMOTE ROOTING.


BRUSH MATTRESS



- HEIGHT OF TERRESTRIAL MOUND SHALL BE 1000 mm TO 2000 mm.
- 2. PLACEMENT OF VEGETATED TERRESTRIAL MOUND TO BE AS PER PLAN, IN DRY AREAS ONLY.
- 3. CONSTRUCTION OF MOUND TO BE COMPLETED IN CONJUNCTION WITH SITE GRADING ACTIVITIES AS TERRESTRIAL MOUNDS TO BE GRADED TO MATCH
- EXISTING GROUND AND/OR TIE INTO EXISTING SLOPES. 4. TERRESTRIAL MOUND TO BE SLIGHTLY CONCAVE/DIMPLED ON TOP.
- 5. SEED MIX TO BE COMPRISED OF RIPARIAN / UPLAND SPECIES AS PER PLANTING


TERRESTRIAL MOUND

N.T.S



- 1. LARGEST AND HEAVIEST LOG MATERIAL SHOULD BE PLACED ON THE BASE OF THE BRUSH PILE. THE SMALLEST BRUSH MATERIAL SHOULD BE PLACED AT THE TOP.
- 2. LOGS SHOULD BE FORMED INTO A PALLET SHAPE.
- 3. HEIGHT OF BRUSH PILE IS NOT TO EXCEED 1.0 M.
- 4. A MIX OF HARDWOOD AND SOFTWOOD SHOULD BE USED.
- 5. PLANT WITH NATIVE FRUIT BEARING VINES.

PALLET TYPE WOOD PILE



- 1. THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023) PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN
- CONJUNCTION WITH THIS DRAWING SET. 2. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING
- CONSTRUCTION FOR REFERENCE.

 3. THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE WORK AT LEAST 48 HOURS IN ADVANCE.
- 4. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES. 5. LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED
- ENGINEER, AND THE CONTRACT ADMINISTRATOR.
- 6. CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
- 7. ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G., GEOTECHNICAL, HYDROGEOLOGICAL, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
- 8. BE ADVISED THAT THE LOCAL REGULATORY BODY MAY, AT ANY TIME, WITHDRAW THIS PERMISSION, IF, IN THE OPINION OF THE AUTHORITY. THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL, PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

TIMING OF WORKS

- 1 WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRE/DEO TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE
- OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF
- 3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS. 4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

SITE AND MATERIAL MANAGEMENT

- 1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m
- AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN. OR IN A DESIGNATED
- IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
- 3. STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS. 4. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW.
- 5. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
- 6. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
- 7. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED, UNLESS OTHERWISE AUTHORIZED IN THE APPLICABLE PERMIT.
- AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ONSITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

EROSION AND SEDIMENT CONTROL

- 1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS. 2. FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES. A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES, DEWATERING, AND IN- OR NEAR-WATER WORKS. SHOULD CONCERNS ARISE; THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND
- ANY OTHER APPROPRIATE PARTIES. 3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE
- 4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER
- 5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE APPROVED BY THE CONTRACT ADMINISTRATOR.
- 6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE
- IMMEDIATE REPAIRS AND/OR UPGRADES AS NEEDED. 7. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE
- 8. THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING
- SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION. 9. IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT

1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY. RAVINE OR STORM SEWER SYSTEM. 2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS,

- 3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR
- SURFACE WATER DRAINAGE. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE.
- 5. THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS
- SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

WORK AREA ISOLATION

- 1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST BE USED FOR UNWATERING.
 2. CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT
- PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM EITHER SIDES OF THE WATERCOURSE OR WETLAND.
- 3. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 M FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER.
- 4. FISH MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTR'S

1.	24/03/15	LD	FIRST	CONCE	PTUAL DESIGN SUBMISSION
	DATE	BY			REVISIONS
DESIG	GNED BY: LD				CHECKED BY: PV
DRAW	/N BY: AS / SG	i			DATE: APRIL 2024

NOT FOR CONSTRUCTION **SCALED FOR PLOT** ON 'ARCH D'



T: 416.920.0926 www.geomorphix.com


Campbellville, Ontario L0P 1B0

BLOCK 1 BSS FRUITLAND-WINONA BLOCK 1 OWNERS GROUP, HAMILTON

WATERCOURSE 5 CONCEPTUAL CHANNEL DESIGN **DETAILS**

DRAWING No.: DET-1 PROJECT No.: 21043 SHEET 4 OF 5 SCALE: AS NOTED

24/03/15




WETLAND CROSS SECTION


1. SUBSTRATES TO BE COMPACTED TO 90% SPD TO PREVENT PIPING/FLOW-THROUGH.

2. FINE NATIVE MATERIAL TO BE ADDED TO SUBSTRATE MIX TO FILL INTERSTITIAL VOIDS, AS REQUIRED.

3. GRANULAR 'B' TO BE SOURCED FROM PIT-RUN MATERIAL AND ROUNDED IN NATURE. NO CRUSHED ROCK, LIMESTONE OR POST-CONSTRUCTION MATERIALS ARE TO BE USED WITHIN THE CHANNEL. MATERIAL TO BE REVIEWED BY THE DESIGNER OR REPRESENTATIVE PRIOR TO INSTALLATION.



ONLINE WETLAND CROSS SECTION



SPECIES AND QUANTITIES

3. GRANULAR 'B' TO BE SOURCED FROM PIT-RUN MATERIAL AND ROUNDED IN

DESIGNER OR REPRESENTATIVE PRIOR TO INSTALLATION.

NATURE. NO CRUSHED ROCK, LIMESTONE OR POST-CONSTRUCTION MATERIALS

ARE TO BE USED WITHIN THE CHANNEL. MATERIAL TO BE REVIEWED BY THE

DRAWINGS FOR SEED MIX SPECIFICATIONS.

VOIDS, AS REQUIRED.

COMMON NAME SCIENTIFIC NAME RED OSIER DOGWOOD Cornus stolonifera **PUSSY WILLOW** Salix discolor SANDBAR WILLOW Salix exigua

- QUANTITY TO BE DETERMINED BASED ON AREA OF DISTURBANCE TO BE RESTORED
- 2. LIVE STAKES SHOULD BE FROM AT MINIMUM 2-YEAR OLD STOCK.
- 3. LIVE STAKES ARE TO BE INSTALLED AT A DENSITY OF 3 STAKES PER SQUARE METRE. 4. LIVE STAKES SHOULD BE PRE-SOAKED (SUBMERGED IN WATER) FOR AT LEAST 24 HOURS AFTER HARVESTING AND IMMEDIATELY BEFORE INSTALLATION.
- 5. LIVE STAKES SHOULD NOT BE STORED FOR A PERIOD LONGER THAN 2 DAYS. UNLESS THEY ARE BEING SOAKED.
- 6. THE CONTRACTOR SHALL PROTECT PLANT MATERIALS FROM DRYING FROM THE TIME OF HARVEST UNTIL INSTALLED.
- 7. LIVE STAKES ARE TO BE A MINIMUM OF 25 mm IN DIAMETER AND CUT TO A LENGTH OF
- 8. CUT ANGLE AT THE BOTTOM OF THE STAKE AND FLAT ON THE TOP.
- 9. TRIM ALL SIDE BRANCHES WHILE TAKING CARE NOT TO DAMAGE THE BARK.
- 10. INSTALL STAKES WITH BUDS POINTING UPWARDS AND THICKER STEM IN THE BED.
- 11. LIVE STAKES SHOULD BE INSTALLED USING A LARGE RUBBER MALLET. 12. 80% OF THE STAKE IS TO BE BELOW SURFACE.
- 13. TAMP THE LIVE STAKE INTO THE GROUND AT RIGHT ANGLE TO THE SURFACE.
- 14. IN COMPACT SOIL A PILOT HOLE SHOULD BE USED TO LIMIT DAMAGE TO THE STAKES.
- IF USING A PILOT HOLE REPACK SOIL AROUND THE LIVE STAKE.
- 16. LIVE STAKES SHOULD STAND FIRM FROM THE SOIL FOLLOWING INSTALLATION.
- 17. ALL STAKES NOT PLANTED TO THE SPECIFICATIONS ABOVE WILL BE REPLACED AT THE CONTRACTOR'S EXPENSE.

LIVE STAKE


EROSION CONTROL BLANKET SPECIFICATIONS

1 m

1 m


1 m

- 1. A BIODEGRADABLE EROSION CONTROL BLANKET (ECB) SHALL BE INSTALLED ON ALL DISTURBED NATURAL SURFACES FOLLOWING THE PLACEMENT OF TOPSOIL AND APPLICATION OF THE NATIVE SEED MIX.
- 2. THE ECB MUST BE CONSTRUCTED OF 100% WOVEN COCONUT FIBRE (E.G., COIR) OR STRAW MAT WITHIN A GEOJUTE NETTING (TOP AND BOTTOM) WITH BIODEGRADABLE THREAD. NON-BIODEGRADABLE MATERIAL INCLUDING POLYPROPELENE OR PLASTICS WITH A BIODEGRADABLE RATING ARE NOT ACCEPTABLE. THE MINIMUM WEIGHT OF THE ECB MUST BE $400 \text{ g/m}^2 (12 \text{ oz./yd}^2).$
- 3. TO INSTALL, THE ECB MUST BE UNROLLED DOWNSLOPE OR IN DIRECTION OF WATER FLOW. ADJACENT ECBS SHOULD OVERLAP A MINIMUM OF 150 mm ALONG THE EDGES. AT THE END OF EACH ROLL, FOLD BACK 100 mm TO 200 mm OF THE ECB. OVERLAP THIS 100 mm TO 200 mm OVER THE START OF THE NEXT ROLL. SECURE THE TWO LAYERS TO THE GROUND SECURELY.
- 4. BIODEGRADABLE OR TAPERED WOODEN STAKES SHALL BE USED TO SECURE THE BLANKET. STAKES SHALL BE INSTALLED AT THE SPACING RECOMMENDED BY THE ECB MANUFACTURER TO PREVENT SURFACE RUNOFF FROM ERODING THE UNDERLYING SOIL.




- CONSTRUCT WITH CONIFER TRUNKS WITH TWO OR MORE
- NATURAL BRANCHES.
- 2. AT LEAST 75% OF THE BARK SHOULD BE INTACT.
- 3. AUGER HOLE TO A DEPTH OF ~1.0 m INSTALL TRUNK AND TAMP IN SAND AROUND BASE.
- 4. ~1.0 m OF TRUNK IS TO BE BURIED.
- 5. PLACE 0.50 m 0.60 m STONE AROUND BASE FOR ADDITIONAL
- 6. IF ROOT WAD IS USED PLACE ROOT AT TOP. LOGS SHOULD BE SOURCED ON SITE (WHERE POSSIBLE).
- 8. AT LEAST 4 RAPTOR POLES ARE TO BE 5 m IN HEIGHT.

RAPTOR POLE




- 50 mm 200 mm STONE MIX WITH SOME ANGULAR STONES. 2. THE STONE MIX SHOULD PROVIDE A VARIETY OF INTERSTITIAL
- 3. PILES ARE AT LEAST 1500 mm IN DIAMETER AND ~1000 mm HIGH. 4. PARTIALLY BURY PILES 300 - 400 mm TO AVOID ROCKFALL

ROCK PILE



- ANCHOR AND SUPPORT BASKING LOGS WITH 75 mm 200 mm STONE MIX. 2. FIRMLY COMPACT STONE MIX TO PREVENT THROUGH FLOW.
- 3. BURY 1/3 OF LOG INTO SOIL.
- 4. LENGTH OF BASKING LOGS ARE TO BE INSTALLED 1000 1500 mm INTO WET AREA. 5. BASKING LOGS TO BE A MINIMUM 500 mm IN DIAMETER AND 2000 - 2500 mm IN LENGTH.
- BASKING LOGS SHOULD BE ANGLED TO PROMOTE TURTLE BASKING.
- 7. BASKING LOGS SHOULD BE A MIXTURE OF SUITABLE HARDWOOD AND SOFTWOOD
- 8. BASKING LOGS SHOULD BE DOUBLED UP IN SPECIFIED LOCATIONS

BASKING LOG



- 1. THE ACCOMPANYING CHANNEL REALIGNMENT TECHNICAL DESIGN BRIEF PREPARED BY GEO MORPHIX LTD. (2023)
- PROVIDES ADDITIONAL DESIGN DETAILS AND DIRECTION FOR IMPLEMENTATION AND IS TO BE REVIEWED IN CONJUNCTION WITH THIS DRAWING SET
- 2. ALL CONTRACT DRAWINGS, SPECIFICATIONS AND APPLICABLE PERMITS MUST BE KEPT ON SITE DURING CONSTRUCTION FOR REFERENCE. 3. THE CONTRACTOR MUST NOTIFY THE DESIGNER AND CONTRACT ADMINISTRATOR OF THE INTENT TO COMMENCE
- WORK AT LEAST 48 HOURS IN ADVANCE 4. THE CONTRACTOR IS RESPONSIBLE FOR ALL UTILITY LOCATES.
- 5. LAYOUT MUST BE REVIEWED AND APPROVED BY THE DESIGNER / DESIGNER REPRESENTATIVE, DESIGNATED ENGINEER, AND THE CONTRACT ADMINISTRATOR.
- 6. CONSTRUCTION OBSERVATION IS TO BE PERFORMED BY A CERTIFIED FLUVIAL GEOMORPHOLOGIST OR EXPERIENCED ENVIRONMENTAL INSPECTOR UNDER DIRECTION FROM THE DESIGNER.
- ON-SITE SUPPORT FROM PROJECT ENGINEER (E.G., GEOTECHNICAL, HYDROGEOLOGICAL, AND/OR WATER RESOURCES ENGINEER) REQUIRED TO ASSESS AND ENSURE FAVOURABLE SURFICIAL AND SUBSURFACE CONDITIONS TO SUPPORT CHANNEL REALIGNMENT CONSTRUCTION.
- OPINION OF THE AUTHORITY, THE CONDITIONS OF THE PERMIT ARE NOT BEING COMPLIED WITH. THIS APPROVAL DOES NOT EXEMPT THE PROPERTY OWNER/APPLICANT/AGENT FROM THE PROVISIONS OF ANY OTHER FEDERAL PROVINCIAL OR MUNICIPAL STATUTES, REGULATIONS OR BY-LAWS, OR ANY RIGHTS UNDER COMMON LAW.

- 1 WORKS SHALL BE COMPLETED DURING THE DESIGNATED IN-WATER WORKS WINDOW SET OUT BY MNRE/DEO TREE CLEARING IS TO BE COMPLETED OUTSIDE THE BIRD NESTING SEASON (APRIL 1ST TO AUGUST 1ST) TO
- COMPLY WITH THE FEDERAL MIGRATORY BIRDS CONVENTION ACT. ANY TREES THAT REQUIRE REMOVAL OUTSIDE OF THIS TIMING WINDOW MUST FIRST BE INSPECTED BY A QUALIFIED BIOLOGIST TO DETERMINE THE PRESENCE OF
- 3. THE WEATHER FORECAST SHOULD BE CONTINUALLY MONITORED TO ENSURE THAT WORKS ARE UNDERTAKEN ONLY DURING FAVOURABLE WEATHER CONDITIONS.
- 4. COMPLETE THE WORKS WITH MINIMAL AVOIDABLE INTERRUPTIONS ONCE THEY COMMENCE.

SITE AND MATERIAL MANAGEMENT

- 1. ALL CONSTRUCTION EQUIPMENT AND MATERIALS (IMPORTED OR EXCAVATED) MUST BE STORED AT LEAST 30 m
- AWAY FROM ANY WATERBODY IN A STABLE AREA ABOVE THE ACTIVE FLOODPLAIN, OR IN A DESIGNATED
- IN THE EVENT OF AN UNEXPECTED STORM, ALL UNFIXED ITEMS THAT HAVE THE POTENTIAL TO CAUSE A SPILL OR AN OBSTRUCTION TO FLOW MUST BE MOVED A STABLE AREA ABOVE ACTIVE FLOODPLAIN.
- STOCKPILES MUST BE LOCATED OUTSIDE THE ISOLATED WORK AREAS
- 4. STABILIZE, TEMPORARILY OR PERMANENTLY, ANY DISTURBED AREAS AS WORK PROGRESSES, OR SOON AS CONDITIONS ALLOW.
- 5. MINIMIZE THE AREA OF DISTURBANCE TO THE EXTENT POSSIBLE. ALL DISTURBED GROUND LEFT INACTIVE FOR
- MORE THAN 30 DAYS SHALL BE STABILIZED USING APPROPRIATE EROSION CONTROL MEASURES AND AN APPROPRIATE SEED MIX AS NOTED WITHIN THE FINAL APPROVED RESTORATION PLAN.
- 6. ALL VEGETATION, ADJACENT TO THE WORK AREA, MUST BE PROTECTED AND DELINEATED WITH CONSTRUCTION FENCING OR TREE PROTECTION BARRIERS.
- 7. ALL GRADES IN THE AREA REGULATED BY THE CONSERVATION AUTHORITY MUST BE MAINTAINED OR MATCHED,
- 8. AN AFTER-HOURS CONTACT NUMBER IS TO BE VISIBLY POSTED ONSITE FOR EMERGENCIES. ALL THE PLANS SHOULD HAVE NAME AND CONTACT INFO OF THE PERSON RESPONSIBLE FOR ESC MEASURES.

EROSION AND SEDIMENT CONTROL

- 1. ALL TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES MUST BE INSTALLED PRIOR TO START OF WORKS FOLLOWING INSTALLATION OF THE PROPOSED ESC MEASURES. A QUALIFIED AGENT OF THE PROPONENT (E.G. CAN-CISEC CERTIFIED MONITOR) WILL CONDUCT REGULAR SITE VISITS TO MONITOR ALL WORKS, PARTICULARLY THE CONDITION OF THE ESC MEASURES, DEWATERING, AND IN- OR NEAR-WATER WORKS. SHOULD CONCE
- ARISE; THE ENVIRONMENTAL MONITOR WILL CONTACT THE PROPONENT, THE CONSERVATION AUTHORITY, AND ANY OTHER APPROPRIATE PARTIES.
- 3. EROSION AND SEDIMENT CONTROLS MUST BE MAINTAINED DURING CONSTRUCTION, AND ANY REQUIRED REPAIRS OR REPLACEMENTS MUST BE COMPLETED WITHIN 24 HOURS AFTER THEY HAVE BEEN IDENTIFIED DURING THE
- 4. EROSION AND SEDIMENT CONTROLS MAY REQUIRE PERIODIC ADJUSTMENTS TO REFLECT CHANGING SITE CONDITIONS. THE CONTRACTOR WILL BE RESPONSIBLE FOR THESE ADJUSTMENTS TO ENSURE PROPER
- 5. ANY CHANGES TO THE EROSION AND SEDIMENT CONTROL PLAN BEYOND MINOR ADJUSTMENTS MUST BE
- APPROVED BY THE CONTRACT ADMINISTRATOR
- 6. ADDITIONAL EROSION AND SEDIMENT CONTROL SUPPLIES MUST BE KEPT ON SITE IN ORDER TO FACILITATE
- ${\tt IMMEDIATE\ REPAIRS\ AND/OR\ UPGRADES\ AS\ NEEDED}.$. ALL TEMPORARY SEDIMENT CONTROLS MUST BE REMOVED AFTER THE CONTRACT ADMINISTRATOR DEEMS THE
- 8. THE PROJECT PROPONENT OR THEIR REPRESENTATIVE IS ULTIMATELY RESPONSIBLE FOR CONTROLLING
- SEDIMENT AND EROSION WITHIN THE CONSTRUCTION SITE FOR THE TOTAL PERIOD OF THE CONSTRUCTION 9. IF EXCESSIVE SILTATION RESULTS FROM THE CONSTRUCTION ACTIVITIES, THE ONSITE SUPERVISOR/INSPECTOR AND/OR THE LOCAL REGULATORY BODY RESERVE THE RIGHT TO REQUEST ADDITIONAL ESC MEASURES WHICH WOULD BE INSTALLED PRIOR TO FURTHER CONSTRUCTION ACTIVITIES.

DELETERIOUS SUBSTANCE CONTROL/SPILL MANAGEMENT

- 1. PREVENT THE RELEASE OF SEDIMENT, SEDIMENT-LADEN WATER, RAW CONCRETE, CONCRETE LEACHATE OR ANY OTHER DELETERIOUS SUBSTANCES INTO ANY WATERBODY. RAVINE OR STORM SEWER SYSTEM.
- 2. ENSURE EQUIPMENT AND MACHINERY ARE IN GOOD OPERATING CONDITION (POWER WASHED), FREE OF LEAKS, EXCESS OIL, AND GREASE 3. NO EQUIPMENT REFUELLING OR SERVICING SHOULD BE UNDERTAKEN WITHIN 30 m OF ANY WATERCOURSE OR
- SURFACE WATER DRAINAGE. 4. A SPILL CONTAINMENT KIT MUST BE READILY ACCESSIBLE ON SITE IN THE EVENT OF A RELEASE OF A DELETERIOUS SUBSTANCE TO THE ENVIRONMENT. ONSITE STAFF MUST BE TRAINED IN ITS USE.
- THE CONTRACT ADMINISTRATOR MUST BE NOTIFIED IMMEDIATELY IN THE EVENT OF A SPILL OF DELETERIOUS
- SUBSTANCE. ANY SEDIMENT SPILL FROM THE SITE SHOULD BE REPORTED TO MINISTRY OF ENVIRONMENT (SPILL ACTION CENTER) AT 1-800-268-6060.

WORK AREA ISOLATION

- 1. ALL WORK IN ISOLATED WORK AREAS MUST BE COMPLETED IN THE DRY. AN ADEQUATE NUMBER OF PUMPS MUST
- BE USED FOR UNWATERING.
 2. CROSSING AN ACTIVE WATERCOURSE OR WETLAND BY EQUIPMENT, VEHICLES, PERSONNEL, ETC. IS NOT PERMITTED UNLESS APPROVED BY THE CONSERVATION AUTHORITY. ALL ACCESS TO WORK SITES SHALL BE FROM
- EITHER SIDES OF THE WATERCOURSE OR WETLAND.

 3. THE UNWATERING DISCHARGE LOCATION MUST BE LOCATED AT LEAST 30 M FROM ANY WATERCOURSE OR WETLAND IN AN AREA WITH DENSE VEGETATIVE GROUNDCOVER, AND WHERE THE DISCHARGE CAN RETURN TO
- THE WATERBODY DOWNSTREAM OF THE WORK AREA OVER THE GROUNDCOVER 4. FISH MUST BE REMOVED FROM THE WORK AREA ONCE ISOLATED. FISH SALVAGE MUST BE COMPLETED BY A QUALIFIED TECHNICIAN WITH A LICENSE FROM THE ONTARIO MINISTRY OF NATURAL RESOURCES AND FORESTR'S

24/03/15 LD FIRST CONCEPTUAL DESIGN SUBMISSION DATE BY **REVISIONS**

DATE: APRIL 2024 DRAWN BY: AS / SG

24/03/15

NOT FOR CONSTRUCTION **SCALED FOR PLOT** ON 'ARCH D'

DESIGNED BY: LD



CHECKED BY: PV

T: 416.920.0926 www.geomorphix.com

BLOCK 1 BSS FRUITLAND-WINONA BLOCK 1 OWNERS GROUP, HAMILTON

WATERCOURSE 5 CONCEPTUAL CHANNEL DESIGN **DETAILS**

DRAWING No.: DET-2 PROJECT No.: 21043 SHEET 5 OF 5 SCALE: AS NOTED



April 18, 2024

Fruitland Landowners Group Inc. c/o Urbantech Consulting Engineers 2030 Bristol Circle, Suite 105 Oakville, Ontario L6H 0H2

Attn: Steve Hader, P.Eng.
Senior Project Manager

Re: Fluvial Geomorphological Assessment

Stoney Creek Watercourse 6.0

Fruitland-Winona Secondary Plan Area

GEO Morphix Project No. 21043a

GEO Morphix Ltd. was retained to examine the potential meander belt width associated with Watercourse 6.0 upstream of Barton Street in the City of Hamilton, Ontario as this allowance may define the development constraint limit for some areas adjacent to this watercourse. Watercourse 6.0 (**Reach WC6-A**) flows south to north between Barton Street and Regional Road 8, immediately east of Jones Road. Meander belt widths for Watercourse 6.0 were previously defined by others as part of the Stoney Creek Urban Boundary Expansion West Subwatershed Study (2013) and the Block 2 Servicing Strategy for the Fruitland-Winona Secondary Plan Lands (2018). These were defined for the tributary (Watercourse 6.0), but not for individual reaches. As such, the meander belt width was refined for the section of creek upstream of Barton Street.

We had previously defined a meander belt width in this area for an alternative project. This memo is consistent with that previous approach. To refine the meander belt width for this section of Watercourse 6.0 (**Reach WC6-A**), we have reviewed various background data and reporting, completed site reconnaissance to document existing watercourse characteristics, and updated the meander belt width assessment at a reach scale based on existing information and newly collected field observations.

Background Review

To inform our meander belt width assessment, we examined the following reports:

- Stoney Creek Urban Boundary Expansion (SCUBE) West Subwatershed Study Phase 1 and Phase 2 Final Report (Aquafor Beech Limited, May 15, 2013)
- Block 2 Servicing Strategy for the Fruitland Winona Secondary Plan Lands (Aquafor Beech Limited, April 3, 2018)
- Natural Heritage Characterization Assessment, 238 Jones Road and 820-832 Barton Street,
 City of Hamilton (Coville Consulting Inc., December 2018)
- City of Hamilton Watercourse 5 & 6 Class Environmental Assessment Study Draft Report (Dillon Consulting Limited, November 2007)
- City of Hamilton Watercourse 5.0 & 6.0 Hydraulic Assessment (Dillon Consulting Limited, September 2010)
- City of Hamilton Watercourse 5.0 & 6.0 Hydraulic Assessment (Dillon Consulting Limited, January 2011)

Aquafor Beech provided meander belt widths in the SCUBE West Subwatershed Study (Aquafor Beech, 2013). All calculations were based on the Toronto Region Conservation Authority (TRCA, 2004) model for defining the meander belt width. Using TRCA's (2004) model, they calculated a future meander belt width of 44 m for Watercourse 6.0. Given that they assumed hydrological changes, it is likely that they applied future flow conditions (i.e., discharge) and a factor of safety.

It should be noted that the TRCA (2004) model is based on gradient, drainage area, and discharge. For smaller watersheds, the model is very sensitive to channel slope, as it directly influences stream power. As such, the model relation between slope and meander belt width is inverse to what is observed in nature for smaller channels. Given this known issue, the TRCA (2004) model should be used with care, especially when it is applied in smaller watersheds and on low-order features.

Aquafor Beech recalculated the meander belt width in their April 2018 study: *Block 2 Servicing Strategy for the Fruitland-Winona Secondary Plan Lands*. The updated meander belt width was again calculated using the TRCA (2004) method. The meander belt width was calculated as 57.8 m. This may not be appropriate for Watercourse 6.0 (**Reach WC6-A**) upstream of Barton Street as only a portion of drainage area feeds this reach; it would therefore likely have a lower discharge and total drainage area than what was applied in the model.

In the 2004 and 2018 studies completed by Aquafor Beech, meander belt widths were not defined on a reach scale, which is the preferred approach/practice. Typically, meander belt widths are defined on the reach scale and not for an entire watercourse or tributary. Completing the analysis on a reach scale allows an appropriate discharge and drainage area to be applied. Applying it to the entire watercourse can result in a substantial overprediction of the meander belt width for upstream reaches. In Dillon's 2007 report *City of Hamilton Watercourse 5 & 6 Class Environmental Assessment Study Draft Report* Watercourse 6.0 was divided into five (5) separate reaches. **Reach WC6-A** is the section of Watercourse 6.0 upstream of Barton Street. Given that the watercourse was split into reaches, it is appropriate to provide meander belt widths for each of the assigned reaches. Furthermore, it was also assumed that the overall watercourse would experience changes in hydrology; however, the proposed Pond 3 will discharge at Barton Street, and therefore the hydrology through the reach upstream of Barton Street may not see an increase in peak flow or total discharge.

Given these facts, it is likely that the meander belt widths calculated by Aquafor Beech (2013, 2018) are an over-prediction for the reach in question. Also, in several locations, the meander belt width appears to be greater than the floodplain width, which is usually an indication that the predicted meander belt width is larger than the creek's realistic migration potential. This is reflected on Figure 5.3 on page 32 of the *Block 2 Servicing Strategy for the Fruitland-Winona Secondary Plan Lands* (Aquafor Beech, 2018). Given these discrepancies, we have reviewed and recalculated the meander belt width for this reach within the clients' properties. We have used a combination of desktop data and observations gathered through recent site reconnaissance.

Reach Delineation

Reaches are homogeneous segments of channel used in geomorphological investigations. Reaches are studied semi-independently as each is expected to function in a manner that is at least slightly different from adjoining reaches. This method allows for a meaningful characterization of a watercourse as the aggregate of reaches, or an understanding of a particular reach, for example, as it relates to a proposed activity.

Reaches are typically delineated based on changes in the following:

- Channel planform
- Channel gradient
- Physiography
- Land cover (land use or vegetation)
- Flow, due to tributary inputs
- Soil type and surficial geology
- Historical channel modifications

Reach delineation follows scientifically defensible methodology proposed by Montgomery and Buffington (1997), Richards et al. (1997), and the Toronto and Region Conservation Authority (2004) as well as others.

As noted previously, Watercourse 6.0 was divided into five (5) separate reaches as part of Dillon's 2007 report titled *City of Hamilton Watercourse 5 & 6 Class Environmental Assessment Study Draft Report*. The section of Watercourse 6.0 upstream (south) of Barton Street was classified as **Reach WC6-A**. Based on our review of available data (e.g., OBM topographic mapping, recent aerial imagery, surficial geology data), we are confidant that the section of Watercourse 6.0 situated between Barton Street and Regional Road 8 can be classified as one reach. The desktop reach delineation was also confirmed as part of our field reconnaissance. A reach map has been included in **Appendix A** for reference.

Field Reconnaissance

A field investigation was completed for **Reach WC6-A** on January 31st, 2024, and included the following observations:

- Habitat sketch maps based on Newson and Newson (2000) outlining channel substrate, flow patterns, geomorphological units (e.g., riffle, run, pool), and riparian vegetation for the extent of each reach assessed
- Descriptions of riparian conditions
- Estimates of bankfull channel dimensions
- Bed and bank material composition and structure
- Observations of erosion, scour, or deposition
- Collection of photographs to document the watercourse, riparian areas and/or valley, surrounding land use, and channel disturbances such as crossing structures

These observations and measurements are summarized below. The descriptions are supplemented and supported with representative photographs, which are included in **Appendix B**. Reach characteristics field sheets are provided in **Appendix C**. General reach characteristics are summarized in **Table 1**.

Reach WC-6A was characterized as unconfined, having a single channel with secondary flow paths, and a shallow gradient. Surrounding land use consisted of agricultural and low-density residential. Riparian vegetation was dominated by a continuous buffer of grasses and shrubs, with some wooded areas interspersed. Several woody debris jams were present at the mid-portion of the reach, with the formation of large pools. The reach lacked a regular riffle pool sequence, aside from a wooded midsection with mature willows. Substrate within the observed riffles consisted largely of clay and silt, rootlets, and some cobble, whereas the runs/pools throughout the reach consisted predominately of clay. The average bankfull width and depth were 2.58 m and 0.56 m, respectively. Bank angles ranged between 30° to 60° and the bank materials consisted of clay, and silt. Evidence of erosion was observed along 30% to 60% of the channel and was primarily observed at the downstream portion along outer the

bends. Rooted emergent vegetation was observed along approximately 45% of the reach. Aquatic vegetation consisted mainly of grasses and cattails. Banks were densely vegetated, and bank materials consisted of clay, and silt.

Table 1: General reach observations

	Average Bankfull	Average Bankfull	Substrate		Riparian	
Reach	Width (m)	Depth (m)	Pools	Riffles	Vegetation	Notes
WC6-A	2.58	0.56	Clay and silt	Clay, cobble, and rootlets	Fragmented coverage of trees and shrubs	Partially confined/ woody debris jams/ encroachment of cattails and grasses downstream

Rapid Assessments

Channel stability and susceptibility to erosion were objectively assessed through the application of the Ontario Ministry of the Environment (MOE) (2003) Rapid Geomorphic Assessment (RGA) technique. The RGA evaluates degradation, aggradation, widening, and planimetric form adjustment at the reach scale. The end result of the RGA is to produce a score, or stability index, which evaluates the degree to which a stream has departed from its equilibrium condition. A stream with a score of less than 0.20 is in regime, indicating minimal changes to its shape or processes over time. A score of 0.21 to 0.40 indicates that a stream is in transition or stress and is experiencing major changes to process and form outside the natural range of variability. A score of greater than 0.41 indicates that a stream is in extreme adjustment, exhibiting a new stream type, or in the process of adjusting to a new equilibrium (MOE, 2003 and VANR, 2007).

The Rapid Stream Assessment Technique (RSAT) was also employed to provide a broader view of the system and consider the ecological functioning of the watercourse (Galli, 1996). Observations were made of channel stability, channel scouring or sediment deposition, instream and riparian habitats, and water quality. The RSAT score ranks the channel as maintaining a poor (<13), fair (13-24), good (25-34), or excellent (35-42) degree of stream health.

The reaches were also classified according to the Downs (1995) Model of Channel Evolution. The Downs (1995) model describes successional stages of a channel as a result of perturbation, namely hydromodification. Understanding the current stage of the system is beneficial as this allows one to predict how the channel will continue to evolve or respond to an alteration to the system. Rapid assessment results are summarized in **Table 2**, below.

For **Reach WC6-A** the RGA score was 0.40, indicating that the stream was in transition. The dominant geomorphic processes shaping the channel were determined to be widening and planimetric form adjustment. Evidence of widening included large organic debris, and basal scour throughout the channel and riffles. Evidence of planimetric adjustment was noted as the evolution of a riffle-pool form to a low bed relief from, single thread to multiple channels, formation of chutes, and poor bar forms. The RSAT score for this reach was 23, indicating that the stream was in fair condition. The limiting features were physical instream habitat due to a lack of riffle pool sequencing and riparian habitat conditions due to limited canopy cover. Using the Downs (1995) model, the dominant channel evolution mechanism was determined to be lateral migration.

Table 2: Rapid assessment results

	RGA			RSAT				
Reach	Score	Condition	Dominant Systematic Adjustment	Score	Condition	Limiting Feature(s)	Downs (1995)	
WC6-A	0.40	In Transition	Evidence of widening and planimetric form adjustment	23	Fair	Physical Instream Habitat, Riparian Habitat Conditions	Lateral Migration	

Meander Belt Width Assessment

There are several methods for determining the meander belt width of individual reaches. The first approach includes collecting field measurements of reaches and meander amplitudes from aerial photographs or field observations. The second approach would be defining the meander belt width based on relations between meander belt width and channel geometry using field measurements of the channel. Finally, the third approach is to apply empirical models, such as TRCA's (2004) model for delineating the meander belt width at a reach scale.

As a component of the *City of Hamilton Watercourse 5.0 & 6.0 Hydraulic Assessment* completed by Dillon Consulting (2011) a preliminary flow analysis for Watercourse 6.0 was completed. All 2-year flows for Watercourse 6.0 identified in this analysis are provided in **Table 2** below. Based on the 2-year flows for Watercourse 6.0, discharge decreases upstream of Barton Street.

Table 2. 2-year flows for Watercourse 6.0 (Dillon, 2010 and 2011)

Location	2-year flow
Watercourse 6.0 at Barton Street*	1.12
Watercourse 6.0 at CNR	1.58
Watercourse 6.0 at South Service Road	1.72
Watercourse 6.0 at QEW/Diversion	1.72

^{*}Location immediately upstream of Barton Street

Using the TRCA (2004) model, GEO Morphix calculated a meander belt width for Watercourse 6.0 (**Reach WC6-A**) on a reach scale. The TRCA model relation is outlined below in Equation 1.

$$Bw = -14.827 + 8.319ln (\rho gQS * DA)$$

[Equation 1]

Where p is water density (1000 kg/m³), g is acceleration due to gravity (9.8 m/s²), Q is discharge (m³/s), S is channel slope (m/m), and DA is drainage area (km²).

To satisfy the model, a drainage area of $1.81~\rm km^2$ was identified using the Ontario Flow Assessment Tool (OFAT). This drainage area extent is likely conservative as it includes a section of channel upstream of the escarpment. The 2-year flow from Dillon's assessment (2011) was applied for **Reach WC6-A** at Barton Street ($1.12~\rm m/s^3$). The meander belt width was calculated as $37.8~\rm m$. This includes one standard deviation, as changes to hydrology upstream of Barton Street are not expected. Without one

standard deviation, the meander belt width for **Reach WC6-A** at Barton Street was 29.2 m. These values are all lower than those previously outlined by Aquafor Beech (2013, 2018).

A modified Williams (1986) model can also be used to determine the meander belt width based on field measurements of channel geometries. This approach has been accepted in numerous Conservation Authority jurisdictions, including Hamilton Region Conservation Authority. This modified model also accounts for the average bankfull width of the channel and an additional 20% factor of safety. This modified relation is outlined below in Equation 2.

$$BW = ([4.3 \times W_b^{1.12}] + W_b) \times 1.2$$

[Equation 2]

Bankfull channel geometry was surveyed as part of our detailed geomorphological assessment for a sub-section of **Reach WC6-A**. Using the Williams (1986) model, with a 20% factor of safety applied, the meander belt width for the average 2.58 m bankfull width was calculated as 18.0 m.

A desktop analysis of aerial photographs was also completed to determine the meander belt width based on existing or historical meander amplitudes. A 13-year record of aerial photographs was available on Google Earth Pro and included photos from 2005, 2009, 2015, 2016, 2017, and 2018. The majority of the channel had a straight planform, however meander amplitudes that were observable were approximately 8.5-9.5 m wide. The largest meanders were measured at 15-16 m. Using the maximum meander amplitude (16 m), the average bankfull width (2.58 m) and a 20% factor of safety, the meander belt width is calculated as 22.3 m. **Table 3** below outlines the range of meander belt widths that have been calculated for Watercourse 6.0 or **Reach WC6-A**.

Table 3. Meander belt widths for Watercourse 6.0

Meander Belt Width Calculation Method	Meander Belt Width (m)
TRCA Model*	
Aquafor Beech (2013)	44.0
Watercourse 6.0	
TRCA Model*	
Aquafor Beech (2018)	57.8
Watercourse 6.0	
TRCA Model*	
One Standard Error Added (Assuming no change to hydrology upstream of Barton St)	37.8
GEO Morphix (2024) using Dillon (2011) modelled discharge (1.12 m ³ /s)	37.0
Reach WC6-A	
TRCA Model*	
No Standard Error Added	29.2
GEO Morphix (2024) using Dillon (2011) modelled discharge (1.12 m ³ /s)	25.2
Reach WC6-A	
Williams Model**	
Assuming 2.58 m wide channel and 20% Factor of Safety	18.0
GEO Morphix (2024)	10.0
Reach WC6-A	
Largest Meander Amplitude	
Largest measured meander amplitude + bankfull channel width + 20% Factor of Safety	22.3
GEO Morphix (2024)	22.5
Reach WC6-A	

^{*} TRCA (2004) Belt Width Delineation Procedures

^{**} Williams (1986) River Meanders and Channel Size

Summary

Based on our review of available reports and data as well as additional field reconnaissance, GEO Morphix calculated a range of meander belt widths for Watercourse 6.0 (specifically Reach WC6-A) using a variety of different methods. Meander belt widths ranged from 22.3 m to 37.8 m. These values were all substantially lower than the previous meander belt widths calculated by Aquafor Beech (2013, 2018). It is likely that the meander belt width falls within the range that we have summarized from our calculations. As such, we suggest a meander belt width of 30 m for Reach WC6-A is appropriate and could be applied.

The meander belt width determined here is based on observations from a sub-section of Reach WC6-A within the 238 Jones Road property. Given our confirmation of watercourse conditions upstream and downstream of the property at Regional Road 8 and Barton Street, we are confident that the meander belt width can be applied to the entire length of the reach.

It should be noted that the previous meander belt width determined by Aquafor Beech can be applied to other reaches of Watercourse 6.0 upstream (south) of Regional Road 8 and downstream (north) of Barton Street. Refinement of the meander belt width in these locations would require additional desktop and field reconnaissance.

We trust this letter meets your current requirements. Should you have any questions, please contact the undersigned.

Respectfully submitted,

Paul Villard, Ph.D., P.Geo., CAN-CISEC, EP, CERP Director, Principal Geomorphologist

Lindsay Davis, M.Sc., P.Geo., CAN-CISEC Geomorphologist, Project Manager

Lindsay Dew

References

Aquafor Beech Ltd. 2018. Block 2 Servicing Strategy for the Fruitland-Winona Secondary Plan Lands. Final Report.

Aquafor Beech Ltd. 2013. Stoney Creek Urban Boundary Expansion (SCUBE) West Subwatershed Study Phase 1 and Phase 2 Final Report.

Colville Consulting Inc. 2018. Natural Heritage Characterization Assessment. 238 Jones Road and 820-832 Barton Street – City of Hamilton.

Dillon Consulting Limited. 2011. Watercourse 5.0 & 6.0 Hydraulic Assessment. City of Hamilton.

Dillon Consulting Limited. 2010. Watercourse 5.0 & 6.0 Hydraulic Assessment. City of Hamilton.


Dillon Consulting Limited. 2007. Watercourse 5 & 6 Class Environmental Assessment Study – Draft Report. City of Hamilton.

Harnes, H.H. 1967. Roughness Characteristics of Natural Channels. Prepared for: U.S. Geological Survey. United States Government Printing Office. Washington, D.C. Retrieved via: https://pubs.usgs.gov/wsp/wsp_1849/pdf/wsp_1849-test-2.pdf

Toronto and Region Conservation Authority (TRCA). 2004. Belt Width Delineation Procedures.

Williams. 1986. River Meanders and Channel Size.

Appendix A Study Area Mapping



Legend





Meander Belt Width


Approximate Extent of MBW



Meander Belt Width

Fruitland-Winona Block 1 Servicing Strategy

Hamilton, Ontario



Imagery: Google Earth Pro: 2018 Subject Property: Parish Aquatic Services, 2019. Watercourse and 1 m Contour: City of Hamilton, 2020. Meander Belt Width: GEO Morphix Ltd., 2024. Printed: April 2024. PN21043. Drawn by: L.D., M.O., G.U.

Appendix B Photographic Record



Upstream extent of **Reach WC-6** facing downstream. The channel was well defined within a grassy corridor and dominated by runs.



Multiple poorly defined secondary flow paths were also present within the corridor.

i



The middle of the reach consisted of a single channel within a narrow forested riparian zone.





Several woody debris jams were present throughout the mid-section of the reach. Woody debris was common along the banks as well.



Basal scouring was observed throughout the reach, in particular at the downstream section. Bed and bank materials consisted primarily of clay.



A swale present in the adjacent agricultural field contributed to stream flow.

Photo 7
Reach WC-6 - Watercourse 6, Hamilton, Ontario



Multiple flow paths were present within a swale feature at the downstream section of the reach.





Downstream extent of **Reach WC-6** facing downstream.

Appendix C Field Sheets

21043a

11



General Site Characteristics

Project Number: 21043a

Date:	2024-01-31	Stream:	
Time:	9:30	Reach:	WC-60
Weather:	4°C	Location:	Fruitland-Winona
Field Staff:	SC HF	Watershed/Subwatershed:	W Lake ON Shoreling

Field	Staff:	SC HF	Watershed/Subwatershed: W Lake ON Shoreline
Featu	ıres	Monitoring	Site Sketch Compass
<u> </u>	Reach break	-oo- Long-profile	
只	Station location	Monumented XS	(1)
X	Cross-section	Monumented photo	
-	Flow direction	Monumented photo	
~~	Riffle	▼ direction	
	Pool	Sediment sampling	
CONTRACT OF THE PARTY OF THE PA	Sediment bar	Erosion pins	dens grassy
HHHHHH	Eroded bank/slope	Scour chains	E wide oded?
	Undercut bank	Additional Symbols	
XXXXXX	Bank stabilization		6
	Leaning tree		
XX	Fence		2 83
	Culvert/outfall		of multiple
	Swamp/wetland		3 mpg,
AAA	Grasses		3 53
	Tree		E3 CO CONTRACTOR OF THE PROPERTY OF THE PROPER
	Instream log/tree		
* * *	Woody debris		3 Suple
**************************************	Beaver dam		S S S S S S S S S S S S S S S S S S S
W	Vegetated island		E Chais Coots
Flow '			5 3 60 C
H1	Standing water H1		
H2	Scarcely perceptible	flow	or from parties the soft woody debris
HA	Smooth surface flow		itiple ins 71
H5	Upwelling Rippled		Wo bour
H6	Unbroken standing w	2010	2 x100. I the lots of woody debris
H7	Broken standing wav		3 of trom cut trees
H8	Chute	е	to Confluence
H9	Free fall H9#	Dissipates below free fall	3.7 VI loses definition
Substi		bissipates below free fall	10ses detinition
S1	Silt	S6 Small boulder	1
S2	Sand	S7 Large boulder	a v // v // agriculture
S3	Gravel	S8 Bimodal	5.4m agriculture
S4	Small cobble	S9 Bedrock/till	1 Field
S5	Large cobble	,	
Other			0 <
ВМ	Benchmark	EP Erosion pin	V V grassy
BS	Backsight	RB Rebar	(channel
DS	Downstream	US Upstream	corridor
WDJ	Woody debris jam	TR Terrace	10 With W
VWC	Valley wall contact	FC Flood chute	
BOS	Bottom of slope	FP Flood plain	TOICE THE
TOS	Top of slope	KP Knick point	Photos: taken US to DS Notes:
0	0 - 1	t and the same	Notes.

Page $_$ of 2



General Site Characteristics Project Number: 21043a

Date:	2024-01-31	Stream:	
Time:	9:30	Reach:	WC-6
Weather:	4·C	Location:	Fruitland-Winong
Field Staff:	SC HF	Watershed/Subwatershed:	W Lake ON Shoreling

Field	Staff:	SC HF		Watershed/Subwate	ershed:	W Lake O	N Short
Featu	res	Monitoring	Site	Sketch (an a		Compass
∀ ×—× →	Flow direction Riffle	Monumented photo Monumented photo Monumented photo direction	tree	line VI		DS	7
########	,	Sediment sampling Erosion pins Scour chains			enc	roched cattails reeds	
**************************************	Undercut bank Bank stabilization Leaning tree Fence Culvert/outfall Swamp/wetland	Additional Symbols	hic	her A	P	rude: 6.23m	
***	Grasses Tree Instream log/tree Woody debris Beaver dam		Pied		multipath a:	ple from swale feature	e Field
Flow 1	Vegetated island		1	V	1		3
H1 H2 H3 H4 H5 H6 H7 H8	Standing water H1. Scarcely perceptible Smooth surface flow Upwelling Rippled Unbroken standing wav Chute	flow vave ve	agriculture		11	orlows	agriculture
H9 Substr	Free fall H9/	A Dissipates below free fall		Fooding =>			
S1 S2 S3 S4 S5	Silt Sand Gravel Small cobble Large cobble	\$6 Small boulder \$7 Large boulder \$8 Bimodal \$9 Bedrock/till		E3 (C3	1 1/2 04	ton high	
Other BM	Benchmark	EP Erosion pin			1	700	
BS DS WDJ VWC	Backsight Downstream Woody debris jam Valley wall contact	RB Rebar US Upstream TR Terrace FC Flood chute			1		
BOS	Bottom of slope	FP Flood plain	Photo				
TOS	Top of slope	KP Knick point	Notes	:			

4) feature w: 10.5m d:1.15m

main channel ww: 1.16m wd: 0.33m

Version #4 Last edited: 21/02/2023

Senior staff sign-off (if required): _____ Checked by: ____ Completed by: ____

Page 2 of 2

Reach Characteristics	stics Project Number:	V0400				MORPHIX
Date:	12-10-4207	Field Staff:	SC FF	Watershed/Subwatershed:	N Lake on	Shoreline
Time:	9:30	Stream:		UTM (Upstream):		2
Weather:	4.C overcast	Reach:	MC-6	UTM (Downstream):	4.7	
Land Use S (Table 1)	Valley Type Channel Type (Table 2)	71	Channel Zone Zone Zone Zone (Table 4)	Evidence of G	Evidence of Groundwater Location:	Photo:
Riparian Vegetation			Aquatic & Instream Vegetation		Water Quality	
Dominant Type (Table 6)	Coverage Channel Widths	Age (yrs)	Type Woody Debris	WD Density WD3/50m:	Odour (Table 16)	Turbidity (Table 17)
Encroachment	<u> </u>	Established (5-30)		Mod		2
(Table 7)	Continuous □ > 10	□ Mature (>30)	Coverage % \Box \Box Not Present	☐ High		
Channel Characteristics	tics					
Sinuosity Type (Table 9)	Sinuosity Degree (Table 10)	Bank Angle	Bank Erosion(Table 19)□ < 5%Bank	Clay/Silt Sand Gr	Gravel Cobble Boulder Parent	nt Rootlets
Gradient	# of Channels	№ 30 – 60	□ 5 – 30% Riffle			
(Table 11)	(Table 12)	06 - 09 🗆	₩30 - 60%			
Entrenchment (Table 13)	Bank Failure (C	□ Undercut	Bed (if no riffle-pool morphology)			
Down's Model M/e (Table 15)	Bankfull Indicators 1, 3, 4 (Table 18)	0	Bankfull Width 2.2 2.8	2:73 Wetted N	Wetted Width (m) [.65] 2.2	2.5
Sed Sorting well (Table 20)	Sediment Transport Observed?	☐ Yes 窗 No ☐ Not Visible	Bankfull Depth (m) (0,55	0.53	Wetted Depth (m) 0.35 0.22	0.3
Mode (Table 21)	% of Bed Active $\left< \right>$		Undercuts (m)	Veloc	Velocity (m/s) 0,092 0,4\	0,26
Geomorphic 8/10	Mass Movement (Table 23)	1, von 76	Pool Depth 0.23 0.47	6.38 Velocit	Velocity Estimate WB Method	3
Spacing (m):	% Riffles:	% Pools:	Riffle Length (m) 1.78	Meander	Meander Amplitude 5.4 6.23	
Notes:	A Total Control of the Control of th					
Flow paths	at the upstream	TOUGHOUT	stream spetions. Hos	Several poorly	defined secondary	CAN
Orossy with	encreaching		eds. The middle of	reach	S a narrow	1 2
Some	eas. The c	S1. 45	pinated by runs	man - C	ococolics of with	60000
	of high flow.	000000	Mas observed th	roughant the	reach. Evidence	
Photos:	3					
		*				

Senior staff sign-off (if required): _

Version #4 Last edited: 04/04/2023

Checked by: _____ Completed by

Completed by: SC/HF



Rapid Geomorphic Assessment Project Number: 2\0\43a

	400	210101							
Time:	9:30 Reach: WC-6								
Weather:		4.C overcas	Location:	Park Commence	Fruitla	nd-la	linar	vC)	
Field Staff:	SC HF Watershed/Subwatershed: W Lake ON Shore								
	Geomorphological Indicator						esent?		
Process	No.	Description		icator		Yes	No	Factor Value	
	1	Lobate bar				1.00	X		
	2	Coarse materials in riffle	es embedded			V	1		
Evidence of	3	Siltation in pools					×	71	
Aggradation	4	Medial bars					V	/7	
(AI)	5	Accretion on point bars					1		
	6	Poor longitudinal sorting	of bed materials			X			
	7	Deposition in the overba			The state of the s				
			/	9	Sum of indices =	. 2	5	0.29	
	1	Exposed bridge footing(s)				17.		
	2			etc.		N	/A	-	
	3	Exposed sanitary / storm sewer / pipeline / etc. Elevated storm sewer outfall(s)				4			
	4						NA		
Evidence of	5	Scour pools downstream of culverts / storm sewer outlets					NA		
Degradation (DI)	6	Cut face on bar forms	1	X					
` ,	7	Head cutting due to knic		1					
	8	Terrace cut through olde					X		
	9	Suspended armour layer	visible in bank						
	10	Channel worn into undis	turbed overburden /	bedrock			X		
				S	Sum of indices =			0	
	1	Fallen / leaning trees / f	ence posts / etc.			X			
	2	Occurrence of large orga	nic debris			X.			
	3	Exposed tree roots				X			
Fuldamen (4	Basal scour on inside meander bends						-	
Evidence of Widening	5	Basal scour on both sides of channel through riffle						6	
(WI)	6	Outflanked gabion baskets / concrete walls / etc.					A	18	
	7	Length of basal scour >50% through subject reach					-		
	8	Exposed length of previously buried pipe / cable / etc.					X		
	9	Fracture lines along top of bank					X		
	10	Exposed building founda	tion			NI	A		
				S	um of indices =	6	2	0.75	
	1	Formation of chute(s)				Х			
Evidence of	2	Single thread channel to				X			
Planimetric	3	Evolution of pool-riffle form to low bed relief form -> pool-riffle in				X		11	
Form Adjustment		Cut-off channel(s) middle of			- V	X	1/7		
(PI)		Formation of island(s)				X	/7		
		Thalweg alignment out o					X		
	7	Bar forms poorly formed	/ reworked / remove	ed		X		V.	
				S	um of indices =	4	3	0.57	
Notes:				Stability Ind	lex (SI) = (AI-	DI+WI	+PI)/4 =	0.40	
				In Regime				djustment	
				□ 0.00 - 0.		1 - 0.40		0.41	

Version #3 Last edited: 10/02/2023 Senior staff sign-off (if required): _____ Checked by: ____ Completed by: ____



Rapid Stream Assessment Technique Project Number: 21043a

Date:	2024-01-31	Stream:				
Time:	9:30	Reach:	13454	WC-6		
Weather: 4°C overcast		Location:			-Winona	
Field Staff: SC HF		Watershed/Subwate	rshed:		N Shoreline	
Category	Poor	Fair	XII SIOOG	Good	Excellent	
	 < 50% of bank network stable Recent bank sloughing, slumping or failure frequently observed 	50-70% of bank network stable Recent signs of bank sloughing, slumping or failure fairly common	stable Infrequ	of bank network ent signs of bank ng, slumping or	 > 80% of bank network stable No evidence of bank sloughing, slumping or failure 	
Channel	 Stream bend areas highly unstable Outer bank height 1.2 m above stream bank (2.1 m above stream bank for large mainstem areas) Bank overhang > 0.8-1.0 m 	Stream bend areas unstable Outer bank height 0.9-1.2 m above stream bank (1.5-2.1 m above stream bank for large mainstem areas) Bank overhang 0.8-0.9m	Outer by mabov 1.5 m a for larg	bend areas stable ank height 0.6-0.9 e stream bank (1.2- bove stream bank e mainstem areas) rerhang 0.6-0.8 m	Stream bend areas very stable	
Stability	 Young exposed tree roots abundant > 6 recent large tree falls per stream mile 	Young exposed tree roots common 4-5 recent large tree falls per stream mile	Exposed tree roots predominantly old and large, smaller young roots scarce 2-3 recent large tree falls per stream mile		Exposed tree roots old, large and woody Generally 0-1 recent large tree falls per stream mile	
	Bottom 1/3 of bank is highly erodible material Plant/soil matrix severely compromised	Bottom 1/3 of bank is generally highly erodible material Plant/soil matrix compromised	Bottom 1/3 of bank is generally highly resistant plant/soil matrix or material		Bottom 1/3 of bank is generally highly resistant plant/soil matrix or materia	
£1,1-₹ 0 on	Channel cross-section is generally trapezoidally- shaped	Channel cross-section is generally trapezoidally- shaped	Channel cross-section is generally V- or U-shaped		Channel cross-section is generally V- or U-shaped	
Point range	□ 0 □ 1 □ 2	□ 3 □ 4 □ 5	₫ 6	0708	□ 9 □ 10 □ 11	
	> 75% embedded (> 85% embedded for large mainstem areas)	• 50-75% embedded (60- 85% embedded for large mainstem areas)	59% en	embedded (35- nbedded for large m areas)	Riffle embeddedness < 25% sand-silt (< 35% embedded for large mainstem areas)	
	Pool substrate composition >81% sandsilt composition >81% sandsilt	Low to moderate number of deep pools Pool substrate composition 60-80% sand-silt	Moderate number of deep pools Pool substrate composition 30-59% sand-silt Streambed streak marks and/or "banana"-shaped sediment deposits uncommon Fresh, large sand deposits uncommon in channel Small localized areas of fresh sand deposits along top of low banks Point bars small and stable, well-vegetated and/or armoured with little or no fresh sand		High number of deep pools (> 61 cm deep) (> 122 cm deep for large mainstem areas) Pool substrate composition <30% sand-silt	
Channel Scouring/ Sediment Deposition	Streambed streak marks and/or "banana"-shaped sediment deposits common	Streambed streak marks and/or "banana"-shaped sediment deposits common			Streambed streak marks and/or "banana"-shaped sediment deposits absent	
	 Fresh, large sand deposits very common in channel Moderate to heavy sand deposition along major portion of overbank area 	 Fresh, large sand deposits common in channel Small localized areas of fresh sand deposits along top of low banks 			Fresh, large sand deposits rare or absent from channel No evidence of fresh sediment deposition on overbank	
D 7	Point bars present at most stream bends, moderate to large and unstable with high amount of fresh sand	Point bars common, moderate to large and unstable with high amount of fresh sand			Point bars few, small and stable, well-vegetated and/or armoured with little or no fresh sand	
Point range	□ 0 □ 1 □ 2	□ 3 □ 4		5 🗵 6	□ 7 □ 8	

Last edited: 10/02/2023

Senior staff sign-off (if required): _____ Checked by: ____ Completed by: ____



Date:	2024-01-31	PN: 21043a	Location: F	ruitland-Winon	
Categor	Poor	Fair	Good	Excellent	
	Wetted perimeter < 40% of bottom channel width (< 45% for large mainstem areas)	Wetted perimeter 40- 60% of bottom channel width (45-65% for large mainstem areas)	Wetted perimeter 61-85% of bottom channel width (66-90% for large mainstem areas)	 Wetted perimeter > 85% of bottom channel width (> 90% for large mainstem areas) 	
	Dominated by one habitat type (usually runs) and by one velocity and depth condition (slow and shallow) (for large mainstem areas, few riffles present, runs and pools dominant, velocity and depth diversity low)	Few pools present, riffles and runs dominant. Velocity and depth generally slow and shallow (for large mainstem areas, runs and pools dominant, velocity and depth diversity intermediate)	Good mix between riffles, runs and pools Relatively diverse velocity and depth of flow	 Riffles, runs and pool habitat present Diverse velocity and depth of flow present (i.e., slow, fast, shallow and deep water) 	
Physica Instrear		Riffle substrate composition: predominantly small cobble, gravel and sand 5-24% cobble	 Riffle substrate composition: good mix of gravel, cobble, and rubble material 25-49% cobble 	 Riffle substrate composition: cobble, gravel, rubble, boulder mix with little sand > 50% cobble 	
Habitat	• Riffle depth < 10 cm for large mainstem areas	Riffle depth 10-15 cm for large mainstem areas	Riffle depth 15-20 cm for large mainstem areas Large pools generally 46-61	Riffle depth > 20 cm for large mainstem areas	
	Large pools generally < 30 cm deep (< 61 cm for large mainstem areas) and devoid of overhead cover/structure	30 cm deep (< 61 cm for large mainstem areas) and devoid of overhead areas) with little or no		cm deep (> 122 cm for large mainstem areas) with good overhead cover/structure	
	Extensive channel alteration and/or point bar formation/enlargement	Moderate amount of channel alteration and/or moderate increase in point bar formation/enlargement	Slight amount of channel alteration and/or slight increase in point bar formation/enlargement	No channel alteration or significant point bar formation/enlargement Riffle/Pool ratio 0.9-1.1:1	
	• Riffle/Pool ratio 0.49:1; ≥1.51:1	• Riffle/Pool ratio 0.5- 0.69:1 ; 1.31-1.5:1	• Riffle/Pool ratio 0.7-0.89:1 ; 1.11-1.3:1	• Riffle/Pool ratio 0.9-1.1:1	
N	• Summer afternoon water temperature > 27°C	Summer afternoon water temperature 24-27°C	Summer afternoon water temperature 20-24°C	Summer afternoon water temperature < 20°C	
Point ran	ge 0 1 2	□ 3 ፳ 4	□ 5 □ 6	□ 7 □ 8	
510	• Substrate fouling level: High (> 50%)	Substrate fouling level: Moderate (21-50%)	Substrate fouling level: Very light (11-20%)	Substrate fouling level: Rock underside (0-10%)	
	• Brown colour • TDS: > 150 mg/L	• Grey colour • TDS: 101-150 mg/L	• Slightly grey colour • TDS: 50-100 mg/L	• Clear flow • TDS: < 50 mg/L	
Water Qua	Objects visible to depth < 0.15m below surface	Objects visible to depth 0.15-0.5m below surface	Objects visible to depth 0.5-1.0m below surface	Objects visible to depth 1.0m below surface	
	 Moderate to strong organic odour 	Slight to moderate organic odour	Slight organic odour	• No odour	
Point ran	ge 0 1 2	□ 3 □ 4	□ 5 × 6	□ 7 □ 8	
Riparia		Ripakian area predominantly wooded but with major localized gaps	Forested buffer generally 31 m wide along major portion of both banks	Wide (> 60 m) mature forested buffer along both banks	
Habita Conditio	Canony coverage:	Canopy coverage: 50- 60% shading (30-44% for large mainstem areas)	Canopy coverage: 60-79% shading (45-59% for large mainstem areas)	Canopy coverage: >80% shading (> 60% for large mainstem areas)	
Point rar	nge 🗆 0 💆 1	□ 2 □ 3	□ 4 □ 5	□ 6 □ 7	
Total ove	rall score (0-42) = 23	Poor (<13) F	Fair (13-24) Good (25-	Excellent (>35)	

Version #2 Last edited: 10/02/2023 Senior staff sign-off (if required): _____ Checked by: ____ Completed by: ____



Fluvial Geomorphology Field Key

Table 1 Land Use

- 1. Forest
- 8. Golf Course

9. Commercial

- 2. Pasture
- 3. Agricultural
- 4. Industrial
- 5. Park
- 6. Institutional
- 7. Residential

Table 2 Valley Type

- 1. Unconfined
- 2. Confined
- 3. Partially Confined

Table 3 Channel Type

Table 4 Channel Zone

- 1. Headwater zone
- 2. Transfer zone
- 3. Deposition zone

Table 5 Flow Type

- 1. Perennial
- 2. Intermittent
- 3. Ephemeral

Table 6 Dominant Vegetation Type

- 1. Trees
- 2. Shrubs
- 3. Grasses
- 4. Herbaceous

Table 7 Encroachment Extent into Channel

- 1. None
- 5. Extreme
- 2. Minimal
- 3. Moderate
- 4. Heavy

Table 11 Gradient

Table 10 Degree of

1. Straight (1 – 1.05)

2. Low sinuosity (1.06-1.30)

3. Meandering (1.31 - 3.0)

Table 12 Number of

2. Up to 3 (Wandering)

4. >3 (Anastamosing or

5. Discontinuous or Absent

1. Low

Meandering

2. Moderate

Channels

3. > 3 (Braided)

Anabranching)

1. Single

Sinuosity

3. High


Table 8 Type of Aquatic Vegetation


- 1. Rooted Emergent
- 2. Rooted Submergent
- 3. Rooted Floating
- 4. Free Floating Roots
- 5. Floating Algae
- 6. Attached Algae


Sinuosity 1. Sinuous


Table 9 Type of

- 2. Irregular Meanders
- 3. Regular Meanders
- 4. Tortuous Meanders
- 5. Confined pattern (within valley)





























discontinuous or absent

Table 13 **Entrenchment**

- 1. Low (>2.2)
- 2. Moderate (1.4 2.2)
- 3. High (<1.4)







Failure

action)

failure)

S – Stable

Table 14 Type of Bank

1. Fluvial Entrainment (Hydraulic

2. Undercutting (Hydraulic action)

3. Slab Failure (Mass failure)

4. Parallel slide (Mass failure)

5. Fall/Sloughing (Mass failure)

6. Rotational slip and slump (Mass

Table 15 Downs's Model of

Channel Classification

M / m - Lateral Migration

D / d - Depositional

E or e - Enlarging

C - Compound

R - Recovering U - Undercutting



old tree roots exposed no tree falls





erosion along outer bank (e.g.

erosion along both banks (e.g.

no alluvial terrace




channel downcutting (e.g. bed scour, lov

steep, high banks above bankfull leve

generally straight

- stable except at sharp bends alluvial terrace/valley wal sharp bends with outside bank erosion, pointvalley wall contacts at few, if any meande har/cut bank development and undercutting
 - no alluvial terrace
- no alluvial terrace






- bank erosion (slumping, exposed tree roots) sediment denosition on hed (e.g. bar
- alluvial terrace with erosis



- ☐ straight alluvial terrace/valley wall
- valley wall contact and erosion at majority of
- erosion along outer bank (e.g. slumping, you deposition along inner bank (i.e. point ba
 - scoured bed, low emb

Slab failure









Table 16

- **Odours**
 - 1. None 2. Fishv
 - 3. Petroleum
 - 4. Sewage
 - 5. Chemical
 - 6. Other

Table 17 Turbidity

- 2. Slightly turbid
- 3. Turbid
- 5. Stained



Version #3 Last edited: 04/04/2023



6. Other



UNCONSOLIDATED MATERIALS

Fluvial Geomorphology Field Key


% Cover

Sorting

Table 18 Bankfull Indicators

- 1. Topography
- 2. Soil Horizons
- 3. Bank Slope
- 4. Sediment Texture
- 5. Vegetation
- 6. Mineral Stains
- 7. Undercuts
- 8. Flood deposits
- 9. Other

GEO



.002	.004-	.008	.010.	2	.053	54.0 53.9 33.1 33.1 117.0 16.0 113.4							0	256	mm	GRAIN					
CLAY		SILT				SAND			4 PEBBLES				00	B0		Went	SIZE				
	fine	Verv	fine	medium	coarse	very	fine	medium	coarse	very	Granules	very	fine	medium	coarse	very	BBLES	ULDERS (≥-8¢)	+	(after worth, 1922)	TERMS

Table 19 Sediment Size

MORPHIX


1×1

in

5 mm

Grain Size Scale

Photo Scale



Very well sorted **Table 20 Sediment Sorting**






Table 22 Geomorphic Units

- 1. Rapids
- 2. Cascade
- 3. Chute
- 4. Fast Glide
- 5. Pool
- 6. Riffle
- 7. Riffle Transition
- 8. Run
- 9. Slackwater
- 10. Slow Glide
- 11. Artificially Forced GU (specify 11-GU #)

(including rock fragments, sheared bedrock, weathered regolith, soils Joint opened (e.g., by Removal of support frost or roo (e.g., by river erosion, uarrying, wave action) Debris topple Clayey gra **Extremely slow** Rock block slide Dip slope Very slow to Soft clay with water-bearing silt movement of soft clays NO BEDROCK **APPROXIMATE** FLOW EQUIVALENT RATE OF Sand or silt flow MOVEMENT 3 m (10 ft) per second Rapid to 0.3 m (1 ft) 1.5 m (5 ft) 1.5 m (5 ft) 1.5 m (5 ft) .3 m (1 ft) MAINLY LARGE ROCK FRAGMENTS MOSTLY PLASTIC





possible.

capture all terraces if

level and

BF

Note: ex beyond B

Table 23 Mass Movement

- 1. Fall
- 2. Topple
- 3. Translational Slide
- 4. Rotational Slide
- 5. Lateral Spread
- 6. Flow

Version #3 Last edited: 04/04/2023

1×1

cm



April 18, 2024

Fruitland Landowners Group Inc. c/o Urbantech Consulting Engineers 2030 Bristol Circle, Suite 105 Oakville, Ontario L6H 0H2

Attn: Steve Hader, P.Eng.
Senior Project Manager

Re: Fluvial Geomorphological Assessment

Stoney Creek Watercourse 6.0

Fruitland-Winona Secondary Plan Area

GEO Morphix Project No. 21043a

GEO Morphix Ltd. was retained to examine the potential meander belt width associated with Watercourse 6.0 upstream of Barton Street in the City of Hamilton, Ontario as this allowance may define the development constraint limit for some areas adjacent to this watercourse. Watercourse 6.0 (**Reach WC6-A**) flows south to north between Barton Street and Regional Road 8, immediately east of Jones Road. Meander belt widths for Watercourse 6.0 were previously defined by others as part of the Stoney Creek Urban Boundary Expansion West Subwatershed Study (2013) and the Block 2 Servicing Strategy for the Fruitland-Winona Secondary Plan Lands (2018). These were defined for the tributary (Watercourse 6.0), but not for individual reaches. As such, the meander belt width was refined for the section of creek upstream of Barton Street.

We had previously defined a meander belt width in this area for an alternative project. This memo is consistent with that previous approach. To refine the meander belt width for this section of Watercourse 6.0 (**Reach WC6-A**), we have reviewed various background data and reporting, completed site reconnaissance to document existing watercourse characteristics, and updated the meander belt width assessment at a reach scale based on existing information and newly collected field observations.

Background Review

To inform our meander belt width assessment, we examined the following reports:

- Stoney Creek Urban Boundary Expansion (SCUBE) West Subwatershed Study Phase 1 and Phase 2 Final Report (Aquafor Beech Limited, May 15, 2013)
- Block 2 Servicing Strategy for the Fruitland Winona Secondary Plan Lands (Aquafor Beech Limited, April 3, 2018)
- Natural Heritage Characterization Assessment, 238 Jones Road and 820-832 Barton Street,
 City of Hamilton (Coville Consulting Inc., December 2018)
- City of Hamilton Watercourse 5 & 6 Class Environmental Assessment Study Draft Report (Dillon Consulting Limited, November 2007)
- City of Hamilton Watercourse 5.0 & 6.0 Hydraulic Assessment (Dillon Consulting Limited, September 2010)
- City of Hamilton Watercourse 5.0 & 6.0 Hydraulic Assessment (Dillon Consulting Limited, January 2011)

Aquafor Beech provided meander belt widths in the SCUBE West Subwatershed Study (Aquafor Beech, 2013). All calculations were based on the Toronto Region Conservation Authority (TRCA, 2004) model for defining the meander belt width. Using TRCA's (2004) model, they calculated a future meander belt width of 44 m for Watercourse 6.0. Given that they assumed hydrological changes, it is likely that they applied future flow conditions (i.e., discharge) and a factor of safety.

It should be noted that the TRCA (2004) model is based on gradient, drainage area, and discharge. For smaller watersheds, the model is very sensitive to channel slope, as it directly influences stream power. As such, the model relation between slope and meander belt width is inverse to what is observed in nature for smaller channels. Given this known issue, the TRCA (2004) model should be used with care, especially when it is applied in smaller watersheds and on low-order features.

Aquafor Beech recalculated the meander belt width in their April 2018 study: *Block 2 Servicing Strategy for the Fruitland-Winona Secondary Plan Lands*. The updated meander belt width was again calculated using the TRCA (2004) method. The meander belt width was calculated as 57.8 m. This may not be appropriate for Watercourse 6.0 (**Reach WC6-A**) upstream of Barton Street as only a portion of drainage area feeds this reach; it would therefore likely have a lower discharge and total drainage area than what was applied in the model.

In the 2004 and 2018 studies completed by Aquafor Beech, meander belt widths were not defined on a reach scale, which is the preferred approach/practice. Typically, meander belt widths are defined on the reach scale and not for an entire watercourse or tributary. Completing the analysis on a reach scale allows an appropriate discharge and drainage area to be applied. Applying it to the entire watercourse can result in a substantial overprediction of the meander belt width for upstream reaches. In Dillon's 2007 report *City of Hamilton Watercourse 5 & 6 Class Environmental Assessment Study Draft Report* Watercourse 6.0 was divided into five (5) separate reaches. **Reach WC6-A** is the section of Watercourse 6.0 upstream of Barton Street. Given that the watercourse was split into reaches, it is appropriate to provide meander belt widths for each of the assigned reaches. Furthermore, it was also assumed that the overall watercourse would experience changes in hydrology; however, the proposed Pond 3 will discharge at Barton Street, and therefore the hydrology through the reach upstream of Barton Street may not see an increase in peak flow or total discharge.

Given these facts, it is likely that the meander belt widths calculated by Aquafor Beech (2013, 2018) are an over-prediction for the reach in question. Also, in several locations, the meander belt width appears to be greater than the floodplain width, which is usually an indication that the predicted meander belt width is larger than the creek's realistic migration potential. This is reflected on Figure 5.3 on page 32 of the *Block 2 Servicing Strategy for the Fruitland-Winona Secondary Plan Lands* (Aquafor Beech, 2018). Given these discrepancies, we have reviewed and recalculated the meander belt width for this reach within the clients' properties. We have used a combination of desktop data and observations gathered through recent site reconnaissance.

Reach Delineation

Reaches are homogeneous segments of channel used in geomorphological investigations. Reaches are studied semi-independently as each is expected to function in a manner that is at least slightly different from adjoining reaches. This method allows for a meaningful characterization of a watercourse as the aggregate of reaches, or an understanding of a particular reach, for example, as it relates to a proposed activity.

Reaches are typically delineated based on changes in the following:

- Channel planform
- Channel gradient
- Physiography
- Land cover (land use or vegetation)
- Flow, due to tributary inputs
- Soil type and surficial geology
- Historical channel modifications

Reach delineation follows scientifically defensible methodology proposed by Montgomery and Buffington (1997), Richards et al. (1997), and the Toronto and Region Conservation Authority (2004) as well as others.

As noted previously, Watercourse 6.0 was divided into five (5) separate reaches as part of Dillon's 2007 report titled *City of Hamilton Watercourse 5 & 6 Class Environmental Assessment Study Draft Report*. The section of Watercourse 6.0 upstream (south) of Barton Street was classified as **Reach WC6-A**. Based on our review of available data (e.g., OBM topographic mapping, recent aerial imagery, surficial geology data), we are confidant that the section of Watercourse 6.0 situated between Barton Street and Regional Road 8 can be classified as one reach. The desktop reach delineation was also confirmed as part of our field reconnaissance. A reach map has been included in **Appendix A** for reference.

Field Reconnaissance

A field investigation was completed for **Reach WC6-A** on January 31st, 2024, and included the following observations:

- Habitat sketch maps based on Newson and Newson (2000) outlining channel substrate, flow patterns, geomorphological units (e.g., riffle, run, pool), and riparian vegetation for the extent of each reach assessed
- Descriptions of riparian conditions
- Estimates of bankfull channel dimensions
- Bed and bank material composition and structure
- Observations of erosion, scour, or deposition
- Collection of photographs to document the watercourse, riparian areas and/or valley, surrounding land use, and channel disturbances such as crossing structures

These observations and measurements are summarized below. The descriptions are supplemented and supported with representative photographs, which are included in **Appendix B**. Reach characteristics field sheets are provided in **Appendix C**. General reach characteristics are summarized in **Table 1**.

Reach WC-6A was characterized as unconfined, having a single channel with secondary flow paths, and a shallow gradient. Surrounding land use consisted of agricultural and low-density residential. Riparian vegetation was dominated by a continuous buffer of grasses and shrubs, with some wooded areas interspersed. Several woody debris jams were present at the mid-portion of the reach, with the formation of large pools. The reach lacked a regular riffle pool sequence, aside from a wooded midsection with mature willows. Substrate within the observed riffles consisted largely of clay and silt, rootlets, and some cobble, whereas the runs/pools throughout the reach consisted predominately of clay. The average bankfull width and depth were 2.58 m and 0.56 m, respectively. Bank angles ranged between 30° to 60° and the bank materials consisted of clay, and silt. Evidence of erosion was observed along 30% to 60% of the channel and was primarily observed at the downstream portion along outer the

bends. Rooted emergent vegetation was observed along approximately 45% of the reach. Aquatic vegetation consisted mainly of grasses and cattails. Banks were densely vegetated, and bank materials consisted of clay, and silt.

Table 1: General reach observations

Reach	Average Bankfull	Average Bankfull	Substrate		Riparian			
	Width (m)	Depth (m)	Pools	Riffles	Vegetation	Notes		
WC6-A	2.58	0.56	Clay and silt	Clay, cobble, and rootlets	Fragmented coverage of trees and shrubs	Partially confined/ woody debris jams/ encroachment of cattails and grasses downstream		

Rapid Assessments

Channel stability and susceptibility to erosion were objectively assessed through the application of the Ontario Ministry of the Environment (MOE) (2003) Rapid Geomorphic Assessment (RGA) technique. The RGA evaluates degradation, aggradation, widening, and planimetric form adjustment at the reach scale. The end result of the RGA is to produce a score, or stability index, which evaluates the degree to which a stream has departed from its equilibrium condition. A stream with a score of less than 0.20 is in regime, indicating minimal changes to its shape or processes over time. A score of 0.21 to 0.40 indicates that a stream is in transition or stress and is experiencing major changes to process and form outside the natural range of variability. A score of greater than 0.41 indicates that a stream is in extreme adjustment, exhibiting a new stream type, or in the process of adjusting to a new equilibrium (MOE, 2003 and VANR, 2007).

The Rapid Stream Assessment Technique (RSAT) was also employed to provide a broader view of the system and consider the ecological functioning of the watercourse (Galli, 1996). Observations were made of channel stability, channel scouring or sediment deposition, instream and riparian habitats, and water quality. The RSAT score ranks the channel as maintaining a poor (<13), fair (13-24), good (25-34), or excellent (35-42) degree of stream health.

The reaches were also classified according to the Downs (1995) Model of Channel Evolution. The Downs (1995) model describes successional stages of a channel as a result of perturbation, namely hydromodification. Understanding the current stage of the system is beneficial as this allows one to predict how the channel will continue to evolve or respond to an alteration to the system. Rapid assessment results are summarized in **Table 2**, below.

For **Reach WC6-A** the RGA score was 0.40, indicating that the stream was in transition. The dominant geomorphic processes shaping the channel were determined to be widening and planimetric form adjustment. Evidence of widening included large organic debris, and basal scour throughout the channel and riffles. Evidence of planimetric adjustment was noted as the evolution of a riffle-pool form to a low bed relief from, single thread to multiple channels, formation of chutes, and poor bar forms. The RSAT score for this reach was 23, indicating that the stream was in fair condition. The limiting features were physical instream habitat due to a lack of riffle pool sequencing and riparian habitat conditions due to limited canopy cover. Using the Downs (1995) model, the dominant channel evolution mechanism was determined to be lateral migration.

Table 2: Rapid assessment results

	RGA			RSAT				
Reach	Score Condition		Dominant Systematic Adjustment	Score	Condition	Limiting Feature(s)	Downs (1995)	
WC6-A	0.40	In Transition	Evidence of widening and planimetric form adjustment	23	Fair	Physical Instream Habitat, Riparian Habitat Conditions	Lateral Migration	

Meander Belt Width Assessment

There are several methods for determining the meander belt width of individual reaches. The first approach includes collecting field measurements of reaches and meander amplitudes from aerial photographs or field observations. The second approach would be defining the meander belt width based on relations between meander belt width and channel geometry using field measurements of the channel. Finally, the third approach is to apply empirical models, such as TRCA's (2004) model for delineating the meander belt width at a reach scale.

As a component of the *City of Hamilton Watercourse 5.0 & 6.0 Hydraulic Assessment* completed by Dillon Consulting (2011) a preliminary flow analysis for Watercourse 6.0 was completed. All 2-year flows for Watercourse 6.0 identified in this analysis are provided in **Table 2** below. Based on the 2-year flows for Watercourse 6.0, discharge decreases upstream of Barton Street.

Table 2. 2-year flows for Watercourse 6.0 (Dillon, 2010 and 2011)

Location	2-year flow
Watercourse 6.0 at Barton Street*	1.12
Watercourse 6.0 at CNR	1.58
Watercourse 6.0 at South Service Road	1.72
Watercourse 6.0 at QEW/Diversion	1.72

^{*}Location immediately upstream of Barton Street

Using the TRCA (2004) model, GEO Morphix calculated a meander belt width for Watercourse 6.0 (**Reach WC6-A**) on a reach scale. The TRCA model relation is outlined below in Equation 1.

$$Bw = -14.827 + 8.319ln (\rho gQS * DA)$$

[Equation 1]

Where p is water density (1000 kg/m³), g is acceleration due to gravity (9.8 m/s²), Q is discharge (m³/s), S is channel slope (m/m), and DA is drainage area (km²).

To satisfy the model, a drainage area of $1.81~\rm km^2$ was identified using the Ontario Flow Assessment Tool (OFAT). This drainage area extent is likely conservative as it includes a section of channel upstream of the escarpment. The 2-year flow from Dillon's assessment (2011) was applied for **Reach WC6-A** at Barton Street ($1.12~\rm m/s^3$). The meander belt width was calculated as $37.8~\rm m$. This includes one standard deviation, as changes to hydrology upstream of Barton Street are not expected. Without one

standard deviation, the meander belt width for **Reach WC6-A** at Barton Street was 29.2 m. These values are all lower than those previously outlined by Aquafor Beech (2013, 2018).

A modified Williams (1986) model can also be used to determine the meander belt width based on field measurements of channel geometries. This approach has been accepted in numerous Conservation Authority jurisdictions, including Hamilton Region Conservation Authority. This modified model also accounts for the average bankfull width of the channel and an additional 20% factor of safety. This modified relation is outlined below in Equation 2.

$$BW = ([4.3 \times W_b^{1.12}] + W_b) \times 1.2$$

[Equation 2]

Bankfull channel geometry was surveyed as part of our detailed geomorphological assessment for a sub-section of **Reach WC6-A**. Using the Williams (1986) model, with a 20% factor of safety applied, the meander belt width for the average 2.58 m bankfull width was calculated as 18.0 m.

A desktop analysis of aerial photographs was also completed to determine the meander belt width based on existing or historical meander amplitudes. A 13-year record of aerial photographs was available on Google Earth Pro and included photos from 2005, 2009, 2015, 2016, 2017, and 2018. The majority of the channel had a straight planform, however meander amplitudes that were observable were approximately 8.5-9.5 m wide. The largest meanders were measured at 15-16 m. Using the maximum meander amplitude (16 m), the average bankfull width (2.58 m) and a 20% factor of safety, the meander belt width is calculated as 22.3 m. **Table 3** below outlines the range of meander belt widths that have been calculated for Watercourse 6.0 or **Reach WC6-A**.

Table 3. Meander belt widths for Watercourse 6.0

Meander Belt Width Calculation Method	Meander Belt Width (m)
TRCA Model*	
Aquafor Beech (2013)	44.0
Watercourse 6.0	
TRCA Model*	
Aquafor Beech (2018)	57.8
Watercourse 6.0	
TRCA Model*	
One Standard Error Added (Assuming no change to hydrology upstream of Barton St)	37.8
GEO Morphix (2024) using Dillon (2011) modelled discharge (1.12 m ³ /s)	37.0
Reach WC6-A	
TRCA Model*	
No Standard Error Added	29.2
GEO Morphix (2024) using Dillon (2011) modelled discharge (1.12 m ³ /s)	25.2
Reach WC6-A	
Williams Model**	
Assuming 2.58 m wide channel and 20% Factor of Safety	18.0
GEO Morphix (2024)	10.0
Reach WC6-A	
Largest Meander Amplitude	
Largest measured meander amplitude + bankfull channel width + 20% Factor of Safety	22.3
GEO Morphix (2024)	22.5
Reach WC6-A	

^{*} TRCA (2004) Belt Width Delineation Procedures

^{**} Williams (1986) River Meanders and Channel Size

Summary

Based on our review of available reports and data as well as additional field reconnaissance, GEO Morphix calculated a range of meander belt widths for Watercourse 6.0 (specifically Reach WC6-A) using a variety of different methods. Meander belt widths ranged from 22.3 m to 37.8 m. These values were all substantially lower than the previous meander belt widths calculated by Aquafor Beech (2013, 2018). It is likely that the meander belt width falls within the range that we have summarized from our calculations. As such, we suggest a meander belt width of 30 m for Reach WC6-A is appropriate and could be applied.

The meander belt width determined here is based on observations from a sub-section of Reach WC6-A within the 238 Jones Road property. Given our confirmation of watercourse conditions upstream and downstream of the property at Regional Road 8 and Barton Street, we are confident that the meander belt width can be applied to the entire length of the reach.

It should be noted that the previous meander belt width determined by Aquafor Beech can be applied to other reaches of Watercourse 6.0 upstream (south) of Regional Road 8 and downstream (north) of Barton Street. Refinement of the meander belt width in these locations would require additional desktop and field reconnaissance.

We trust this letter meets your current requirements. Should you have any questions, please contact the undersigned.

Respectfully submitted,

Paul Villard, Ph.D., P.Geo., CAN-CISEC, EP, CERP Director, Principal Geomorphologist

Lindsay Davis, M.Sc., P.Geo., CAN-CISEC Geomorphologist, Project Manager

Lindsay Dew

References

Aquafor Beech Ltd. 2018. Block 2 Servicing Strategy for the Fruitland-Winona Secondary Plan Lands. Final Report.

Aquafor Beech Ltd. 2013. Stoney Creek Urban Boundary Expansion (SCUBE) West Subwatershed Study Phase 1 and Phase 2 Final Report.

Colville Consulting Inc. 2018. Natural Heritage Characterization Assessment. 238 Jones Road and 820-832 Barton Street – City of Hamilton.

Dillon Consulting Limited. 2011. Watercourse 5.0 & 6.0 Hydraulic Assessment. City of Hamilton.

Dillon Consulting Limited. 2010. Watercourse 5.0 & 6.0 Hydraulic Assessment. City of Hamilton.


Dillon Consulting Limited. 2007. Watercourse 5 & 6 Class Environmental Assessment Study – Draft Report. City of Hamilton.

Harnes, H.H. 1967. Roughness Characteristics of Natural Channels. Prepared for: U.S. Geological Survey. United States Government Printing Office. Washington, D.C. Retrieved via: https://pubs.usgs.gov/wsp/wsp_1849/pdf/wsp_1849-test-2.pdf

Toronto and Region Conservation Authority (TRCA). 2004. Belt Width Delineation Procedures.

Williams. 1986. River Meanders and Channel Size.

Appendix A Study Area Mapping



Legend





Meander Belt Width


Approximate Extent of MBW



Meander Belt Width

Fruitland-Winona Block 1 Servicing Strategy

Hamilton, Ontario



Imagery: Google Earth Pro: 2018 Subject Property: Parish Aquatic Services, 2019. Watercourse and 1 m Contour: City of Hamilton, 2020. Meander Belt Width: GEO Morphix Ltd., 2024. Printed: April 2024. PN21043. Drawn by: L.D., M.O., G.U.

Appendix B Photographic Record



Upstream extent of **Reach WC-6** facing downstream. The channel was well defined within a grassy corridor and dominated by runs.



Multiple poorly defined secondary flow paths were also present within the corridor.

i



The middle of the reach consisted of a single channel within a narrow forested riparian zone.





Several woody debris jams were present throughout the mid-section of the reach. Woody debris was common along the banks as well.



Basal scouring was observed throughout the reach, in particular at the downstream section. Bed and bank materials consisted primarily of clay.



A swale present in the adjacent agricultural field contributed to stream flow.

Photo 7
Reach WC-6 - Watercourse 6, Hamilton, Ontario



Multiple flow paths were present within a swale feature at the downstream section of the reach.





Downstream extent of **Reach WC-6** facing downstream.

Appendix C Field Sheets

21043a

11



General Site Characteristics

Project Number: 21043a

Date:	2024-01-31	Stream:	
Time:	9:30	Reach:	WC-60
Weather:	4°C	Location:	Fruitland-Winona
Field Staff:	SC HF	Watershed/Subwatershed:	W Lake ON Shoreling

Field	Staff:	SC HF	Watershed/Subwatershed: W Lake ON Shoreline
Featu	ıres	Monitoring	Site Sketch Compass
<u> </u>	Reach break	-≎≎- Long-profile	
只	Station location	I——I Monumented XS	3 (A)
X	Cross-section	Monumented photo	
-	Flow direction	Monumented photo	
~~	Riffle	▼ direction	
	Pool	Sediment sampling	
CANADO .	Sediment bar	Erosion pins	· dens grassy
HHHHHH	Froded bank/slope	0 Scour chains	E wide saded?
	Undercut bank	Additional Symbols	E widens grassy Plooded?
XXXXXX	Bank stabilization		
	Leaning tree		8
××	Fence		2 833
	Culvert/outfall		- multiple
	Swamp/wetland		of multiple
VVV	Grasses	Y .	E3 Commons
	Tree		is what
	Instream log/tree		
***	Woody debris		3 Swale
******	Beaver dam		2
W	Vegetated island		E Chais Cooks
Flow			5 3 50 VIV 51 50 50
H1	Standing water H1		
H2	Scarcely perceptible	flow	
H3	Smooth surface flow		Hiple Miles
HA H5	Upwelling		or flow parks & Flow of woody debris
1	Rippled		2 thouse of woody debris
H6	Unbroken standing w	1	30 Cut trees
H7 H8	Broken standing wav Chute	e	The confidence
H9			3 7.
Substi	Free fall H9A	Dissipates below free fall	24 loses definition
S1	Silt	S6 Small boulder	
S2	Sand		8 V V V V Dancoutture
S3	Gravel	S7 Large boulder S8 Bimodal	5.4m agriculture
S4	Small cobble	S9 Bedrock/till	1 2.74 2.014
S5	Large cobble	oo bedrocky till	1 Viles Con
Other			0 6
вм	Benchmark	EP Erosion pin	V V grassy
BS	Backsight	RB Rebar	(channel
DS	Downstream	US Upstream	corridor
WDJ	Woody debris jam	TR Terrace	10 miles
VWC	Valley wall contact	FC Flood chute	US made for a Corest line
BOS	Bottom of slope	FP Flood plain	TOICST MILE
TOS	Top of slope	KP Knick point	TARCH US TO DS
^	p or slope	KHICK POINT	Notes:

Page $_$ of 2



General Site Characteristics Project Number: 21043a

Date:	2024-01-31	Stream:	
Time:	9:30	Reach:	WC-6
Weather:	4·C	Location:	Fruitland-Winong
Field Staff:	SC HF	Watershed/Subwatershed:	W Lake ON Shoreling

Field	Staff:	SC HF		Watershed/Subwate	ershed:	W Lake 0	N Short
Featu	res	Monitoring	Site	Sketch	ana		Compass
₽ ×—× →	Flow direction Riffle	O Long-profile Monumented XS Monumented photo Monumented photo direction	tree !	line VI		DS	7
########	,	Sediment sampling Erosion pins Scour chains		1	enc	roched cattails reeds	
**************************************	Undercut bank Bank stabilization Leaning tree Fence Culvert/outfall Swamp/wetland	Additional Symbols	hic	her A	P	rude: 6.23 m	
***	Grasses Tree Instream log/tree Woody debris Beaver dam		Pied Pied		multi path a	ple from 15 within Swale feature	e Field
Flow 1	Vegetated island		1	V			Š
H1 H2 H3 H4 H5 H6 H7 H8	Standing water H1, Scarcely perceptible Smooth surface flow Upwelling Rippled Unbroken standing way Broken standing way Chute	flow vave ve	agriculture	500		orrows	agriculture
H9 Substr	Free fall H9/	A Dissipates below free fall		Flooding =>	(()		
\$1 \$2 \$3 \$4 \$5	Silt Sand Gravel Small cobble Large cobble	\$6 Small boulder\$7 Large boulder\$8 Bimodal\$9 Bedrock/till		ස	1 1/2 04	ton high	
Other BM	Benchmark	EP Erosion pin			/	70	
BS DS WDJ VWC	Backsight Downstream Woody debris jam Valley wall contact	RB Rebar US Upstream TR Terrace FC Flood chute			V		
BOS TOS	Bottom of slope Top of slope	FP Flood plain	Photo				
.03	1 oh or siohe	KP Knick point	Notes				

4) feature w: 10.5m d:1.15m

main channel ww: 1.16m wd: 0.33m

Version #4 Last edited: 21/02/2023

Senior staff sign-off (if required): _____ Checked by: ____ Completed by: ____

Page 2 of 2

Reach Characteristics		Project Number:	ber: 21043a							M O R P H I X"
Date:	2024-01-	100	Field Staff:	出 XX		Watershed	Watershed/Subwatershed:	ned:	NO	Moreline
Time:	9:30		Stream:			UTM (Upstream):	ream):	1	,	
Weather:		overcast	Reach:	MC-6		UTM (Downstream):	nstream):			
Land Use	Valley Type (Table 2)	Channel (Table 3)	Type 12	Channel Zone Zable 4)	Flow Type (Table 5)	Ev	idence of Groun	Evidence of Groundwater Location:		Photo:
Riparian Vegetation				Aquatic & Inst	Aquatic & Instream Vegetation			Water Quality		
Dominant Type	Coverage ch	Channel Widths	s Age (yrs)	Туре	Woody Debris	WD Density		Odour		Turbidity
	□ None	1 - 4	☐ Immature (<5)	(Table 8)	☐ In Cutbank	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \	WDJ/50m:	(Table 16)		(Table 17)
Encroachment (Table 7)	Fragmented		¥ Established (5-30) □ Mature (>30)	Reach	In Channel	Mod High	o v			7
Channel Characteristics	itics									
Sinuosity Type (Table 9)	Sinuosity Degree (Table 10)	ty Degree (Table 10)	Bank Angle	Bank Erosion □ < 5%	(Table 19)	Clay/Silt	Sand Gravel	Cobble Boulder	der Parent	Rootlets
Gradient (Table 11)	# of Channels (Table 12)	Channels (Table 12)	30 - 60	□ 5 – 30%	Riffle					
Entrenchment (Table 13)	Bank Failure (Table 14)		Undercut	□ 60 - 100%	Bed (if no riffle-pool	9 🗆				
Down's Model m/& (Table 15)	Bankfull I		5,5	Bankfull Width (m)	2.8 2.8	273	Wetted Width (m)	n (m) (.5	2.2	2.5
Sed Sorting well (Table 20) Sorted	Sediment]	☐ Yes 🗹 No 🗆 Not Visible	Bankfull Depth (m)	0.55	0.53	Wetted Depth (m)	n (m) 0,35	22.0	0.38
Transport Mode (Table 21)	% of Bed Active	\vee	V)	Undercuts (m)			Velocity (m/s)	m/s) 0.042	14.0	0.36
Geomorphic 8/10	Mass	fovement (Table 23)	9L on 1.	Pool Depth (m)	74.0 82.	6.38	Velocity Estimate Method	Stimate $\omega \mathcal{B}$	E S	83
Spacing (m):	% Ri	% Riffles:	% Pools:	Riffle Length (m)	318	0	Meander Amplitude (m)	itude (m)	6.73	
Notes:										
Flow paths	at the	hannel	throughout	treow section	reach.	Several	4 400c/V	-	secondo	
arassy with	energo	Ching	cattails 4	H	die.	1 1/4	ach ha	0000	1	3 5
Some	oreas. 1	- 4		dominated k	SVOOD TO	to sta	M Sinu	MITH COOD	les 4	poulders e
OF recei	nt high	300	06 670800	MOS OUSE	× 1000 +	ronghant	the r	each. Evi	idence	
Photos:	>									

Version #4 Last edited: 04/04/2023

Completed by: SC/HF

Checked by:

Senior staff sign-off (if required): _



Rapid Geomorphic Assessment Project Number: 2\0\43a

	400							
Time:	9	:30	Reach:		MC-6	*		
Weather:		4.C overcas	Location:		Fruitlan	nd-la	linar	AC).
Field Staff:		SC HF		ubwatershed:	WLake			
			eomorphological Indi	icator	10 20011100		esent?	
Process	No.	Description				Yes	No	Factor Value
	1	Lobate bar				1.00	X	
	2	Coarse materials in riffle	es embedded			V	+ -	-
Evidence of	3	Siltation in pools				_	×	11
Aggradation	4	Medial bars					V	/7
(AI)	5	Accretion on point bars	· · · · · · · · · · · · · · · · · · ·				1	-
	6	Poor longitudinal sorting	g of bed materials	*****	· · · · · · · · · · · · · · · · · · ·	X		
	7	Deposition in the overba						
			*	S	Sum of indices =	. 2	5	0.29
	1	Exposed bridge footing(s)				1,.	
	2	Exposed sanitary / stori		etc.		N	177	-
	3	Elevated storm sewer o			· · · · · · · · · · · · · · · · · · ·	4	IVA	
	4	Undermined gabion bas		ns / etc.	· · · · · · · · · · · · · · · · · · ·	N		-
Evidence of Degradation	5	Scour pools downstream				N	VA	10/6
(DI)	6	Cut face on bar forms	*	4		.,	X	
` ,	7	Head cutting due to knie	ckpoint migration				V	-
	8	Terrace cut through old	er bar material		7		X	
	9	Suspended armour laye	r visible in bank				T ×	1
	10	Channel worn into undis	sturbed overburden /	bedrock	-		X	
				S	um of indices =			0
	1	Fallen / leaning trees / f	ence posts / etc.			X		
	2	Occurrence of large orga	anic debris			X		
	3	Exposed tree roots		X		1		
Evidones	4	Basal scour on inside me	eander bends			X		
Evidence of Widening	5	Basal scour on both side	es of channel through	riffle		X		- 6/
(WI)	6	Outflanked gabion baske				N	M	1 8
	7	Length of basal scour >				X		
	8	Exposed length of previous		ible / etc.			X	
	9	Fracture lines along top					X	
	10	Exposed building founda	ition			NI		
				S	um of indices =	6	2	0.75
	1	Formation of chute(s)				Х		
Evidence of	2	Single thread channel to				X		
Planimetric	3	Evolution of pool-riffle fo	orm to low bed relief	form -> pool-ri	ffle in	X		11
Form Adjustment		Cut-off channel(s)		mid	idle of -	- V	X	1/2
(PI)		Formation of island(s)			ach		X	//
		Thalweg alignment out o					X	
	7	Bar forms poorly formed	/ reworked / remove	ed		X		V
				Sı	um of indices =	4	3	0.57
Notes:				Stability Ind	ex (SI) = (AI+	-DI+WI	+PI)/4 =	0.40
				In Regime				djustment
				□ 0.00 - 0.		1 - 0.40		,

Version #3 Last edited: 10/02/2023 Senior staff sign-off (if required): _____ Checked by: ____ Completed by: ____



Rapid Stream Assessment Technique Project Number: 21043a

Date:	2024-01-31	Stream:						
Time:	9:30	Reach:	13454	WC-6	Cotuany Pas			
Weather:	4.C overcas	Location:			d-Winona			
Field Staff:	SC HF	Watershed/Subwate	rshed:		N Shoreline			
Category	Poor	Fair	XII SIOOG	Good	Excellent			
	 < 50% of bank network stable Recent bank sloughing, slumping or failure frequently observed 	50-70% of bank network stable Recent signs of bank sloughing, slumping or failure fairly common	cable ecent signs of bank oughing, slumping or stable Infrequent signs of bank sloughing, slumping or					
Channel Stability Point range Channel Scouring/ Sediment Deposition	 Stream bend areas highly unstable Outer bank height 1.2 m above stream bank (2.1 m above stream bank for large mainstem areas) Bank overhang > 0.8-1.0 m 	Stream bend areas unstable Outer bank height 0.9-1.2 m above stream bank (1.5-2.1 m above stream bank for large mainstem areas) Bank overhang 0.8-0.9m	Outer by mabov 1.5 m a for larg	bend areas stable ank height 0.6-0.9 e stream bank (1.2- bove stream bank e mainstem areas) rerhang 0.6-0.8 m	Stream bend areas very stable Height < 0.6 m above stream (< 1.2 m above stream bank for large mainstem areas) Bank overhang < 0.6 m			
	 Young exposed tree roots abundant > 6 recent large tree falls per stream mile 	Young exposed tree roots common 4-5 recent large tree falls per stream mile	predom large, s scarce • 2-3 rec	d tree roots inantly old and maller young roots ent large tree falls am mile	Exposed tree roots old, large and woody Generally 0-1 recent large tree falls per stream mile			
	Bottom 1/3 of bank is highly erodible material Plant/soil matrix severely compromised	Bottom 1/3 of bank is generally highly erodible material Plant/soil matrix compromised	general	1/3 of bank is ly highly resistant oil matrix or material	Bottom 1/3 of bank is generally highly resistant plant/soil matrix or materia			
	Channel cross-section is generally trapezoidally- shaped	Channel cross-section is generally trapezoidally- shaped		Cross-section is ly V- or U-shaped	Channel cross-section is generally V- or U-shaped			
Point range	□ 0 □ 1 □ 2	□ 3 □ 4 □ 5	₫ 6	0708	□ 9 □ 10 □ 11			
	> 75% embedded (> 85% embedded for large mainstem areas)	• 50-75% embedded (60- 85% embedded for large mainstem areas)	59% en	embedded (35- nbedded for large m areas)	Riffle embeddedness < 25% sand-silt (< 35% embedded for large mainstem areas)			
Point range Channel Scouring/ Sediment	Pool substrate composition >81% sandsilt composition >81% sandsilt	Low to moderate number of deep pools Pool substrate composition 60-80% sand-silt	pools Pool sub	ce number of deep estrate composition sand-silt	High number of deep pools (> 61 cm deep) (> 122 cm deep for large mainstem areas) Pool substrate composition <30% sand-silt			
	Streambed streak marks and/or "banana"-shaped sediment deposits common	Streambed streak marks and/or "banana"-shaped sediment deposits common	and/or "	ped streak marks banana"-shaped ot deposits	Streambed streak marks and/or "banana"-shaped sediment deposits absent			
190511 101 (* 103 <) pa	 Fresh, large sand deposits very common in channel Moderate to heavy sand deposition along major portion of overbank area 	 Fresh, large sand deposits common in channel Small localized areas of fresh sand deposits along top of low banks 	uncommSmall lo fresh sa	arge sand deposits non in channel calized areas of nd deposits along w banks	Fresh, large sand deposits rare or absent from channel No evidence of fresh sediment deposition on overbank			
D 7	Point bars present at most stream bends, moderate to large and unstable with high amount of fresh sand	Point bars common, moderate to large and unstable with high amount of fresh sand	well-veg	rs small and stable, letated and/or ld with little or no and	Point bars few, small and stable, well-vegetated and/or armoured with little or no fresh sand			
Point range	□ 0 □ 1 □ 2	□ 3 □ 4		5 🗵 6	□ 7 □ 8			

Last edited: 10/02/2023

Senior staff sign-off (if required): _____ Checked by: ____ Completed by: ____



Date:	2024-01-31	PN: 21043a	Location: F	ruitland-Winon		
Categor	y Poor	Fair	Good	Excellent		
	 Wetted perimeter < 40% of bottom channel width (< 45% for large mainstem areas) 	Wetted perimeter 40- 60% of bottom channel width (45-65% for large mainstem areas)	 Wetted perimeter 61-85% of bottom channel width (66-90% for large mainstem areas) 	 Wetted perimeter > 85% of bottom channel width (> 90% for large mainstem areas) 		
	Dominated by one habitat type (usually runs) and by one velocity and depth condition (slow and shallow) (for large mainstem areas, few riffles present, runs and pools dominant, velocity and depth diversity low)	Few pools present, riffles and runs dominant. Velocity and depth generally slow and shallow (for large mainstem areas, runs and pools dominant, velocity and depth diversity intermediate)	Good mix between riffles, runs and pools Relatively diverse velocity and depth of flow	 Riffles, runs and pool habitat present Diverse velocity and depth of flow present (i.e., slow, fast, shallow and deep water) 		
Physica Instrear		Riffle substrate composition: predominantly small cobble, gravel and sand 5-24% cobble	 Riffle substrate composition: good mix of gravel, cobble, and rubble material 25-49% cobble 	 Riffle substrate composition: cobble, gravel, rubble, boulder mix with little sand > 50% cobble 		
Habita	• Riffle depth < 10 cm for large mainstem areas	Riffle depth 10-15 cm for large mainstem areas	Riffle depth 15-20 cm for large mainstem areas	Riffle depth > 20 cm for large mainstem areas		
N/A Point range	Large pools generally < 30 cm deep (< 61 cm for large mainstem areas) and devoid of overhead cover/structure	Large pools generally 30- 46 cm deep (61-91 cm for large mainstem areas) with little or no overhead cover/structure	Large pools generally 46-61 cm deep (91-122 cm for large mainstem areas) with some overhead cover/structure	Large pools generally > 61 cm deep (> 122 cm for large mainstem areas) with good overhead cover/structure		
	Extensive channel alteration and/or point bar formation/enlargement	Moderate amount of channel alteration and/or moderate increase in point bar formation/enlargement	Slight amount of channel alteration and/or slight increase in point bar formation/enlargement	No channel alteration or significant point bar formation/enlargement		
	• Riffle/Pool ratio 0.49:1; ≥1.51:1	• Riffle/Pool ratio 0.5- 0.69:1 ; 1.31-1.5:1	• Riffle/Pool ratio 0.7-0.89:1 ; 1.11-1.3:1	• Riffle/Pool ratio 0.9-1.1:1		
1	• Summer afternoon water temperature > 27°C	Summer afternoon water temperature 24-27°C	Summer afternoon water temperature 20-24°C	Summer afternoon water temperature < 20°C		
Point rar	ge 0 1 2	□ 3 ሺ 4	□ 5 □ 6	□ 7 □ 8		
91	Substrate fouling level: High (> 50%)	Substrate fouling level: Moderate (21-50%)	Substrate fouling level: Very light (11-20%)	Substrate fouling level: Rock underside (0-10%)		
Water Ou	Brown colour TDS: > 150 mg/L	• Grey colour • TDS: 101-150 mg/L	• Slightly grey colour • TDS: 50-100 mg/L	• Clear flow • TDS: < 50 mg/L		
Water Qu	Objects visible to depth < 0.15m below surface	Objects visible to depth 0.15-0.5m below surface	Objects visible to depth 0.5-1.0m below surface	Objects visible to depth 1.0m below surface		
	Moderate to strong organic odour	Slight to moderate organic odour	Slight organic odour	· No odour		
Point rar	nge	□ 3 □ 4	□ 5 × 6	□ 7 □ 8		
Riparia		 Ripalian area predominantly wooded but with major localized gaps 	Forested buffer generally 31 m wide along major portion of both banks	Wide (> 60 m) mature forested buffer along both banks		
Habita Conditio	Canony coverage:	Canopy coverage: 50- 60% shading (30-44% for large mainstem areas)	Canopy coverage: 60-79% shading (45-59% for large mainstem areas)	Canopy coverage: >80% shading (> 60% for large mainstem areas)		
Point rai	nge 🗆 0 💆 1	□ 2 □ 3	□ 4 □ 5	□ 6 □ 7		
Total ove	erall score (0-42) = 23	Poor (<13) F	Fair (13-24) Good (25-	Excellent (>35)		

Version #2 Last edited: 10/02/2023 Senior staff sign-off (if required): _____ Checked by: ____ Completed by: ____



Fluvial Geomorphology Field Key

Table 1 Land Use

- 1. Forest
- 8. Golf Course

9. Commercial

- 2. Pasture
- 3. Agricultural
- 4. Industrial
- 5. Park
- 6. Institutional
- 7. Residential

Table 2 Valley Type

- 1. Unconfined
- 2. Confined
- 3. Partially Confined

Table 3 Channel Type

Table 4 Channel Zone

- 1. Headwater zone
- 2. Transfer zone
- 3. Deposition zone

Table 5 Flow Type

- 1. Perennial
- 2. Intermittent
- 3. Ephemeral

Table 6 Dominant Vegetation Type

- 1. Trees
- 2. Shrubs
- 3. Grasses
- 4. Herbaceous

Table 7 Encroachment Extent into Channel

- 1. None
- 5. Extreme
- 2. Minimal
- 3. Moderate
- 4. Heavy

Table 11 Gradient

Table 10 Degree of

1. Straight (1 – 1.05)

2. Low sinuosity (1.06-1.30)

3. Meandering (1.31 - 3.0)

Table 12 Number of

2. Up to 3 (Wandering)

4. >3 (Anastamosing or

5. Discontinuous or Absent

1. Low

Meandering

2. Moderate

Channels

3. >3 (Braided)

Anabranching)

1. Single

Sinuosity

3. High


Table 8 Type of Aquatic Vegetation


- 1. Rooted Emergent
- 2. Rooted Submergent
- 3. Rooted Floating
- 4. Free Floating Roots
- 5. Floating Algae
- 6. Attached Algae


Sinuosity 1. Sinuous


Table 9 Type of

- 2. Irregular Meanders
- 3. Regular Meanders
- 4. Tortuous Meanders
- 5. Confined pattern (within valley)





























discontinuous or absent

Table 13 **Entrenchment**

- 1. Low (>2.2)
- 2. Moderate (1.4 2.2)
- 3. High (<1.4)








Failure




- old tree roots exposed no tree falls
 - no bank erosion no alluvial terrace



erosion along outer bank (e.g.

erosion along both banks (e.g. no alluvial terrace




channel downcutting (e.g. bed scour, lov


steep, high banks above bankfull leve

generally straight

- stable except at sharp bends alluvial terrace/valley wal sharp bends with outside bank erosion, pointvalley wall contacts at few, if any meande har/cut bank development and undercutting
 - no alluvial terrace



no alluvial terrace



- bank erosion (slumping, exposed tree roots) sediment denosition on hed (e.g. bar
- alluvial terrace with erosic

- ☐ straight alluvial terrace/valley wall

Slab failure

- valley wall contact and erosion at majority of deposition along inner bank (i.e. point ba
 - scoured bed, low emb

erosion along outer bank (e.g. slumping, you

Table 14 Type of Bank 1. Fluvial Entrainment (Hydraulic

- action) 2. Undercutting (Hydraulic action)
- 3. Slab Failure (Mass failure) 4. Parallel slide (Mass failure)
- 5. Fall/Sloughing (Mass failure)
- 6. Rotational slip and slump (Mass failure)






Table 15 Downs's Model of


- D / d Depositional
- M / m Lateral Migration E or e - Enlarging

Channel Classification

C - Compound

S – Stable

- R Recovering
- U Undercutting



Odours

1. None

2. Fishv

3. Petroleum

4. Sewage


6. Other

5. Chemical

Table 17 Turbidity

- 1. Clear
- 2. Slightly turbid
- 3. Turbid
 - 4. Opaque
 - 5. Stained 6. Other







UNCONSOLIDATED MATERIALS

Fluvial Geomorphology Field Key


% Cover

Sorting

Table 18 Bankfull Indicators

- 1. Topography
- 2. Soil Horizons
- 3. Bank Slope
- 4. Sediment Texture
- 5. Vegetation
- 6. Mineral Stains
- 7. Undercuts
- 8. Flood deposits
- 9. Other

GEO



.002	.004-	.008-	.016	2 :	.053	.105	.210 .177 .149	.420 .354 .297	.840 .707 .545	1.63 1.41 1.19	2.38 2.00	3.36	6.73 5.66 4.76	13.4 11.3 9.52	26.9 22.6 17.0	53.9 45.3 33.1		0	256	mm	GRAIN
CLAY			SIL					SAND			4			BBLE			8	B0		Went	SIZE
	fine	var.	fine	medium	coarse	very	fine	medium	coarse	very	Granules	very	fine	medium	coarse	very	BBLES	ULDERS (≥-8¢)	+	(after worth, 1922)	TERMS

Table 19 Sediment Size

MORPHIX


1×1

in

5 mm

Grain Size Scale

Photo Scale



Very well sorted **Table 20 Sediment Sorting**






Table 22 Geomorphic Units

- 1. Rapids
- 2. Cascade
- 3. Chute
- 4. Fast Glide
- 5. Pool
- 6. Riffle
- 7. Riffle Transition
- 8. Run
- 9. Slackwater
- 10. Slow Glide
- 11. Artificially Forced GU (specify 11-GU #)

(including rock fragments, sheared bedrock, weathered regolith, soils Joint opened (e.g., by Removal of support frost or roo (e.g., by river erosion, uarrying, wave action) Debris topple Clayey gra **Extremely slow** Rock block slide Dip slope Very slow to Soft clay with water-bearing silt movement of soft clays NO BEDROCK **APPROXIMATE** FLOW EQUIVALENT RATE OF Sand or silt flow MOVEMENT 3 m (10 ft) per second Rapid to 0.3 m (1 ft) 1.5 m (5 ft) 1.5 m (5 ft) 1.5 m (5 ft) .3 m (1 ft) MAINLY LARGE ROCK FRAGMENTS MOSTLY PLASTIC





possible.

capture all terraces if

level and

BF

Note: ex beyond B

Table 23 Mass Movement

- 1. Fall
- 2. Topple
- 3. Translational Slide
- 4. Rotational Slide
- 5. Lateral Spread
- 6. Flow

Version #3 Last edited: 04/04/2023

1×1

cm